ALEXA

Software Update Packet 6.1

USER MANUAL

Date: 9th May 2012

All rights reserved.

This document is provided under a license agreement containing restrictions on use and disclosure and is also protected by copyright law.

Due to continued product development this information may change without notice. The information and intellectual property contained herein is confidential between ARRI and the client and remains the exclusive property of ARRI. If you find any problems in the documentation, please report them to us in writing. ARRI does not warrant that this document is error-free.

Arnold & Richter Cine Technik
Tuerkenstr. 89
D-80799 Munich
Germany

mailto: service@arri.com
http://www.arri.com

Contents

1 Disclaimer 7

2 Scope 9

3 Introduction to ALEXA 10

3.1 About This Manual ... 13

4 ALEXA Images 13

5 Safety Instructions 16

5.1 Explanation of Warning Signs and Indications ... 16

5.2 General Safety Instructions ... 16

5.3 Specific Safety Instructions ... 17

6 General Precautions 19

6.1 Storage and Transport ... 19

6.2 Electromagnetic Interference ... 19

6.3 Condensation ... 20

7 Power Supply 21

7.1 Power Management ... 21

7.2 BAT Connector ... 22

7.3 Mains Unit NG 12/26 R ... 22

7.4 Cine-Style Batteries ... 22

7.5 Onboard Batteries ... 23

7.6 V-Lock Batteries ... 23

7.7 Gold Mount Batteries ... 25

7.8 Power Outputs ... 26

7.8.1 12 V Accessories ... 26

7.8.2 24 V Accessories ... 26

8 Installation of the Camera 27

8.1 Minimum Equipment Recommended For Operation ... 27

8.2 Tripod and Remote Heads ... 27

8.3 Electronic Viewfinder EVF-1 ... 28

8.3.1 Viewfinder Cables ... 29

8.3.2 Viewfinder Mounting Bracket ... 30

8.4 Center Camera Handle CCH-1 ... 32
8.5 Side Camera Handle SCH-1 ... 33
8.6 Bridge Plates BP-12/BP-13 ... 34
8.7 Bridge Plate adapter BPA-1 ... 35
8.8 Wedge Adapter WA-1 + Quick-Release Plate ... 35
8.9 Leveling Block LB-1 ... 35
8.10 Shoulder Pad SP-3 ... 36

9 Connectors 38
9.1 BAT ... 40
9.2 REC OUT 1 + 2 ... 40
9.3 RET/SYNC IN ... 40
9.4 MON OUT ... 40
9.5 EXT ... 40
9.6 ETHERNET ... 41
9.7 EVF ... 41
9.8 AUDIO IN ... 41
9.9 RS ... 41
9.10 12 V ... 42
9.11 TC ... 42
9.12 AUDIO OUT ... 42
9.13 SD Card ... 42
9.14 SxS Slots ... 43

10 Optics 45
10.1 Lens Adapter PL Mount LA-PL-1 (no LDS) ... 45
10.2 Lens Support ... 46

11 Camera Controls 48
11.1 Main Controls ... 48
11.1.1 Display ... 49
11.1.2 Screen Buttons ... 49
11.1.3 HOMESCREEN ... 49
11.1.3.1 Lists and User Lists ... 52
11.1.3.2 FPS ... 54
11.1.3.3 AUDIO ... 58
11.1.3.4 SHUTTER ... 60
11.1.3.5 EI ... 61
11.1.3.6 COLOR ... 63
11.1.3.7 WB ... 65
11.1.4 Function Buttons ... 67

11.1.4.1 TC (Time Code) 68
11.1.4.2 INFO 70
11.1.4.3 USER 73
11.1.4.4 PLAY 76
11.1.5 Menu 79
11.1.5.1 Recording 79
11.1.5.2 Monitoring 85
11.1.5.3 Project 90
11.1.5.4 System 92
11.1.5.5 Frame grabs 99
11.1.5.6 User Setups 100
11.2 Operator controls 101
11.3 EVF Controls 102
11.3.1 Viewfinder EVF menu 102
11.3.2 Viewfinder CAM menu 103

12 Operation of The Camera 104
12.1 Recording 104
12.1.1 Internal recording 104
12.1.2 External recording 111
12.1.3 Parallel recording 113
12.1.4 High Speed recording 113
12.2 Monitoring 114
12.2.1 Frame Lines 114
12.3 Using Time Code 117
12.4 Syncing the Sensors of Two Cameras 118
12.5 Syncing the Settings of Two Cameras 119
12.6 Sensor modes 16:9 and 4:3 121

13 ALEXA Plus 123
13.1 General Description 123
13.2 Optics 124
13.2.1 Lens Adapter PL-Mount LA-PL-2 (with LDS) 125
13.3 Radio System 126
13.4 Wireless Remote System 127
13.4.1 Lens Motors 127
13.4.2 Hand Units 129

13.5 Lens Data Display LDD-FP 130
13.6 Plus Camera Controls 131

14 ALEXA Plus 4:3 136

15 ALEXA Studio 138
15.1 General Description 138
15.2 ALEXA Studio Images 139
15.3 Optics 141
15.3.1 Electronic Mirror Shutter 142
15.3.2 Lens Adapter PL Mount LA-PL-2 (with LDS) 142
15.3.3 Optical Viewfinder 143
15.3.4 ND Filter 151
15.4 Studio Camera Controls 152
15.5 4:3 Mode 155
15.6 Licensed Features 156

16 ALEXA M 157
16.1 General Description 157
16.2 ALEXA M Images 158
16.3 ALEXA M Camera Head 163
16.3.1 CCH-2 163
16.4 ALEXA M Camera Backend 163
16.5 Fibre Connection 164
16.6 4:3 mode 166
16.7 Licensed Features 167
16.8 Lens Data System 167

17 RCU-4 168

18 Index 169

Appendix 173
A.1 Appendix 174
A.2 Connector Pin Outs 179
A.3 False Color Display 184
A.4 Infos and Warnings 185
A.5 Dimensions, Weights and Menu Structure Trees 193

1 Disclaimer

Before using the products described in this manual be sure to read and understand all respective instruction.

The ARRI ALEXA is only available to commercial customers. The customer grants by utilization that the ARRI ALEXA or other components of the system are deployed for commercial use. Otherwise the customer has the obligation to contact ARRI preceding the utilization.

While ARRI endeavors to enhance the quality, reliability and safety of their products, customers agree and acknowledge that the possibility of defects thereof cannot be eliminated entirely. To minimize risk of damage to property or injury (including death) to persons arising from defects in the products, customers must incorporate sufficient safety measures in their work with the system and have to heed the stated canonic use.

ARRI or its subsidiaries do not assume any responsibility for incurred losses due to improper handling or configuration of the camera or other system components, due to sensor contamination, occurrence of dead or defective pixels, defective signal connections or incompatibilities with third party recording devices.

ARRI assumes no responsibility for any errors that may appear in this document. The information is subject to change without notice.

For product specification changes since this manual was published, refer to the latest publications of ARRI data sheets or data books, etc., for the most up-to-date specifications. Not all products and/or types are available in every country. Please check with an ARRI sales representative for availability and additional information.

Neither ARRI nor its subsidiaries assume any liability for infringement of patents, copyrights or other intellectual property rights of third parties by or arising from the use of ARRI products or any other liability arising from the use of such products. No license, express, implied or otherwise, is granted under any patents, copyrights or other intellectual property right of ARRI or others.

ARRI or its subsidiaries expressly exclude any liability, warranty, demand or other obligation for any claim, representation, or cause, or action, or whatsoever, express or implied, whether in contract or tort, including negligence, or incorporated in terms and conditions, whether by statue, law or otherwise. In no event shall ARRI or its subsidiaries be liable for or have a remedy for recovery of any special, direct, indirect, incidental, or consequential damages, including, but not limited to lost profits, lost savings, lost revenues or economic loss of any kind or for any claim by third party, downtime, good-will, damage to or replacement of equipment or property, any cost or recovering of any material or goods associated with the assembly or use of our products, or any other damages or injury of the persons and so on or under any other legal theory.

In the case one or all of the foregoing clauses are not allowed by applicable law, the fullest extent permissible clauses by applicable law are validated.

ARRI is a registered trademark of Arnold & Richter Cine Technik GmbH & Co Betriebs KG.

Note: This product and the accessories recommended by the manufacturer fulfill the specifications of the European Directive 2004/108/EC (15th December 2004).

The ALEXA viewfinder EVF-1 contains proprietary technology owned by Fourth Dimension Displays Limited and licensed by ARRI.

This product contains licensed technology from Linotype.

Quicktime and Quicktime logo are trademarks or registered trademarks of Apple Computer, Inc., used under license therefrom.

Apple ProRes 422 (Proxy), Apple ProRes 422 (Lt), Apple ProRes 422, Apple ProRes 422(Hq), Apple ProRes 4444 and the ProRes logo are trademarks or registered trademarks of Apple Computer, Inc., used under license therefrom.

SxS and SXS are trademarks of SONY corporation.

mkdosfs

Portions © 1998, Robert Nordier. All Rights Reserved.

© 1998, Robert Nordier. All rights reserved.

Redistribution and use in source and binary forms, with or without modification, are permitted provided that the following conditions are met:

Redistributions of source code must retain the above copyright notice, this list of conditions and the following disclaimer.

Redistributions in binary form must reproduce the above copyright notice, this list of conditions and the following disclaimer in the documentation and/or other materials provided with the distribution.

THIS SOFTWARE IS PROVIDED BY THE AUTHOR(S) “AS IS” AND ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE ARE DISCLAIMED. IN NO EVENT SHALL THE AUTHOR(S) BE LIABLE FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION) HOWEVER CAUSED AND ON ANY THEORY OF LIABILITY, WHETHER IN CONTRACT, STRICT LIABILITY, OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

This product meets CE regulations.

2 Scope

This instruction manual applies to the following hardware, software and firmware versions:

ARRI ALEXA, ARRI ALEXA PLUS, ARRI ALEXA PLUS 4:3, ALEXA M camera with ARRI EVF-1 electronic viewfinder ;

ARRI ALEXA Studio with optical viewfinder or ARRI-EVF-1 electronic viewfinder:

- Camera software update packet (SUP): 6.1
- EVF-1 software packet: 1.27

Document revision history

SUP	ID	drawing	release/ revision	date
2.1	K5.72550.0	2031-00-00-00-99	FG5445	29th Nov 2010
3.0	K5.72550.0	2031-00-00-00-99	K7741	11th Feb 2011
3.1	K5.72550.0	2031-00-00-00-99-B	K7776	04th Apr 2011
3.1	K5.72550.0	2031-00-00-00-99-C	K7781	07th Apr 2011
4.0	K5.72550.0	2031-00-00-00-99-D	K7817	05th Jul 2011
4.0.1	K5.72550.0	2031-00-00-00-99-E	K7845	24th Aug 2011
5.0	K5.72550.0	2031-00-00-00-99-F	K7874	16th Nov 2011
5.0 + 5.1	K5.72550.0	2031-00-00-00-99-G	K7890	19th Dec 2011
5.0 + 5.1	K5.72550.0	2031-00-00-00-99-H	K8005	26th Jan 2011
5.1 + 6.0	K5.72550.0	2031-00-00-00-99-I	K8021	12th Feb 2012
6.1	K5.72550.0	2031-00-00-00-99-J	K8071	14th May 2012

3 Introduction to ALEXA

ALEXA is a 35 format film-style digital camera made by ARRI, the world leader in professional cinematographic imaging. It combines leading edge digital technology with film camera features that have been refined over more than 90 years of ARRIs history. The result is a camera that allows cinematographers with a film background to shoot digitally without the need for a extensive training.

People who are used to shoot digitally will experience a camera like they never did before, providing more powerful features than in any other camera available today.

Handling

The camera is a true ARRI. It has a high-precision integrated housing with an ergonomic design. It is rugged, reliable, flexible and sealed to make it splash-proof. It also has mounting points for accessories, as ALEXA integrates well with existing ARRI accessories. In addition, a new range of accessories specifically designed for ALEXA is available.

Operation

ALEXA features a unique user interface, designed to make camera operation easier than ever, while giving easy access to a large number of controls.

There are three different control interfaces:

- The main user interface on the right side gives access to every camera parameter through a graphical display and a button panel.
- The operator user interface on the left side for basic control, adjustable to the operator's individual needs by supplying assignable buttons in addition to function buttons.
- The viewfinder user interface for adjusting the most important image parameters with buttons on the viewfinder and the interface graphics overlayed to the viewfinder image.

Power management

The camera accepts any input voltage from 10.5-34 V DC. Different power sources can be connected to the camera simultaneously. The camera's power management ensures that the power source with the highest voltage level is used. Power sources are hot-swappable to minimize the risk of sudden power loss.

ALEV III sensor

The ALEV III sensor has a horizontal pixel count of 3.5K resulting in true 2K resolution. It covers the full Super-35 format and it provides a latitude of 14 stops and a base sensitivity of 800 ASA.

The sensor temperature is kept stable by a Peltier element to ensure optimum image quality under all operating conditions.

AIT - ARRI Imaging Technology

ARRI imaging technology ensures the most organic, film-like image quality of any digital camera with natural color rendition and pleasing skin tones.

Thermal concept

The camera electronics are fully sealed to protect them from dirt and moisture. Camera heat is transported via heat pipes to a radiator which is cooled by a fan. The fan itself is very silent, so the camera noise level is below 20 dB (A)* - this is the same as with ARRI sync-sound film cameras. If the fan noise level starts to increase due to fan aging, the fan can be swapped in a matter of minutes by a trained technician.

*at 24 fps and ambient temperature < 25°C

EVF-1 electronic viewfinder

ARRI is redefining electronic viewfinders with LED lighting, high resolution and a viewing experience that comes as close to an optical viewfinder as possible.

Internal recording

ALEXA can internally record Quicktime movie clips with Apple ProRes™ or MXF files with AVID DNxHD codecs to Sony **SxS PRO** cards. The cards deliver high data rates and are very robust. ProRes™ can be natively edited in Apple FinalCutPro, eliminating the need to transcode. ProRes 422 (HQ) and ProRes 4444 deliver visually lossless compressed images with a color depth of 10 bit for ProRes 422 and 12 bit for ProRes 4444.

DNxHD can be natively edited in AVID MediaComposer without transcoding.

Quicktime movie clips and and MXF files can be played back in the camera with output on REC OUT, MON OUT and the electronic viewfinder.

Audio recording

Analog 2-channel audio can be recorded as 24 bit 48 kHz PCM in the Quicktimes, as well as embedded to the HD-SDI signals.

Licensed features

By adding license keys, new camera features can be enabled that go beyond the initial camera specification.

High speed image capture

In Regular Speed mode, ALEXA has a frame rate range from 0.75 to 60 fps. By adding a license key for High Speed mode, the frame rate range of the camera can be extended up to 120 fps.

3.1 About This Manual

It is recommended that all users of the ALEXA camera read the manual front to back prior to the first usage. The manual's structure also provides quick access for reference to experienced users. All directions are given from an operator's point of view.

- Images: give a quick overview of the camera.
- Safety instructions / general precautions: very important - do not skip this part.
- Power supply: overview how the camera is supplied with power.
- Installation of the camera: information on camera mechanics.
- Connectors: what goes into the camera and what comes out.
- Optics: how to get a good image into the camera.
- Camera controls: how to set up the camera.
- Operation of the camera: gives examples and recommendations on camera operation.

4 ALEXA Images

Figure 1: ALEXA right

Figure 2: ALEXA left

Figure 3: ALEXA top



Figure 4: ALEXA bottom

Figure 5: ALEXA front

Figure 6: ALEXA back

5 Safety Instructions

Any violation of these safety instructions or non-observance of personal care could cause serious injuries (including death) to users and affiliates and damage to the equipment or other objects.

5.1 Explanation of Warning Signs and Indications

Indicates a possible risk of injury or damage to the equipment

Indicates the risk of electric shock or fire danger that could result in injury or damage to the equipment.

Note: Indicates further information or information from other instruction manuals

5.2 General Safety Instructions

- Always follow these instructions to ensure against injury to yourself or others and damage to the system or other objects.
- This safety information is in addition to the product specific operating instructions in general and must be strictly observed for safety reasons.
- Read and understand all safety and operating instructions before you operate or install the system!
- Retain all safety and operating instructions for future reference.
- Heed all warnings on the system and in the safety and operating instructions before you operate or install the system. Follow all installation and operating instructions.
- Do not use accessories or attachments that are not recommended by ARRI, as they may cause hazards and invalidate the warranty!
- Do not attempt to repair any part of the system! Repairs must only be carried out by authorized ARRI Service Centers.

5.3 Specific Safety Instructions

- Do not remove any safety measures from the system!
- Do not operate the system in areas with humidity above operating levels or expose it to water or moisture!
- Do not cover the fan openings at the camera back top and bottom!
- Do not subject the system to severe shocks!
- Do not place the system on an unstable trolley/hand truck, stand, tripod, bracket, table or any other unstable support device! The system may fall, causing serious personal injury and damage to the system or other objects.
- Operate the system using only the type of power source indicated in the manual! Unplug the power cable by gripping the power plug, not the cable!
- Never insert objects of any kind into any part of the system if not clearly qualified for the task in the manual, as objects may touch dangerous voltage points or short out parts! This could cause fire or electrical shock.
- Unplug the system from the power outlet before opening any part of the system or before making any changes to the system, especially the attaching or removing of cables!
- Do not use solvents to clean!
- Do not remove any stickers or paint marked screws!
- Always place a lens or a protective cap in the lens mount receptacle!
- Never run a camera with a mirror shutter without a lens or a protective cap in the lens mount receptable!
- Changing camera lenses should be done in a dry and dust-free environment. If this is not possible, take extra care that no dust enters the camera while the lens is off!
- When no lens is attached to the camera, immediately place the protective on the lens mount to avoid contamination of the sensor cover glass!
- After changing lenses, always perform a dust check to make sure no dust has settled on the sensor cover glass!
- Clean optical lens surfaces only with a lens brush or a clean lens cloth. in cases of solid dirt or grease, moisten a lens cloth with pure alcohol. Discard contaminated lens cloth after use! Never attempt to clean a lens brush with your fingers!
- NEVER USE CANS WITH COMPRESSED AIR OR GAS TO BLOW OFF THE DUST! This can severely damage optical elements.
- If the sensor cover glass has been contaminated by solid dirt or grease, special optical cleaning kits should be used for dirt removal under very high care! If the contamination cannot be removed, the camera should be taken to an ARRI service center for cleaning.

- THE USE OF METHANOL TO CLEAN OPTICAL SURFACES IS NOT RECOMMENDED!
- NEVER USE ACETONE TO CLEAN OPTICAL SURFACES!
- NEVER TRY TO REMOVE THE SENSOR COVER GLASS!
- DO NOT POINT THE CAMERA INTO DIRECT SUNLIGHT, VERY BRIGHT LIGHT SOURCES, OR HIGH-ENERGY LIGHT SOURCES (e.g. laser beams)! This may cause permanent damage to the camera image sensor.
- DO NOT POINT THE VIEWFINDER INTO DIRECT SUNLIGHT, VERY BRIGHT LIGHT SOURCES, OR HIGH-ENERGY LIGHT SOURCES (e.g. laser beams)! This may cause permanent damage to the viewfinder display and optical elements.

6 General Precautions

6.1 Storage and Transport

- To prevent damage to the optical filters and the sensor, a protective cap must be on the lens mount receptacle while no lens is attached.
- All cables have to be unplugged from the camera when it is transported or stored inside a camera case.
- Do not store the camera in places where it is subject to extreme temperatures, direct sunlight, high humidity, severe vibration, or near strong magnetic fields.

6.2 Electromagnetic Interference

ALEXA meets EC regulations by fulfilling the specifications of the European Directive 2004/108/EC (15th December 2004).

This equipment has been tested and found to comply with the limits for a Class A digital device, pursuant to part 15 of the FCC Rules. These limits are designed to provide reasonable protection against harmful interference when the equipment is operated in a commercial environment. This equipment generates, uses, and can radiate radio frequency energy and, if not installed and used in accordance with the instruction manual, may cause harmful interference to radio communications. Operation of this equipment in a residential area is likely to cause harmful interference in which case the user will be required to correct the interference at his own expense.

Changes or modifications not expressly approved by the party responsible for compliance could void the user's authority to operate the equipment.

Complies with the canadian ICES-003 Class A specifications. Cet appareil numérique de la Classe A est conformé à la norme NMB-003 du Canada.

This device complies with RSS 210 of Industry Canada. This Class A device meets all the requirements of the Canadian interference-causing equipment regulation. Cet appareil numérique de la Class A respecte toutes les exigences du Réglement sur le matérial brouilleur du Canada.

6.3 Condensation

When moving the camera from a cool to a warm location or when the camera is used in a damp environment, condensation may form inside the lens compartment, on the sensor cover glass, between sensor and its cover glass, and on internal or external electrical connections.

- Operating the camera in these conditions may result in personal injury or damage to the equipment!

Condensation on the optical components may have a visible effect on the output images. To reduce the risk of condensation:

- Find a warmer storage location.
- Attach the ARRI air-drying cartridge (silica bottle) to the PL-Mount of the camera during storage (NOT during transport!)
- If camera needs to be stored in a place that is considerably cooler than the location where it will be used, consider keeping the camera powered from a mains unit in addition to using the air-drying cartridge.
- In ambient temperatures above 30°C/86°F and/or humidity above 60%, always attach the air-drying cartridge to the PL-Mount of the camera when not in use. This not only applies to storage, but also to shooting breaks and situations when the camera remains without an attached lens for an extended time.
- MAKE SURE THE SILICA BOTTLE IS SECURELY FASTENED. UNDER NO CIRCUMSTANCES SPILL SILICA INTO THE LENS COMPARTMENT!

7 Power Supply

- Only use recommended power supply solutions.
- Manipulation of power supplies can result in severe damage to the equipment and humans, including death.

ALEXA accepts an input voltage range from 10.5 to 34 V DC. The camera can be powered through the BAT connector or can be equipped with battery adapters accepting V-Lock or Gold Mount batteries.

The power supply should deliver an output of more than 90 W to power the camera sufficiently. The power draw of the camera in basic configuration is about 85 W.

A 12-15 V battery should have at least 6 A maximum output current.

Note: when powering accessories through the camera, the power draw of the camera is increased by the amount of power drawn by the accessories.

7.1 Power Management

When using the BAT connector and one or more onboard battery adapters simultaneously, the camera power management ensures that the power source with the highest voltage level is used. When the voltage level of one power source drops below the level of the other, or a power source is disconnected from the camera, the power management automatically switches to the other power source, avoiding shutdown of the system.

So as an example, one could use a 12 V onboard battery as backup for the main 24 V battery, or power the camera from the 24 V battery while on a tripod and use the 12 V battery for fast switching to handheld mode by just unplugging the power cable.

When using two onboard battery adapters with batteries in parallel (one on top and one on the back), they are treated as one source by the camera. This allows combining small batteries with less load per item into one strong power source.

7.2 BAT Connector

The BAT connector of ALEXA is a Fischer 2-pin socket located on the bottom back of the camera right side.

The socket accepts power cables KC-20S and KC-29S. The cables can either be connected to the mains unit NG 12/26R or to 24V Cine-style batteries with three-pin XLR outputs.

Figure 7: BAT connector

7.3 Mains Unit NG 12/26 R

Use of the mains unit is recommended for shooting in the studio and when using electronic accessories with high power consumption.

- First check that the correct mains voltage is set on the mains unit (fuse on back of unit).
- Connect the mains unit to AC mains power.
- Ensure that the camera power is turned off.
- Set the voltage switch on the mains unit to 26 V.

Plug the battery cable KC-20S or KC-29S (spiral cable) into the power supply socket on the camera and into the 26 V socket on the mains unit.

Note: The NG 12/24 R was the original design that provided 12 & 24 volts output – it was superseded by the NG 12/26 R, which outputs 12 & 26 volts. The NG 12/24 R can easily be upgraded to NG 12/26 R specification at an ARRI service center.

7.4 Cine-Style Batteries

Any Cine-style battery with level of 24 V and a three-pin XLR out can be used to power the camera through a KC-20S or a KC-29S.

Available from ARRI is the battery CINE VCLX/2 battery (280 Wh) with charger.

To connect the battery to the camera:

- Ensure that the main switch on the camera is off.
- Plug the battery cable KC-20S or KC-29S (spiral cable) into the power supply socket on the camera and the battery 28 V output socket.

Note: When the battery voltage drops below the warning level, the BAT1 level in the camera display will start flashing. A white "i" will appear, signaling more information is available on the INFO screen.

Note: For more information on setting the low battery warning level, see *Menu>System>Power* (on page 93).

Charging the battery

- Connect the charger to AC mains power.
- Plug the charger cable into the charge input socket of the battery.
- Once charged, batteries may be kept on the charger until required.

Note: For more information on CINE VCLX/2 battery and charger, please check the corresponding manual.

7.5 Onboard Batteries

The camera can be equipped with adapters for either V-Lock or Gold Mount video-style batteries.

Four different adapters are available:

- BAB-G: Back-mount adapter Gold Mount batteries
- BAB-V: Back-mount adapter V-Lock batteries
- BAT-G: Top-mount adapter Gold Mount batteries
- BAT-V: Top-mount adapter V-Lock batteries

Note: Adapters must be installed by a trained technician!

7.6 V-Lock Batteries

V-Lock batteries are available from a number of manufacturers. Some of these batteries are able to transmit information on their remaining capacity to the camera. ALEXA displays the remaining capacity in percent on the Homescreen of the camera display. For these batteries, the user does not need to set the battery warning level due to the communication of camera and battery. Currently, batteries by ID-X, Bebop or any battery using the TI-protocol for battery communication will have their capacity displayed as percentage in the camera.

Attaching the battery to the adapter

- Place the battery with the V-shaped wedge into the adapter so that the wedge sits right above its counterpart of the mount.
- Move the battery downwards until you hear a snap.
- Make sure it is connected correctly and sits tight.

Releasing the battery

- When facing the battery, press the button located on the mount on the left side. Some batteries have an additional top-release mechanism.
- Move the battery upwards and remove it.

Figure 8: ALEXA with BAB-V and V-Mount battery

Note: Not all V-Lock batteries deliver enough power to supply the camera. We recommend to not use any batteries with a capacity of less than 90 Wh to prevent damage to the battery and unpredictable camera behavior. Any camera-battery combination should be tested prior to use, especially when accessories are powered through the camera.

7.7 Gold Mount Batteries

Gold Mount is the battery mounting system of Anton Bauer batteries. The batteries transmit information on their remaining capacity to the camera. ALEXA displays the remaining capacity in percent on the Homescreen of the camera display. For Gold Mount batteries, the user does not need to set the battery warning level due to the communication of camera and battery.

Attaching the battery to the adapter

- Place the battery with the three pins into the adapter so that the pins sit in the corresponding holes of the mount.
- Move the battery to the right until you hear a snap.
- Make sure it is connected correctly and sits tight.

Releasing the battery

- When facing the battery, move the lever located on the left side of the mount down.
- Move the battery left, then pull it towards you and remove it.

Figure 9: Camera with BAB-G and a Gold Mount battery

Note: Not all Gold Mount batteries deliver enough power to supply the camera. We recommend to not use any batteries with a capacity of less than 90 Wh to prevent

damage to the battery and unpredictable camera behavior. Any camera-battery combination should be tested prior to use, especially when accessories are powered through the camera.

7.8 Power Outputs

The camera has three power outputs for accessories, 2x 24 V and 1x 12 V.

Figure 10: 24 V outputs (RS) and 12 V output

7.8.1 12 V Accessories

The 12 V output is located on the right side of the camera and has a 2-pin LEMO connector. It is limited to 12 V and can supply a device with a current of up to 2.2 A, depending on the camera power supply.

7.8.2 24 V Accessories

Two RS outputs are located on the right side of the camera. They have a 3-pin Fischer connector. They can supply two devices with a combined load of up to 2.2 A (shared with the EXT connector power out), depending on the camera power supply. When the camera is powered from a source with a voltage below 24 V, they output 24 V. If the camera's power source is supplying more than 24 V, this voltage level is also present on the RS outputs.

Besides powering accessories, these sockets can also be used to send a remote start+stop signal to the camera.

8 Installation of the Camera

8.1 Minimum Equipment Recommended For Operation

- ARRI ALEXA camera body including **SxS** module and Lens Adapter PL mount without LDS (LA-PL-1)
- EVF-1 Electronic Viewfinder
- VMB-1 Viewfinder Mounting Bracket
- KC 150-S Viewfinder Cable short 0.35m/1.2ft
- CCH-1 Center Camera Handle
- BP-12 Bridge Plate with base plate, or BPA-1 with BP-5/BP-8 Bridge Plate and base plate, or WA-1 Wedge Adapter and Quick Release HD Baseplate
- SD card
- Compatible power supply
- Sony **SxS PRO** card for recording

8.2 Tripod and Remote Heads

Tripod and remote heads used with ALEXA have to provide enough load capacity to support the camera and attached accessories. The table to the right shows the camera weight for different components.

Note: Check for the payload of remote heads and cranes.

In applications where the camera mount is subject to high forces (e.g. car or helicopter mounts) the camera must be additionally secured with retaining cords. All fastening screws must be tightened firmly with an appropriate screwdriver (not with the commonly used coin!).

Camera weight	lbs	kg
ARRI ALEXA incl. **SxS** module, EVF-1, VMB-1, CCH-1, KC-150S	16.85	7.65
ALEXA camera body including **SxS** module	13.79	6.26
Electronic Viewfinder EVF-1	1.65	0.75
Viewfinder Mounting Bracket VMB-1	0.55	0.25

Viewfinder Cable short KC-150S	0.26	0.12
Center Camera Handle CCH-1	0.60	0.27

8.3 Electronic Viewfinder EVF-1

The EVF-1 employs an LCOS imaging device together with a temperature stabilized LED light source to provide an accurate and bright view of the sensor image under all operating conditions. The viewfinder is calibrated to match the image of the camera's HD outputs.

The image area of the EVF-1 has a size of 1280x720 pixels. 32 additional pixels each above and below the image provide two status bars for displaying camera information. The EVF-1 can display the 10% surround view area of the sensor to help the operator track unwanted elements before they enter the recorded image area. Focus can be checked by temporarily zooming into the image center with a magnification of 2.25x. The low-latency interface of the EVF-1 has a delay of less than 1 frame.

The viewfinder is connected to the camera with the mounting bracket VMB-1.

Figure 11: Camera with EVF-1

Note: Do not point the viewfinder eyepiece at direct sunlight or bright light sources, as this could damage the LCOS imaging device. If possible, cover the eyepiece when not in use to prevent any damage.

8.3.1 Viewfinder Cables

The viewfinder cables are unidirectional with a male plug to connect to the camera and a female plug to connect to the viewfinder.

Cables are available in the following lengths:

Model	Length (m / ft)	Purpose
KC-150-S	0.35 / 1.2	For use of EVF-1 on camera left side in handheld mode
KC-151-S	0.65 / 2.1	For use of EVF-1 on camera right side or when using Viewfinder Extension Bracket VEB-1
KC-152-S	2.00 / 6.6	Longest possible length for use with specialty rigs

Figure 12: EVF cables: KC-150S (center), KC-151S (middle), KC-152S (outer)

8.3.2 Viewfinder Mounting Bracket

The viewfinder mounting bracket VMB-1 / VMB-2 is attached to the camera with two 3mm Allen screws at the very front of the camera top. The viewfinder is attached to the mounting bracket by sliding the dove tail into the receptacle of the mounting bracket and then closing the lever on the viewfinder.

The position of the viewfinder can be adjusted by loosening the levers of the mounting bracket, adjusting the position as desired and closing the levers.

It can be flipped over by first unscrewing the cap at the end of the side adjusting rod, then removing the rod itself and inserting it into its mount from the other side. Then reattach the cap.

Note: Camera right operation is not possible with the standard EVF cable KC-150-S. Instead, the longer cable KC-151-S is needed.

Figure 13: VMB-1 on camera

The viewfinder extension bracket VEB-1 extends the mounting point of the EVF further back. It can be attached to a tripod head for use with geared heads or greater comfort when using fluid heads. The VEB-1 has a standard attachment point for the ARRI eyepiece leveler EL-3. When using the VEB-1 with an eyepiece leveler, loosening the friction where the VEB-1 and the VMB-1 / VMB-2 are joined is critical as tiliting can the damage the friction setting.

Figure 14: EVF extension bracket

Figure 15: Camera with EVF-1 on extension and cable KC-151S

8.4 Center Camera Handle CCH-1

The Center Camera Handle CCH-1 is attached to the camera top with 3 screws, two at the front and one at the back. Make sure the screws are well tightened with a 3mm Allen key.

Figure 16: Camera with CCH-1, side view

The handle extension block HEB-2 mounts to the front end of the CCH-1 and adds one more focus hook to the camera in a high position, so the tape measure clears the matte box.

8.5 Side Camera Handle SCH-1

The SCH-1 is used in conjunction with a BAT-V or BAT-G battery top mounting adapter, or with third-party onboard recorders. It is attached to the camera with 3 screws, two at the front and one at the back. Make sure the screws are tightened firmly with a 3 mm Allen key.

If a tall battery or a tall third-party onboard recorder is used, the adjustable center grip of the SCH-1 can be replaced by the taller Adjustable Center Grip Tall (ACG-2).

Figure 17: SCH-1

Figure 18: Camera with SCH-1, side view

8.6 Bridge Plates BP-12/BP-13

The bridge plate BP-12 for 19 mm studio rods has been newly developed for ALEXA. It mounts directly to the camera housing with two screws and ensures that support rods, matte boxes and follow focus units are positioned properly in regards to the optical center of the camera, just like all other ARRI cameras.



The bridge plate BP-13 is equivalent to the BP-12, but for 15 mm studio rods.

Note: Make sure bridge plates are tightened firmly with a screwdriver, not the commonly used coin!

8.7 Bridge Plate adapter BPA-1

The bridge plate adapter BPA-1 can be used to attach a BP-3/BP-5/BP-8/BP-9 to ALEXA. First attach the BPA-1 to the camera with the two screws. Then attach the bridge plate to the adaptor with its two screws. Make sure the screws are tightened firmly with a screwdriver.

8.8 Wedge Adapter WA-1 + Quick-Release Plate

The WA-1 can be mounted at the same position as a bridge plate. It has a dove tail that slides into the counter part of a quick-release plate, like the ARRI QR-HD-1. The quick-release plate has a pin at its back, which fits into the pin receptacle at the back of the camera base.

Figure 19: ARRI QR-HD-1

8.9 Leveling Block LB-1

The leveling block LB-1 attaches to the bottom of the ALEXA back foot. It prevents the camera from resting on a back mounted battery when a bridge plate is attached and the camera is placed on a flat surface.

It is mounted by inserting its top lid into the pin receptacle on the end of the shoulder arc in the camera base. Twist the knob clockwise to tighten.

Figure 20: Leveling Block LB-1

8.10 Shoulder Pad SP-3

The camera base has an integrated arch to fit to the operator's shoulder. For extended handheld shoots, the newly designed shoulder pad SP-3 can be attached to the base of the camera with velcro.

Note: The SP-3 can only be used with a BP-12 and 19 mm rods or with 15 mm rods and a WA-1+quick-release base plate. When using the BPA-1 with a BP-5/BP-8, the bridge plate has to be removed prior to attaching the SP-3.



Figure 21: SP-3 shoulder pad

Figure 22: SP-3 below camera

9 Connectors

Camera back

Figure 23: Connectors at back

From top to bottom: MON OUT, RET/SYNC IN, EXT, REC OUT 1&2, BAT, ETHERNET

Camera right

Figure 24: Connectors on right side

From left to right, top to bottom: 2x RS (24 V) out, AUDIO OUT, TC, 12V out, AUDIO IN, SD CARD (camera bottom)

Camera left

Figure 25: Camera left: SxS slots

Top to bottom: SxS slot 1, SxS slot 2

Camera front

Figure 26: Camera front connector

EVF connector

9.1 BAT

The BAT connector can be used to power the camera from an external power source with cables KC-20S and KC-29S.

It is located on the camera back lower right.

9.2 REC OUT 1 + 2

The REC OUT consists of two BNC plugs capable of carrying 1920x1080 1.5G or 3G HD-SDI signals with frame rates from 23.976 to 60 fps according to SMPTE standards 274M, 292M, 372M and 425M (Level B). In addition, it outputs ARRIRAW in a proprietary format that is supported by a range of 3rd party recorders. RGB 444 at frame rates of 48, 50, 59.94 and 60 fps is output in a proprietary format utilizing two 3G connections. The signal format can be changed in the camera menu.

The connectors are located on the camera back mid right.

9.3 RET/SYNC IN

Via the RET connector a return signal from another image source can be fed into the camera for displaying on EVF and/or MON OUT. The signal must be a 1920x1080 422 1.5G single link according to SMPTE 274M and 292M. The output routing of the RET in signal can be set in the camera menu.

It is located on the camera back mid right.

9.4 MON OUT

The MON OUT is a single BNC connector capable of carrying a 1920x1080 422 YCbCr 1.5G HD-SDI signal with frame rates of 23.976, 24, 25, 29.97 or 30 fps according to SMPTE standards 274M and 292M. The signal format can be changed in the camera menu.

It is located on the camera back upper right.

9.5 EXT

The EXT connector is a multi-pin accessory connector. It carries signals for communication with various accessories and 24V power. The maximum power output is 2.2A, shared with the RS outputs.

Cables are currently available for:

- Connecting a UMC-3 remote motor controller

(model UMC Connection Cable (0.80m/2.6ft) K-UMC3-ALEXA)

- Connecting two ALEXA cameras for synchronized operation
  (model EXT to EXT Cable (2.00m/6.6ft) KC 155-S)

The connector is located on the camera back mid right.

9.6 ETHERNET

Regular ethernet connectors neither deliver power nor the durability and reliability required by ARRI, so ALEXA uses a 10-pin LEMO connector. A special cable, available from ARRI (model KC-153-S), is required to connect the Ethernet socket to a standard RJ-45 Ethernet socket.

The ethernet port can be used to operate two ALEXA cameras with synced settings by connecting the cameras with cable KC 156-S, or to connect and RCU-4 to the camera.

The ethernet connector can output 24 V with 1.2 A power.

It is located on the camera back lower right.

9.7 EVF

The EVF connector connects the camera to an EVF-1 electronic viewfinder. The signals on this connector are proprietary and can only be used to drive an EVF-1. This proprietary signal assures very low latency for the viewfinder image.

It is located on the camera front lower left.

9.8 AUDIO IN

2-channel analog line level audio can be fed to the camera via the 5-pin XLR connector located on the front right side of the camera.

The audio signal is A/D-converted to 24 bit 48 kHz PCM.

9.9 RS

The two RS connectors supply external accessories with at least 24 V power and combined load of up to 2.2 A (shared with the EXT connector power out). The sockets also accept an ARRI remote start/stop trigger button.

They are located on the camera right lower front.

9.10 12 V

The 12 V connector supplies an external accessory with 12 V power and up to 2.2 A current.

It is located on the camera right lower front.

9.11 TC

The TC connector is a 5pin LEMO socket. It accepts and distributes LTC (Longitudinal Time Code) signals.

It can be used to

- Jam sync the camera time code to a Clockit, TC Slate or another camera
- Transmit the camera's time code to a Clockit, TC Slate or another camera
- Tune the camera crystal oscillator's frequency with an Ambient ACC Clockit Controller

It is located on the camera right lower front.

9.12 AUDIO OUT

The AUDIO OUT is a 3.5mm TRS connector (headphone jack), which outputs the audio fed to the 5-pin XLR connector with a maximum power of 2.5 dBm.

It is located on the camera right lower front.

Note: Do not connect a headphone to the camera during recording. Connecting a headphone to the camera can cause a short audio signal interruption due to static electricity.

9.13 SD Card

The SD card slot is located at the bottom on the camera right side middle. Most SD or SDHC card with a capacity of up to 4 GB can be used. The card should be pre-formatted with a FAT or FAT32 file system. The slot is protected from dirt and rain by a slider door. Insert the SD card according to the drawing on the camera housing.

Note: Always keep the slider door closed during operation to prevent dirt and moisture from entering the camera.

On the SD card, the folder structure presented in the following example should be created by the user prior to first use of the card.



Figure 27: Folder structure required for SD card

An unformatted SD card can be formatted with the camera. Go to MENU>System>SD card>Format + prepare SD card. A screen will appear and ask for confirmation of the format operation through a double press of the two lower screen buttons. After formatting the card, the camera automatically creates the required folder structure.

Note: Formatting the SD card will irreversibly remove all data on the SD card.

The correct folder structure can be created by the camera. Go to MENU>System>SD card>Prepare SD card. The camera will create all missing folders without deleting any data on the SD card.

Firmware update files are recognized by the camera anywhere within the structure, but are still recommended to be placed in the Firmware folder.

9.14 SxS Slots

On the camera's left side are two **SxS PRO** card slots. They are behind a door that can be opened by pulling the top lid backwards. The door opens towards the camera housing for permanent accessability even in tight spaces or on special rigs. Make sure the door is always closed to prevent moisture and dirt from entering the camera!

The cards are inserted with the card contacts first and the **SxS** labeled side outwards. They have to be pushed inwards against a spring until they lock in place. Make sure the cards are locked before closing the door, or the cards could be damaged.

Note: Do not force the cards into the slots in the wrong direction. This could cause

damage to both card and camera!

To release a card, push it inwards until it is unlatched. The spring will push the card outwards. Be careful that the card does not drop out of the slot!

Cards do not have to be mounted or unmounted. They can be ejected whenever the camera is not writing to the cards. Even if cards are ejected during record, they maintain their functionality with the last take intact, except that the last second of the take is lost.

Note: If a writing process is interrupted by power loss or card eject, remove the card from the camera, copy all data from the card and format the card before using it again.

A card select button is located between the card slots. By pushing it, the currently active card can be toggled.

Each card has an LED that signals the card state to the user.

LED state	Card state
Off	No card present Card is unreadable (e.g. wrong file system) Card is inactive
Solid green	Card is selected and ready
Solid red	Card is accessed (read/write) **!DO NOT REMOVE CARD!**

Only **Sony SxS PRO** cards can be used with ALEXA. **Sony SxS-1** cards are not supported.

---

10 Optics

ALEXA is equipped with an exchangeable lens mount.

Note: Lenses must cover an image circle of at least 30 mm diameter to eliminate the risk of vignetting.

10.1 Lens Adapter PL Mount LA-PL-1 (no LDS)

The lens adapter LA-PL-1 is the standard lens mount delivered with ALEXA. It can be used to attach any modern PL-mount lens to the camera.

Attaching a lens to the camera

- Twist the bayonet ring anti-clockwise as far as it will go.
- Remove the protective lens cap.
- Insert the lens into the lens mount receptacle without catching it at the edges. One of the four slots on the lens mount must fit over the index pin in the lens mount receptacle.
- Choose a lens position that gives good readability of lens markings.
- Press the lens flat onto the lens mount receptacle.
- Twist the bayonet ring clockwise until the lens is attached.
- Make sure the lens is properly mounted.

Note: When no lens is attached to the camera, use the protective cap to avoid dust entering the lens cavity.

Note: The sophisticated design principle of the camera’s optical module delivers outstanding images with a cinematic look and feel, but also makes the imager sensitive to contamination. Dust particles that have settled on the sensor cover glass during a lens change may become visible as dark spots in the output image, similar to lint leaving marks on exposed film. The degree of this effect depends on the aperture of the lens.



Figure 28: PL mount LA-PL-1 with index pin

10.2 Lens Support

Heavy lenses may require additional lens support. This guarantees that the flange focal depth is not influenced by the lens weight and reduces stress on the lens mount.

To support a lens use 15mm studio or 19mm studio rods and a fitting lens bridge. 15mm studio rods require a bridge-plate with 15mm studio rod support (BP-3/BP-9 + BPA-1), while 19mm studio rods require a bridge-plate with 19mm studio rod support (BP-12 or BP-5/BP-8 + BPA-1).

The lens bridge LS-10 for 15 mm studio rods is mounted to the rods by pushing it on the rods from the front, while the lens bridge LS-9 for 19 mm studio rods is mounted to the rods by pushing it on them from the top.

When the bridge is in the right position on the rods, it is fixed with the screw or lever on its side. It is attached to the lens support ring with its center screw. The lever on the back of the lens bridge fixes the height of the center screw.

Figure 29: Camera with BP-12, 19mm studio rods and lens bridge

11 Camera Controls

The camera can be controlled through three different interfaces:

1	Main controls	Located on the camera right side. Consist of a 3" LCD-screen with screen buttons changing their behavior depending on the screen content, a jogwheel to navigate through menus and adjust parameters and a range of function buttons with dedicated behavior.
2	Operator controls	Located on the camera left side. Consist of three assignable function buttons plus three function buttons for quick-and-easy operator interaction.
3	EVF controls	Located on the electronic viewfinder. Allow adjustment of viewfinder parameters and the most important image related parameters.

11.1 Main Controls

The main controls can be used to set all camera parameters.

Figure 30: Main user interface

11.1.1 Display

The LCD display on the right side has a size of 3" and a resolution of 400x240 pixels. The display is back illuminated and transflective which results in exceptional contrast even in bright sunlight. When the Homescreen is displayed, the brightness of the display can quickly be adjusted by turning the jogwheel while pressing the BACK button.

A removable plastic shield protects the display from scratches and can simply be removed by pulling it off the four pins on its corners that hold it in place.

11.1.2 Screen Buttons

Six screen buttons are located above and below the display. They change their behavior depending on the screen content. The function related to each button in a screen is shown by a black label in the screen located below or above the button. Buttons without a black label have no function in that screen.

Operations that cannot be reversed and can result in the loss of data require the simultaneous pressing of two buttons to prevent accidental use.

11.1.3 HOMESCREEN



Figure 31: Homescreen

The HOMESCREEN is the default screen of the camera. It shows the most important camera parameters and gives quick access to changing them through the screen buttons. To return to the HOMESCREEN from anywhere in the camera controls, press the HOME button.

While the Homescreen is active, the display brightness can be changed with the jog wheel when the BACK button is pressed simultaneously.

Screen content

Screen Buttons

FPS	Currently set frame rate of sensor, adjustable from 0.750-60.000 fps in Regular Speed Mode, and from 60.000-120.000 fps in High Speed Mode. *Note: High Speed Mode can only be activated with valid High Speed license key installed in camera.*
AUDIO	Shows current level of audio. If Audio is set to Off, the audio input is switched off, no audio is embedded to HD-SDI outputs, and no audio tracks are recorded on the **SxS PRO** cards. The same applies if audio is disabled, which is the case if the sensor frame rate is not equal to the project fps setting (=over- or undercranking).
SHUTTER	Currently set shutter angle of sensor, adjustable from 5.0-358.0°. Shutter Angle and sensor fps determine exposure time of the sensor in seconds by the following equation: Angle/(360*Fps).
EI	Currently set exposure index rated in ASA. ALEXA has a base sensitivity of 800 ASA, the camera rating can be adjusted from 160-3200 ASA. *Note: ASA rating is identical to ISO rating.* *Note: Exposure Index is not applied to ARRIRAW signals.*
COLOR	Opens color screen, where gamma and look settings for SxS , REC OUT, MON OUT and EVF can be changed .
WB	Camera white balance. This is the color temperature of the light source the camera is currently adjusted for. Can be adjusted from 2000-11000 Kelvin in steps of 100K. In addition to the red/blue correction of the white balance, ALEXA can also compensate for a green/magenta tint. This value, called CC (after color compensation), is shown as an exponent of the WB value. Positive values are marked with a "+" and negative values with a "-". The camera can also perfom an automatic white balance upon a button press.

Center Info Bar

TC	Displays current time code including source (INT=internal or EXT=external source). Frames are not displayed, instead the timebase of the time code is shown in small digits.
MASTER	Camera is set to Ext sync: MASTER
SLAVE	Camera is set to Ext sync: SLAVE
	Settings sync is active
BAT 1	Voltage level power source present at BAT connector, or percentage of remaining capacity of

	attached battery if it transmits this information.
BAT 2	Voltage level of battery attached to onboard battery adapter, or percentage of remaining capacity of attached battery if it transmits this information.
REEL	Identifies current reel. Consists of camera index and reel counter.
CLIP	Identifies current clip. Consists of Clip index and clip counter.
DUR	Duration of current clip during recording or length of last recorded clip during standby. Shown as h:mm:ss.
CARD section	Displays capacity information of **SxS PRO** cards.
	Capacity of currently active card in minutes. Calculated for currently set framerate and codec.*
	Green capacity bar showing remaining capacity in percentage. Grey if card slot is empty. Red if card cannot be recorded. In this case, see INFO screen for more details.
<	Marks the active card.
	The camera is in standby and ready to record.
	The camera is recording.
	An error occured. Recording is not possible. Press the INFO button for more info. If nothing is shown, the camera works properly, but no **SxS PRO** card is present for recording.

---

* Note: When **SxS** recording is set to ProRes™, the value that is shown is the minimum available recording time for the currently set sensor fps and codec combination. Apple ProRes™ is a variable bit rate codec, so the actual remaining recording time depends on the image content.

When using DNxHD, the remaining recording time is accurate.

Icons

Name	Icon	Description
General Warning		Important information waiting on the INFO screen.
General Error		An error occured. Check the INFO screen for more info.

Temperature Warning		Small sensor temperature offset. Image quality might be affected slightly.
Temperature Error		Large sensor temperature offset. Image quality might be affected seriously.
Lock		Camera is locked.
SD Card		SD card present. Turns orange when card is accessed.
Grab		Still frame is currently grabbed to the SD card.
Tropical mode		Sensor is in tropical mode (=40° C sensor temperature).
Radio		WRS radio is active (ALEXA Plus only)

Note: A sensor temperature warning or error after bootup is normal until the sensor has reached its preset temperature.

11.1.3.1 Lists and User Lists

The HOMESCREEN screen buttons FPS, SHUTTER, WB (White Balance) and EI (Exposure Index) open screens with lists that contain preconfigured values for the respective setting.

Except for EI, all lists are user lists where the user can store a selection of his preferred settings for quick access.

Select a list value



Figure 32: Sensor fps list

To select a list value, turn the jogwheel until the selection bar is on the desired value and press the jogwheel.

Add a list value

If the list lacks the required setting, press the ADD screen button. This opens a screen where the desired value can be set. Either use the jogwheel for changing the value, or use the screen buttons for bigger adjustment steps.

When the desired value is set, press the jogwheel to add the value to the list.

Note: A maximum of 16 entries are supported by the list. After reaching this number of entries, it is no longer possible to add entries without deleting others first.

Delete a list value

List values no longer required can be deleted by pressing the DELETE screen button. This opens a screen where the values desired for deletion can be selected with the jogwheel. To delete the selected value, press the two lower outer screen buttons simultaneously.

Note: Every list contains standard values that cannot be deleted. These values are grayed out in the DELETE screen.

Note: The EI list is static and cannot be changed by the user. It contains ASA values from 160-3200 ASA in steps of 1/3 stop.

11.1.3.2 FPS

Pressing the FPS screen button opens the FPS list screen. It contains the default frame rates 23.976, 24.000, 25.000, 29.970, 30.000, 48.000, 50.000, 59.940 and 60.000 fps.



Figure 33: Sensor fps list

Note: Access to this screen is disabled during record.

The maximum fps value that can be set is determined by the maximum frame rate recordable by the **SxS PRO** card in use. This value is influenced by the codec set for recording, as well as the write speed of the card. While the write speed is a constant factor, the codec and its data rate can change the maximum frame rate the card can record at.

The following table shows the maximum available frame rate for all codec/card combos.

	Regular Speed mode		High Speed mode	
Codec	**SxS PRO 8-32 GB**	**SxS PRO 64 GB**	**SxS PRO 8-32 GB**	**SxS PRO 64 GB**
ProRes 422 Proxy	60 fps	60 fps	120 fps	120 fps
ProRes 422 LT	60 fps	60 fps	120 fps	120 fps
ProRes 422	60 fps	60 fps	60 fps	120 fps
ProRes 422 HQ	60 fps	60 fps	60 fps	120 fps
ProRes 4444	40 fps	60 fps	---	---
DNxHD 115/120/145	40 fps	60 fps	60 fps	120 fps
DNxHD 185x/195x/220x	60 fps	60 fps	60 fps	120 fps

If the desired frame rate cannot be set because it is greyed out, changing the **SxS** codec to one with a lower data rate can re-enable the high frame rates.

The lower screen buttons provide shortcuts to the screens of SxS CARDS (MENU>Recording>SxS CARDS) and SxS INFO (INFO>SxS CARDS) and SDI FPS. In the SDI FPS screen, both MON OUT and REC OUT frame rates can be adjusted within the limits of their current format settings.

Setting sensor fps through REC OUT fps

If the sensor fps is linked to the REC OUT frame rate, a message appears instead of the list. While this setting is active, sensor fps can only be changed by changing the REC OUT frame rate.

To change this setting, access the REC OUT menu screen (MENU>Recording>REC OUT) and set "REC OUT fps sets sensor fps" to "Off".



Figure 34: Fps screen with linked sensor fps

Setting correct frame rates for recording with external devices

It is very important to pay good attention to setting frame rates when recording with external devices. Mistakes can result in dropped frames and ruin the shot.

The sensor fps setting determines the amount of frames per second generated by the sensor. This can be anywhere in the range between 0.750 and 60.000 frames per second. The images are then processed by the camera electronics for the different output paths.

The REC OUT is the recording output path, which transmits images to an external recorder that stores the images. Its frame rate can only be set to standard speeds.

Ideally the REC OUT frame rate matches the sensor frame rate! If the REC OUT frame rate is lower than the sensor frame rate, the images cannot be output as fast as they are created by the sensor, resulting in dropped frames which are irretrievably lost!

If the REC OUT frame rate is higher than the sensor frame rate, duplicate frames are output on the REC OUT. For example, if the sensor is running at 10 fps and the REC OUT is set to 30 fps, every image is output 3 times, resulting in two duplicate frames following every active frame. A standard recorder would record these duplicate frames, which have to be removed in post.

To prevent this, the camera can mark the duplicate frames with a Variflag. If the recorder supports Variflag recording, it will discard the duplicate frames and only record the active frames. This saves valuable storage space and worktime. To activate the Variflag in the camera, go to Menu>Recording>REC OUT>Variflag.

The MON OUT should match the sensor and the REC OUT frame rate. If the sensor frame rate exceeds the available MON OUT frame rates, set the MON OUT to half the sensor frame rate if possible. This minimizes to risk of jittering image movements.

How to correctly set frame rates for recording with external devices:

- Decide which frame rate you want to set
- Go to MENU>Recording>REC OUT
- Set the REC OUT frame rate to the desired value. The HD-SDI format should match the recorder's setting
- If the desired sensor frame rate is a standard speed, set "REC OUT fps sets sensor fps" to "On". This way, the sensor always follows the REC OUT frame rate, avoiding dropped or duplicate frames.
- When the REC OUT settings are done, press HOME.
- Go to MENU>MON OUT and set the frame rate to the same value as REC OUT. If this is not possible because the REC OUT frame rate exceeds the range of MON OUT frame rates, use half the frame rate of the REC OUT.
- When the MON OUT settings are done, press HOME.
- If sensor is not set by REC OUT, press FPS and choose the desired sensor fps value from the list. Then press the jogwheel.
- If the desired value is not available, press the ADD screen button to set the desired value and add it to the list by pressing the jogwheel.
- All frame rate settings should be correct now.

High Speed Mode

If a valid High Speed license key is installed on the camera, the upper middle screen button will provide a link to switch the camera into High Speed mode. Loading the High Speed mode takes approximately 40 seconds.



When loading has finished, a success screen will appear that shows the currently set codec. The codec can be changed by pressing the lower mid screen button, which quick-links into the SxS recording menu screen.



In High Speed mode, the camera can only run frame rates of 60.000-120.000 fps. Default frame rates in the FPS list are 60.000, 72.000, 75.000, 90.000, 96.000, 100.000 and 120.000 fps.

Recording is only possible with **SxS** cards, the REC OUT outputs carry the MON OUT signal with a maximum frame rate of 30 fps.

It is highly recommended to only use **Sony SxS PRO** 64 GB cards in High Speed mode, as only these allow recording at sensor frame rates from 60-120 fps with all High Speed codecs. When using **Sony SxS PRO** 32 GB cards with codecs ProRes 422, ProRes 422 HQ, DNxHD 115/120/145 and DNxHD 175x/185x/220x, the sensor frame rate is limited to 60 fps maximum.

The High Speed mode is exited the same way it is loaded, by pressing the upper middle screen button of the FPS list screen. Exiting High Speed mode takes approximately 40 seconds.

11.1.3.3 AUDIO

Pressing the AUDIO screen button in the Home screen opens the Audio screen. This screen shows the level on the two audio channels in the camera. The audio levels are displayed from -45 dB FS to 0 dB FS.

Note: When audio is switched off or disabled, no meters are displayed, but a message shows OFF or DISABLED. Audio is disabled by the camera when sensor fps does not match project fps.

Light blue markers show reference levels of -20, -18 and -9 dB FS.

Red markers at levels -1 and 0 dB FS warn of clipping. With a properly levelled audio signal, the red markers should almost never be visible.



Figure 35: Audio screen

Gain can be applied to the audio channels by either turning the jogwheel to set both channels, or with the associated screen buttons (CH 1/2/ +/-) individually. The amount of gain applied by the camera is visible next to the levels in light gray.

Pressing the OPTIONS screen button opens the audio options screen. It contains a list of audio parameters to set.



Figure 36: Audio options screen

Record	Sets audio recording On or Off. If audio recording is switched off, no audio is recorded on **SxS** cards, the HD-SDI contains no audio and the Audio out is muted.

Channel 1 level	Manual allows the user to manually apply gain to the input signal on channel 1 to reach a correct level. Unity matches a 4 dBu input signal to -20 dB FS. This setting leaves enough headroom for recording and avoids audio clipping. With unity, audio levels can not be adjusted by the user.
Channel 2 level	Manual allows the user to manually apply gain to the input signal on channel 2 to reach a correct level. Unity matches a 4 dBu input signal to -20 dB FS. This setting leaves enough headroom for recording and avoids audio clipping. With unity, audio levels can not be adjusted by the user.
Channel 1 source	Choose whether left or right input signal shall be routed to channel 1.
Channel 2 source	Choose whether left or right input signal shall be routed to channel 2.
Soundroll (=Tape)	Enter the name of the soundroll (also known as Tape in the menus of some recorders) of an external audio recorder, for easier sound alignment in post. The name is written to the FCP XML file and the Avid log exchange (ALE) file on the **SxS PRO** cards.

Figure 37: Audio out screen

The AUDIO OUT opens a screen where the global volume for both Audio out channels can be adjusted. The OPTIONS button in this screen loads a list of Audio out options.



Figure 38: Audio out options

- Left out: Sets which channel is routed to the left output.
- Right out: Sets which channel is routed to the right output.

Note: This setting does not influence audio embedding in HD-SDI or recording in QuickTime clips. It only affects the AUDIO OUT connector!

- Audio out level: Choose to determine the level of the audio out channels manually, or set it fix to the maximum output.

Note: ALEXA automatically determines the internal signal run time and matches audio and images so they are always in sync. When changing sensor fps or project fps, it may take up to 2 seconds for the camera to resync image and audio signals.

11.1.3.4 SHUTTER

Pressing the SHUTTER screen button in the HOMESCREEN opens the SHUTTER list screen. The list contains default shutter angles 11.2°, 22.5°, 45.0°, 90.0°, 172.8°, 180.0°, 270.0° and 358.0°.

Note: Access to this screen is disabled during record.

Below the list, the actual exposure time at the currently set frame rate is shown.

Note: Be aware that combination of long exposure times (small sensor frame rate with large shutter angle) and high exposure indexes can lead to image artifacts!



Figure 39: Shutter list

The shutter angle can be set in a range from 5.0° to 358.0°.

11.1.3.5 EI

The Exposure Index is the applied sensitivity of the camera.

Note: The Exposure Index list has a fixed content, meaning that it cannot be changed by the user.



Figure 40: Exposure Index screen

ALEXA has a basic sensitivity of 800 ASA. This means that the dynamic range is almost evenly distributed above and below neutral grey with very low noise in the dark parts of the image and a very clean and smooth clipping behavior in the bright parts.

Due to its high dynamic range, the sensitivity can be set in a range from 160-3200 ASA in steps of 1/3 stops while keeping a high image quality.

Applying the extreme ASA ratings will nonetheless have an influence on the images. At low ASA ratings like 160 ASA, the dynamic range below neutral grey increases, which will reduce noise even further. At the same time, the dynamic range above neutral grey is slightly reduced. The clipping itself is not influenced by this, but the shoulder of the gamma curve will get slightly steeper, which will reduce the smoothness of the clipping.

At high ASA ratings like 1600 ASA, the images behave the opposite way. Noise is increased, which makes it important to judge the dark parts of the image, while the clipping behavior will be even smoother.

EI $160^{+5.0}_{-9.0}$ EI $200^{+5.3}_{-8.7}$ EI $400^{+6.3}_{-7.7}$ EI $800^{+7.4}_{-6.6}$ EI $1600^{+8.4}_{-5.6}$ EI $3200^{+9.4}_{-4.6}$

Figure 41: Exposure Indexes and latitude aboive and below neutral grey



Figure 42: Graphical comparison of latitude at different exposure indexes

11.1.3.6 COLOR

By pressing the COLOR button all settings related to color management can be accessed. The first screen gives an overview of the color settings of all image paths of the camera. It shows the currently active gamma on EVF, MON OUT, REC OUT and SxS. In addition, it shows whether a look is active on any of these image paths, and which look is selected in the camera.

Note: When High Speed mode is activated, no look can be applied to the REC OUT, because the REC OUT shows the same image as the MON OUT.



Figure 43: Color screen

Look files are a way for the user to influence the color appearance of the camera. A look file alters the way the sensor image is converted to video color space. Image paths that are set to LOG C cannot have a look applied and are always recorded clean.

The currently selected look file can be applied to any of the image path by pressing the correspnding screen button. If no look is selected, or if a path is set to LOG C, it cannot have a look applied.

To select a look file, press the SET LOOK screen button and select a look from the list. Confirm the selection by pressing the wheel.



Figure 44: List of look files on camera

The looks are stored in the camera. Additional looks can be loaded from the SD card. Press the ADD button to see look files stored on the SD card. These look files must be stored on the SD card in a folder named *LookFiles*. The required folder structure on the SD card can be created under MENU>System>SD card>Prepare SD card.

Look files on the camera that are not needed any more can be deleted by pressing the DELETE button. Select the look and press the two lower screen buttons labeled DELETE simultaneously to remove the look file from the camera.

In the COLOR screen, pressing the GAMMA button opens a screen where the Gamma of all 4 image paths (SxS, REC OUT, MON OUT, EVF) can be adjusted centrally.



Gamma defines the contrast curve that is applied to the images. Three different gamma settings are possible:

LOG C	Gamma according to Cineon specification. Images are prepared for output to film material or DI-like treatment. Images will appear flat on a standard broadcast monitors, the use of external devices to apply a LUT is a must to get visually pleasing images on a monitor.
REC 709	Gamma according to ITU.R-BT709 standard. Images are prepared for playback on standard broadcast monitors.
DCI P3	The new option is suited for DCI P3 (also known as SMPTE 431-2) compliant displays. This color space is used for digital cinema purposes.
LOG C film matrix	When set to "On", a matrix is applied to the image paths set to LOG C, which makes the image appear like an image coming from a film negative that has been scanned with an ARRISCAN. This is meant for a DI workflow that utilizes preview LUTs that were generated for film scans.

Note: Due to technical limitations, it is not possible to set REC OUT to REC 709 and SxS to DCI P3, and vice versa. When one of them is changed, the value of the other image path is matched automatically by the camera.

Note: During High Speed mode, REC OUT gamma cannot be set, because the REC OUT shows the same image as the MON OUT.

LOG C is an intermediate color format and not designed as a display standard. Thus color grading becomes an obligatory post production step and for proper previewing, creation of dailies or editing proxies it is necessary to use Look Up Tables. Matching preview LUTs can be generated with the ARRI ALEXA LUT generator on www.arridigital.com.

Playback and Look Files

Look settings of the camera outputs also apply to any clip during playback, if this clip was recorded in LOG C. A clip recorded in REC 709 or ITU P3 with or without look will be played back "as is", even if the output is set to LOG C.

Please note that the currently active look is applied to the clip, not the one that was active at the time of recording. It is the courtesy of the user to make sure the right look is applied during playback.

11.1.3.7 WB

Pressing the WB screen button in the HOMESCREEN opens the WB list screen. The list presets are 3200K for Tungsten, 4300K for Fluorescent, 5600K for Daylight and 7000K for Daylight cool.

White Balance adjusts the color balance of the camera according to the lighting in use. It can be adjusted in steps of 100K from 2000 to 11000K.

In addition to the white balance, which influences only the red-blue balance of the image, the CC (color compensating) shift can also adjust the green-magenta balance.

Any light source that does not have a continuous spectrum, like fluorescent tubes, will have peaks in its spectrum that can not be corrected with the traditional white balance. The CC shift can correct these peaks up to the same amount of a full green or a full magenta gel. 1 step of CC SHIFT translates to 035 Kodak CC values or 1/8 Rosco values.



Figure 45: White balance list

White balance and color compensation should be adjusted only with the help of appropriate equipment. This can either be a color meter or a vectorscope together with a calibrated grey card.

AUTO WB

The camera can also perform an automatic white balance. To do this, press the AUTO WB screen button once. The EVF and MON OUT image show a mask with a center cut-out. Place a well-lit grey card in the are of the mask cut-out, and press the AUTO WB screen button again. The camera will calculate a WB and CC value based on the color values in the image center. If these values are out of range, or the image center is strongly under- or over-exposed, the camera cannot calculate a WB value and will show an error message.



The AUTO WB value is always stored as the first entry of the WB list. This entry is overwritten every time an automatic white balance is performed. To save an AUTO WB value, press ADD after the successfull calulation, and press the wheel twice. The AUTO WB result will be saved as a user value in the WB list.

User entries of the WB list can be assigned a new name to match either the type of lighting used, or to match to a certain type of setup (e.g. INDOOR DAY).

In the WB screen, press RENAME, then adjust the string as desired, and confirm the changes by pressing DONE. The action can be aborted by pressing BACK.



Figure 46: WB rename screen

Note: Default values cannot be renamed.

11.1.4 Function Buttons

The main controls feature the following function buttons:

ON/OFF	Press shortly to switch the camera on. To switch off the camera, the button must be pressed for several seconds. In the Homescreen, a countdown is displayed. If the button is released before the countdown has elapsed, the camera does not shut down.
REC	Starts/stops internal recording to **SxS PRO** cards.
LOCK	Press long to lock/unlock the user interface. The recessed buttons USER, REC, and ON/OFF are not affected by the lock.
GRAB	Grabs a still frame to an internal cache, from where the image is written to the SD card. When storing the image is finished, a new frame can be grabbed.
TC	Enters the screen for configuring Time code.
WRS	Available on ALEXA Plus only, it gives access to the Plus camera functions.
PLAY	Activates playback on MON OUT and EVF. Opens the play screen and loads the last active clip of the **SxS PRO** cards in pause.
INFO	Enters the Status Info screen, where you get information on the system's state. Also available is version info, where you get information on camera hard- and firmware, storage info giving details about **SxS PRO** cards, and system info.
USER	Enters the user screen, where the three user buttons of the operator controls, as well as the five screen buttons of the user screen (Note: the top three screen buttons of the user screen reflect the behavior of the three user buttons that are part of the operator controls) can be assigned with user defined functions.
MENU	Starts the menu, where most camera settings can be adjusted. Navigate inside the menu with the jogwheel.
BACK	When navigating, this button brings you back to the previous screen. When editing, this button reverts your adjustment and quits edit mode.
HOME	Returns to the Homescreen from any other screen.

11.1.4.1 TC (Time Code)

The TC screen shows the currently set TC. The currently active TC settings are displayed below the TC values.



Figure 47: Timecode screen

Note: Individual frame values are not shown in the screen, even though they are counted.

By pressing the OPTIONS screen button, the Time Code options list opens, where TC settings can be changed.

- Source: Choose the TC source

Int TC	Internal TC counter
Ext LTC	TC is read from the LTC input. Only possible with Mode set to Free Run, and the project fps must match the sensor fps setting!

- Mode: Defines how the TC is counted

Rec Run	TC will only increment during record. The TC value is increasing with every frame generated by the sensor during record while counting with the set time base (=project fps).
Free Run	TC is running free. If the source is set to Int TC, and the sensor frame rate does not match the time base of the TC, the value is incrementing with every new frame generated by the sensor while counting with the set time base (=project fps).

- Generator:

Regen	Rec Run TC is regenerated from the last valid TC value. With Ext LTC, it means that the camera is continuously reading the TC signal at the LTC socket as long as it is present. Only upon disconnection or loss of signal, the camera continues counting on its own. When the external signal reappears, the camera uses the values of the external signal again. With Int TC, the value is increased with each new image generated by the sensor.
Jam sync	Only Ext LTC can be jam synced. This means that the external TC source is connected to the camera, then the camera reads the external TC count and continues counting on its own. Due to a highly precise crystal oscillator in ALEXA, the internal counter will count accurately for 8 hours. After that period, the camera has to be resynced to avoid any TC offset. The camera can be synced to TC signals whose time base differs from the camera's project fps, as long as both are integer (24, 25 and 30 fps) or non-integer (23.976 and 29.97 fps) signals. It is not possible to mix signals of these two groups.

Note: It is recommended to sync after every shooting break to avoid the risk of having to resync during the shoot.

Note: The camera will keep its TC for about 10 minutes after disconnection from the power source. If a power source is connected, the camera will remember its TC for as long as the power source is connected, even if it is switched off.

- Userbit source: shows the source of the user bits.

Internal	User bits are set manually in the User Bit screen.
LTC in UB	When using Ext LTC as TC source, the user bits are sampled from the external signal.

Press the SET TC screen button to adjust the TC counter (only with Int TC as source). Reset it or match it to the system clock with the upper screen buttons that appear during edit mode.

Note: The camera will force Time code to "Internal Rec Run Regenerate" if the sensor fps does no match the project fps!

The PROJECT button is a quick link into the PROJECT menu screen, where project fps can be adjusted. Project fps sets the time base of the time code.

Note: Non-integer TC time base settings 23.976 and 29.97 are currently always counted as non-dropframe time code!

USER BITS

Press the USER BITS screen button to access the USER BITS screen.

The content of the User binary group in the time code. Can contain 8 letters of Hex values (0-9, A-F).

Press the SET UB screen button to adjust the User Bits values.



Figure 48: User bits screen

Note: If Vari flag in the REC OUT menu screen is set to "On", the last two digits cannot be set, as they contain the Vari flag.

11.1.4.2 INFO

STATUS Info

The first INFO screen contains information on the current state of the camera system. If the camera behaves normally, the message "System state: Good" is displayed. Other messages can either contain a warning or an error message. For info on these messages, see the Appendix "Errors and warnings".

When an SD card is present, a system log can be stored to the SD card by pressing the lower mid screen button labeled SAVE TO SD. Patience is required as it can take about a minute until the log is written to the SD card.

Note: Saving a system log is only necessary if the camera is showing unnormal behavior. It can then be sent to the ARRI camera service for analysis. The log is not human-readable and can only be analyzed by the ARRI camera service.

VERSION Info

Cam serial no.	The serial number of the camera.
Cam ID	Translation of the camera serial number to Base36, with an additional prefix for 3D applications.
Firmware	Version number of the currently installed camera SUP (Software Update Packet).
EVF serial number	The serial number of the viewfinder that is attached to the camera.
EVF firmware	Version number of the viewfinder's firmware.



Figure 49: VERSION info screen

SxS CARDS Info

Codec	Currently set codec for internal recording.
Status	Current status of **SxS PRO** cards in slot 1 and 2.
Free capacity	Free storage space of **SxS PRO** cards in percent.
Max. fps current	Maximum frame rate of the **SxS PRO** cards with currently set codec.
Card size	Total available storage space on **SxS PRO** card



Figure 50: SxS CARDS info screen

SYSTEM Info

Date	Currently set date. Can be set in MENU>SYSTEM>DATE/TIME.
Time	Currently set time. Can be set in MENU>SYSTEM>DATE/TIME.
Fan speed	Speed of camera cooling fan in rotations per minute.
Sensor mode	Shows active sensor mode, either 16:9 or 4:3. *Note: 4:3 only possible with ALEXA M, ALEXA Plus 4:3 or ALEXA Studio.*
Sensor temperature	Current temperature of image sensor. Target is 35°C in standard mode, 40°C in tropical mode.
IP address	IP address of the camera's Ethernet port.
Operating time	Shows the total operating time of the camera in hours (since first installation of SUP 4.0 or higher)



Figure 51: SYSTEM info screen

FPS Info

Gives an overview of all frame rates in the camera.

Sensor fps	Frames per second generated by the sensor.

Project fps	Frames per second the Timecode is counting and frame rate used for playback of QuickTime clips.
REC OUT frame rate	The rate at which frames are output on the REC OUT HD-SDI.
MON OUT frame rate	The rate at which frames are output on the MON OUT HD-SDI.
SxS CARD 1 max. fps	Maximum frames per second the **SxS PRO** card in card slot 1 can record with currently set SxS codec.
SxS CARD 2 max. fps	Maximum frames per second the **SxS PRO** card in card slot 2 can record with currently set SxS codec.


LIVE INFO
VERSION
SxS CARDS
Sensor fps 24.000 fps
Project fps 24 fps
REC OUT frame rate 24 fps
MON OUT frame rate 24 fps
SxS CARD 1 max. fps current 60 fps
SxS CARD 2 max. fps current 60 fps
SYSTEM
FPS INFO

Figure 52: FPS Info screen

11.1.4.3 USER

By pressing the USER button the USER screen is loaded where the screen buttons can be assigned with user defined functions.

The upper three screen buttons of the USER screen mirror the behavior of the three assignable buttons on the camera left side (labeled 1, 2, 3). The two outer lower screen buttons function as additional assignable buttons with extended functionality.

By pressing the lower right EDIT screen button, the functions can be assigned to the buttons.



Figure 53: User screen

Assign functions to the buttons by using the jogwheel.



Figure 54: Edit User Button assignment

For user buttons 1-3, which are also available on the camera left side, the following functions can be assigned:

Name	**Description**
None	button has no function
MON OUT surround	toggles surround view of the MON OUT image on/off
MON OUT gamma	toggles gamma of the MON OUT between REC 709 and log C (only with recording gamma set to log C)
MON OUT frame lines	toggles frame lines of the MON OUT image on/off
MON OUT status info	toggles status info of the MON OUT image on/off
MON OUT false color	toggles false color display on MON OUT on/off
MON OUT peaking	toggles peaking on MON OUT on/off
MON anam. desqueeze	toggles anamorphic desqueeze options of MON OUT *Note: Only with valid Anamorphic De-squeeze license key installed on camera*
Frame lines color	toggles color of frame lines image on/off
EVF surround	toggles surround view of the EVF image on/off
EVF gamma	toggles gamma of the EVF image between REC 709 and log C (only with recording gamma set to log C)
EVF frame lines	toggles frame lines of the EVF image on/off
EVF status info	toggles status info of the EVF image on/off
EVF zoom	toggles the zoom function of the EVF
EVF false color	toggles false color display on EVF on/off
EVF peaking	toggles peaking on EVF on/off

EVF anam. desqueeze	toggles anamorphic desqueeze options of MON OUT *Note: Only with valid Anamorphic De-squeeze license key installed on camera*
Grab still frame	grabs a still frame to the SD card *Note: Disabled in High Speed mode*
Return in active	toggles RET IN signal active ond EVF and MON OUT according to user settings
Toggle SxS	toggles the currently active **SxS PRO** card
Check last clip	play last 5 seconds of last clip, then return to live image
Circle clip	set a clip to Circle clip during recording
Auto WB	1st press loads Auto WB frame 2nd press within 1 second performs Auto White Balance

User buttons 4 and 5 have partially different functions

Name	**Description**
None	button has no function
MON OUT surround	toggles surround view of the MON OUT image on/off
MON OUT gamma	toggles gamma of the MON OUT between REC 709 and log C (only with recording gamma set to log C)
MON OUT frame lines	toggles frame lines of the MON OUT image on/off
MON OUT status info	toggles status info of the MON OUT image on/off
MON OUT false color	toggles false color display on MON OUT on/off
MON OUT peaking	toggles peaking on MON OUT on/off
MON anam. desqueeze	toggles anamorphic desqueeze options of MON OUT *Note: Only with valid Anamorphic De-squeeze license key installed on camera*
Return in active	toggles RET IN signal active ond EVF and MON OUT according to user settings
Frame lines color	toggles color of frame lines image on/off
Toggle SxS	toggles the currently active **SxS PRO** card
Format Card 1	quick link to the menu screen where SxS card 1 can be formatted
Format Card 2	quick link to the menu screen where SxS card 2 can be formatted
Format Card 2	quick link to the menu screen where SxS card 2 can be formatted
False color index	quick link to the menu screen MENU>Monitoring>False color index

View position	moves the mirror shutter to the View position *ALEXA Studio only*
Gate position	moves the mirror shutter to the Gate position *ALEXA Studio only*

11.1.4.4 PLAY

Clips that have been recorded to the SxS cards can be played back by the camera on EVF, MON OUT and REC OUT.

Note: The REC OUT signal cannot be used for playback when it is set to ARRIRAW.

Pressing the PLAY button opens the play screen and loads the last clip in pause. Pressing the wheel plays the clip back. pressing the wheel again brings the clip back into pause.



Figure 55: Play screen

In the play screen the playback actions can be controlled.

STEPSIZE	Toggles the scrub stepsize between 1 frame and 1 second.
CIRCLE CLIP	Mark the clip as circle clip. This will set the <GOOD> tag in the FCP XML to YES. Press again to unmark it.
LIVE	Switches to the live sensor image as long as the button is pressed.

Note: When surround view is active, the image angle changes slightly when switching between live and playback image because the playback image does not contain the surround view.

The jogwheel can be used to scrub through the paused clip. The scrub stepsize is shown in the lower mid of the screen.

Additionally, important clip information is visible. The clip name is shown in the top line of the blue center bar. Below it is a progress bar showing the current position in the clip. The current duration is shown below the progress bar at the left, and the total duration at the right. The center shows the playback Time code.

Note: Do not eject a card during playback.

To stop playback and return to the live image, press HOME or BACK. If you press REC, playback is stopped, recording is started and the Home screen is loaded.

OPTIONS

The OPTIONS screen button opens a list of general playback options.



Figure 56: Play options screen

Clip end action	Determines what happens when the end of a clip is reached. Options are Pause and Loop.
Show frame lines	Sets frame lines to On or Off during playback. Center mark is always switched off during playback.
Status info on MON OUT	Sets status info overlays on MON OUT on or off during playback.

CLIPLIST

The CLIPLIST screen button loads a list of all clips on the SxS card, where a different clip can be selected for playback. Additional clip info is shown at the bottom of the screen.



Figure 57: Cliplist screen

Playback and Look Files

Look settings of the camera outputs also apply to any clip during playback, if this clip was recorded in LOG C. A clip recorded in REC 709 or ITU P3 with or without look will be played back "as is", even if the output is set to LOG C.

Please note that the currently active look is applied to the clip, not the one that was active at the time of recording. It is the courtesy of the user to make sure the right look is applied during playback.

11.1.5 Menu

The menu contains parameters for the basic camera setup. It has a tree structure and the current path in the menu is displayed in the top section of every screen.

To access a new menu level, select the group with the jogwheel and press the jogwheel. This will open the next level.

To go one level back up, press BACK. A parameter has its value displayed at the right part of the screen. Select it with the jogwheel and press the jogwheel to edit it.

Cancel an edit action by pressing BACK, confirm the setting by clicking the jogwheel.



Figure 58: MENU

11.1.5.1 Recording

Provides access to SxS CARDS and REC OUT parameters.



Figure 59: MENU>RECORDING

SxS CARDS

ALEXA can internally record to Sony **SxS PRO** cards. The card slots are located on the camera's left side.


MENU>RECORDING>SxS CARDS
SxS recording ProRes
Codec ProRes 4444
HS codec ProRes 422 (HQ)
Dual recording Off
Quick format SxS CARD 1 >
Quick format SxS CARD 2 >

SxS recording	Switches **SxS** recording between Off and ProRes™ or DNxHD (requires license key). With **SxS** recording off, power consumption is reduced by 15 W. Switching **SxS** recording on takes approximately 15 seconds to reboot the hardware.
Codec	Set the codec to be used for internal recording to **SxS** cards. Choose from the full range of Apple ProRes™ codecs or two types of Avid DNxHD codecs (requires license key). *Note: Disabled during High Speed mode.*
HS Codec	Set the codec to be used for internal recording to **SxS** cards during High Speed mode. Choose from the full range of Apple ProRes 422™ codecs or two types of Avid DNxHD codecs (requires license key). *Note: Only visible if High Speed license key is installed on camera. Disabled during Regular Speed mode.*
Dual recording	Record parallely to two **SxS PRO** cards. Both cards must be of the same size and must not differ in structure or content.
Quick format SxS CARD 1/2	Opens a screen where the **SxS PRO** card can be formatted. This action is fast, as it only erases the file allocation table.
Erase SxS CARD 1/2	Opens a screen where the **SxS PRO** card can be erased. This action takes longer than the quick format, but ensures that all data of the card is erased, and can also result in higher card write speeds.

Note: Formatting and erasing is only enabled if the write protection of the card is switched off. The write protection cannot be switched off while the card is mounted in the camera!

Note: Formatting or erasing an **SxS PRO** card removes all data irreversibly from the card. Be careful not to format any **SxS PRO** cards with data before they have been backed up!

When cards without a valid file system are inserted into the camera, a screen will appear that asks for card formatting. It is recommended to directly format the card and not to postpone this action.

Apple ProRes™ codecs

The following table gives an overview of the range of ProRes codecs. All these codecs are supported by ALEXA.

Name	Color coding	Data rate @ 30 fps	Recording time on 32 GB SxS PRO @ 30 fps[3]	max. frame rate with SxS PRO 8-32 GB	max. frame rate with SxS PRO 64 GB
ProRes 422 (Proxy)	YCbCr	45 Mb/s	1 h 23 min	60 fps	120 fps[2]
ProRes 422 (LT)	YCbCr	102 Mb/s	37 min	60 fps	120 fps[2]
ProRes 422	YCbCr	147 Mb/s	25 min	60 fps	120 fps[2]
ProRes 422 (HQ)	YCbCr	220 Mb/s	17 min	60 fps	120 fps[2]
ProRes 4444[1]	RGB[1]	330 Mb/s[1]	11 min	40 fps	60 fps

[1]Without alpha channel (444 only)

[2]The maximum frame rate is also limited by the write speed of the **SxS PRO** card in use, which might reduce the maximum frame rate below the values given in the table. ProRes 4444 is limited to 40 fps with **SxS PRO** cards up to 32 GB capacity, and only reaches 60 fps with **SxS PRO** 64 GB cards .

[3]Apple ProRes™ is a VBR (variable bit rate) codec. This means that the actually available recording time depends on the image content. The number given in the table is the MINIMUM available recording time for a 32 GB card. When image content is easily compressable without loss of image quality, the available recording time can exceed the number given in the table.

Also note that the available recording time is given for a 32 GB **SxS PRO** card at 30 fps. A lower sensor fps will increase the available recording time, while a higher sensor fps will decrease it.

[2]Only with High Speed license key installed on camera and active High Speed mode. Outside of High Speed mode, the camera is limited to 60 fps.

The following Avid DNxHD codecs are available on ALEXA (when the required license key is installed):

Name	Color coding	Data rate @ 29.97 fps	Recording time on 32 GB SxS PRO @ 29.97 fps	max. frame rate[2]
DNxHD 115/120/145	YCbCr	145 Mb/s	29 min	60 fps
DNxHD 175x/185x/220x	YCbCr	220 Mb/s	19 min	60 fps

DNxHD 115/120/145 has a bit depth of 8 bit. DnxHD 175x/185x/220x has a bit depth of 10 bit.

DNxHD is a FBR (fixed bitrate codec), the codec naming differs with the project frame rate. The lowest number is for 23.976/24 fps, the middle number for 25 fps and the highest number for 29.97 fps. 30 fps project frame rate is not available with DNxHD. The given recording time does not depend on the image content.

[2]The maximum frame rate is also limited my the write speed of the **SxS PRO** card in use, which might reduce the maximum frame rate below the values given in the table.

REC OUT



Figure 60: MENU>REC OUT

The camera has two HD-SDI outputs that carry the camera image to be recorded with external recording devices.

Note: Only use double shielded HD-SDI cables for recording to ensure error free data transmission!

Frame rate	Select the rate at which images are transmitted per second.
HD-SDI format	Select the format that is used to transmit images. See following table for format details.
Scan format	Defines how images are transmitted.

	• p: Progessive. Images are transmitted line by line from left to right, starting at the top-left pixel. • psf : Progressive segmented. Images are first split into fields, which are then transmitted line by line from left to right. *Note: Frame rates over 30 fps are only available in progressive scan. This complies with SMPTE standards.*
Output range	Defines which bit range of the full 10 bit (0-1023) is used to transmit image data. • Legal: Uses values 64-940 for RGB and Y signals, and values 64-960 for CbCr signals. This complies with the SMPTE 274M 8.7. • Extended: uses values 5-1019, which results in about 10% more steps. Complies with SMPTE 274M 8.12 (called undershoot/overshoot). *Note: Check which mode your recorder supports. If you set the camera to extended, but your recorder only supports legal, you will end up with clipped images!*
REC OUT fps sets sensor fps	If set to "On", the sensor will always follow the REC OUT frame rate setting. This ensures no frames are dropped on the output.
SDI remote	When set to "On", the REC OUT and MON OUT will carry a flag in their data stream to signal an external recorder if the camera is currently recording internally. When **SxS** recording is switched off, the REC button will only trigger the sending of this flag.
Vari flag	When set to "On", the Vari flag marks duplicate images in the HD-SDI stream. A recorder that supports the Vari flag can detect these frames and discard them. This makes sure that no duplicate frames are recorded if the HD-SDI is set to a higher frame rate than the sensor.

HD-SDI formats and corresponding frame rates

Format	Links Used	Image Raster	Sampling Structure	Color Mode	Possible Frame Rates (fps)
422 1.5G SL	1	1920x1080	4:2:2	YCbCr	23.976, 24, 25, 29.97, 30
422 1.5G DL	2	1920x1080	4:2:2	YCbCr	48, 50, 59.94, 60

422 3G SL	1	1920x1080	4:2:2	YCbCr	48, 50, 59.94, 60
444 1.5G DL	2	1920x1080	4:4:4	RGB	23.976, 24, 25, 29.97, 30
444 3G SL	2	1920x1080	4:4:4	RGB	23.976, 24, 25, 29.97, 30
444 3G DL*	2	1920x1080	4:4:4	RGB	48, 50, 59.94, 60
ARRIRAW 1.5G DL**	2	2880x1620	Bayer	Bayer	23.976, 24, 25, 29.97, 30
ARRIRAW 3G SL**	2	2880x1620	Bayer	Bayer	23.976, 24, 25, 29.97, 30
ARRIRAW 3G DL**	2	2880x1620	Bayer	Bayer	48, 50, 59.94, 60

*Note: Proprietary signal format, as no SMPTE standard supports RGB 444 with frame rates higher than 30 fps. Only supported by few recorders.

**Note: The RAW sensor image is transmitted wrapped as 1920x1080 RGBA. This signal can only be recorded with Arriraw T-Link certified recorders. Some recorders only support certain types of ARRIRAW T-Link.

30-60 fps recording with ALEXA over HD-SDI

Unlike the ARRIFLEX D-21, which used a proprietary mode for recording frame rates between 30-60 fps, ALEXA complies with SMPTE standard 372M in terms of image transmission for 422 1.5G DL and 3G SL formats.

This means that images are split into fields, and every field is transmitted over one link. The second field of every image is transmitted over the other link, so that every link carries an interlaced signal in field integration mode. The recorder realigns the images correctly into a progressive sequence.

Two proprietary formats allow transmission of 444 RGB or ARRIRAW images at frame rates between 30-60 fps. These are 444 3G DL for RGB and ARRIRAW 3G DL for raw images. These formats do not comply to a SMPTE standard and are only supported by a few recorders. Please refer to the manual of your recorder to see if it supports these formats.

11.1.5.2 Monitoring

The Monitoring section defines setup of EVF-1 electronic viewfinder and MON OUT. These outputs are meant for monitoring, not for recording of images.

The frame lines setup applies to both MON OUT and EVF-1. Frame lines can of course be switched on or off individually for MON OUT and EVF-1.



Figure 61: MENU>MONITORING

Electronic viewfinder	Opens the screen where EVF settings can be changed
MON OUT	Opens the screen where MON OUT settings can be changed
Frame lines	Opens a screen where frame lines can be set up
RET IN path	Defines on which of the monitoring image paths the signal present at the RET IN connector is visible when return in is activated via user button.
Electronic level sensitivity	Increases the sensitivity of the electronic level overlay on MON OUT and EVF *Note: Available on ALEXA Plus only*
False color index	Opens a screen where the color coding of the false color display option of EVF and MON OUT is explained.

Electronic Viewfinder

Brightness	Select the brightness of the EVF.
Rotate image	When mounting the EVF to the right side of the camera, the image can be flipped so it appears correctly in the viewfinder. Affects only the EVF image, MON OUT and recording images are not rotated!

Smooth mode	With smooth mode set, the EVF image shutters less when panning. *Note: Smooth mode is only possible with frame rates up to 30 fps and shutter angles of 180.0 or less.*
Surround view	The ALEV III sensor has 10% additional pixels outside the recorded image for a better monitoring experience. The user can decide whether he wants to see these 10% in the viewfinder or not. By switching surround view on, objects that are not wanted in the image, such as microphone booms, can be seen by the operator before they enter the image.
Frame lines + status info	Links to a screen where frame lines, surround mask, center mark and status info overlays can be switched on or off in the EVF.
Peaking	Opens a screen where peaking in the EVF can be switched on or off, and the strength of peaking can be set.
Anamorphic desqueeze	Only shown if a license for anamorphic desqueeze is active in the camera. The desqueeze can correct the image for 1.3x and 2.0x lenses. With 2.0x lenses, the user can choose from seeing the full sensor image (2.0x), or only the relevant image area (2.0xmag) while left and right image parts outside the 2.39 aspect area are cropped.
Zoom position	The part of the image which is magnified when pressing the ZOOM button on the viewfinder can be set to the center of the sensor image, or a vertically upwards shifted area (*Eye level*). The *Eye level* setting allows focus check on a person's eyes.



Figure 62: MENU>MONITORING>EVF

Frame lines + status info screen

Frame lines	Frame lines are a reference for framing that typically consist of an image frame, a center mark and an aspect ratio reference. See the appendix for more information on the ALEXA frame line format.
Surround mask	If surround view is set to "On", it must be separated from the recorded image area to allow proper framing. Users can choose from different mask levels, or a black or colored line for separation.

Center mark	A center mark, either a cross or a dot can be added to the image to help the framing.
Status info	At the upper and lower edge of the EVF, right outside the active image area, additional status info can be displayed. The upper area contains camera image parameters, the lower area contains camera status infos.
Electronic level	Overlay showing the horizontal levelling of the camera. *Only available on ALEXA Plus.*
LDS info	Overlay showing LDS lens info. *Only available on ALEXA Plus.*

MON OUT

The MON OUT is a 422 1.5G single link HD-SDI output. The output range is fixed to legal range.

Frame rate	The MON OUT frame rate can be set to 23.976, 24, 25, 29.97 or 30 fps. The frame rate should, if possible, match the sensor frame rate to avoid frame drops or duplicate frames on the output, which would result in jittering images when image content is moving.
Scan format	Defines how images are transmitted. • p: Progessive. Images are transmitted line by line from left to right, starting at the top-left pixel. • psf: Progressive segmented. Images are first split into fields, which are then transmitted line by line from left to right.
Surround view	The ALEV III sensor has 10% additional pixels outside the recorded image for a better monitoring experience. The user can decide whether he wants to see these 10% in the MON OUT or not. By switching surround view on, objects that are not wanted in the image, such as microphone booms, can be seen by the operator before they enter the image.
Frame lines + status info	Links to a screen where frame lines, surround mask, center mark and status info overlays can be switched on or off in the MON OUT.
Peaking	Opens a screen where peaking in the MON OUT can be switched on or off, and the strength of peaking can be set.
False color	Activates the false color display on the MON OUT. The false color display is a visual exposure help that uses color coding to emphasize significant luminance values.

Anamorphic desqueeze	Only shown if a license for anamorphic desqueeze is active in the camera. The desqueeze can correct the image for 1.3x and 2.0x lenses. With 2.0x lenses, the user can choose from seeing the full sensor image (2.0x), or only the relevant image area (2.0xmag) while left and right image parts outside the 2.39 aspect area are cropped.



Figure 63: MENU>MONITORING>MON OUT

Note: Only use double shielded HD-SDI cables for monitoring to ensure error free data transmission!

Frame lines + status info screen

Frame lines	Frame lines are a reference for framing that typically consist of an image frame, a center mark and an aspect ratio reference. See the appendix for more information on the ALEXA frame line format.
Surround mask	If surround view is set to "On", it must be separated from the recorded image area to allow proper framing. Users can choose from different mask levels, or a black or colored line for separation.
Center mark	A center mark, either a cross or a dot can be added to the image to help the framing.
Status info	At the upper and lower edge of the EVF, right outside the active image area, additional status info can be displayed. The upper area contains camera image parameters, the lower area contains camera status infos.
Electronic level	Overlay showing the horizontal levelling of the camera. Only available on ALEXA Plus.
LDS info	Overlay showing LDS lens info. Only available on ALEXA Plus.

Show reel + clip info	Shows reel & clip number in the MON OUT image.
Camera index letter	Adds the camera index letter to the top left corner of the MON OUT overlays.

Frame Lines



Figure 64: MENU>MONITORING>FRAMELINES

Frame lines are an image overlay that can be applied to either the EVF image, the MON OUT image, or both.

ALEXA frame lines are stored as XML files containing definitions what the frame lines look like.

The camera contains default frame lines for 1.33:1, 1.66;1 1.78:1, 1.85:1, 2.39:1, 2.39 1.3x anamorphic and 2.39 2.0x anamorphic aspect ratios. Additional frame lines can be loaded from the SD card.

To load more frame lines, press the ADD screen button in the Frame lines data base screen. This opens a list of all frame line files located on the SD card, which can then be copied to the camera. The camera supports up to 16 frame line templates.

Frame line 1	Select the main frame line template.
Frame line 2	Choose a second frame line, if desired.
User rectangles	Opens a screen where two user rectangle overlays can be adjusted.
Color	In the frame lines definition file, lines can either be given a fixed color, or they can have the color specified as "User". If "User" is chosen for a line, the setting chosen in this menu section is applied to the line.
Intensity	Sets the intensity of the frame lines. The higher the number, the brighter the frame lines appear.

User rectangles screen

User rectangles	Display up to two additional rectangles that can be adjusted manually.
Set rect 1	Set the shape of rectangle 1. Activate it through User rectangles.
Set rect 2	Set the shape of rectangle 2. Activate it through User rectangles.

Note: Default frame lines have "User" specified as color for all content.

False Color Index

The false color index screens contains a visual reference for the false color mode available for EVF and MON OUT. It shows which signal levels the colors are related to.

What	Signal Level	Color	
White clipping	100% - 99%	red	
Just below white clipping	99% - 97%	Yellow	
One stop over medium gray (Caucasian skin)	56% - 52%	pink	
18% medium gray	42% - 38%	green	
Just above black clipping	4.0% - 2.5%	blue	
Black clipping	2.5% - 0.0%	purple	

Figure 65: False Color Encoding

11.1.5.3 Project

Project fps	Sets the timebase of the time code, which determines how many frames the time code counts per second. Also sets the frame rate of Quicktime clips recorded to **SxS PRO** cards during playback.
Camera index	Identifies camera unit in clips. Influences clip names on **SxS PRO** cards.
Next reel count	Counter assigned to the next new card used for recording. Automatically increased by the camera. Influences clip names on **SxS PRO** cards.
Production info	Redirects to a screen where the user can enter info metadata regarding the production.

Note: The user should set the value of reel counter to 001 before a shoot begins.



Figure 66: MENU>PROJECT

Production Info

The production info screen contains fields to enter info metadata regarding the production. The user can enter the names of the director, cinematographer, location and production. Furthermore, two fields allow entering undefined data the user would like to add.

Director	Enter the name of the director
Cinematographer	Enter the name of the cinematographer
Location	Enter the name of the location
Production	Enter the name of the production
User Info 1	Enter other info
User Info 2	Enter other info



Figure 67: Production info screen



Figure 68: Production info edit screen

11.1.5.4 System

Contains groups of system settings.



Figure 69: MENU>SYSTEM

Sensor

Sensor temperature	When shooting in tropical conditions with high temperature and humidity, the sensor temperature can be changed to "Tropical". This will avoid condensation on the sensor coverglass.
Mirror image horizontal	Mirrors the image horizontally on all image paths.



Power

BAT1 (Plug) warning	The level at which a power warning is exhibited for the power source connected to the BAT plug. Can be adjusted to match the used battery type. Default value is 21.0 V.
BAT2 (Onboard) warning	The level at which a power warning is exhibited for the onboard battery. Can be adjusted to match the used battery type. Default value is 12.0 V.

Note: At a level 10% below the set warning level, a battery error is emitted. This means that the power source is treated as insufficient to power the camera and recording is prohibited.



Figure 70: MENU>SYSTEM>POWER

Smart batteries that transmit their remaining load to the camera emit a warning at 10% remaining capacity and an error at 5% remaining capacity. Currently batteries by ID-X, Bebop, Anton Bauer and any battery using the TI-protocol support this feature.

External Sync

Eye index	The first letter of the Camera ID can be changed between L and R for stereoscopic productions to identify left and right eye camera. Influences naming of clips on **SxS** cards.
Sensor sync	The sensors of 2 ALEXA cameras can be synced. See *Sensor sync* (on page 118) for more info. • Off: The camera is in non-synced mode for regular use. • EXT master: The camera sends signals to an EXT SLAVE camera via the EXT connector containing sync clock and TC signals. • EXT slave: The camera listens on the EXT connector to signals from an EXT MASTER camera containing sync clock and TC signals.
HD out phase	The phase of the HD out can be adjusted in the range

	of -30 to +30 HD clocks (1 HD clock = 13.4 ns). This can be necessary for 3D applications with external recorders that require the slave signal to arrive after the master signal. Shift the phase backwards (+) on a slave camera or frontwards (-) on a master camera to achieve this behavior.
Send HD sync trigger	When using two cameras in sensor sync mode without settings sync, the EXT MASTER camera must send a trigger to the EXT SLAVE camera to ensure the HD outputs of the cameras are synced. Press the jogwheel to send the trigger.
Settings sync	ALEXA cameras can be operated in synced settings mode, where two cameras sync their settings via Ethernet. See *Settings sync* (on page 119) for more info.



Figure 71: MENU>SYSTEM>EXT SYNC

Test Signal

Color bar	Activates a SMPTE color bar on MON OUT and REC OUT. *Note: Color bar is switched off when recording is started.* *Note: When REC OUT is set to ARRIRAW, REC OUT is set to black while color bar is active.*
Enable test tone	Enables a 1 kHz test tone on all channels when color bar is active. *Note: Test tone is only active when audio recording is on and possible.*
Test tone level	Sets the level of the test tone. Available are -9 dB (FS), -18 dB (FS) and -20 dB (FS)



Figure 72: Test signal screen

Display + Beeper

Display brightness	Set the brightness of the camera right side LCD display. The brightness can also be adjusted when the Homescreen is active by turning the jogwheel while pressing the BACK button.
Button brightness	Set the brightness of the button illumination.
Run beeper mode	Set whether the run beeper shall beep at start or stop of recording, at both or not at all.



Figure 73: MENU>SYSTEM>DISPLAY

System Time + Date

Time	Shows the currently set time (read-only)
Date	Shows the currently set date (read-only)
Set time + date	Opens a screen whre time and date can be set
Time zone	Set time zone to match your current location

DST	Set daylight savings time

Set time + date



Figure 74: MENU>SYSTEM>CLOCK/DATE

Use the lower screen buttons to navigate between the elements in the screen and to finish your setting.



Figure 75: Set time + date screen

Fan

Fan mode	Set the fan mode to *Regular* for locations with ambient temperatures up to 30°C (86°F). If the ambient temperature gets higher, set it to *Rec low*.

SD card

Format + prepare SD card	Formats the SD card and creates the required folder structure after confirmation. *Note: This removes all data present on the SD card.*
Prepare SD card	Creates or completes the required folder structure on the SD card without touching any data present on the SD card.

WNA-1

The Wireless Network Adapter WNA-1 is a new accessory from ARRI that will soon be released and allows to connect a camera to a WLAN network.

Firmware

The camera firmware can be updated to enable new camera features. To update the camera firmware, store a SUP (Software Update Packet) file on the SD card and follow the instructions given with the SUP.

Select update file	If an SD card containing update files is inserted in the camera, you can select an update file from the list and perform an update. Start the update procedure by pressing the two lower outer screen buttons simultaneously.
Current version	Release code of currently installed firmware
Licensed features	Opens a screen where licenses for licensed features can be managed.

Note: DO NOT INTERRUPT THE UPDATE ONCE IT HAS STARTED. MAKE SURE THE CAMERA POWER SUPPLY WILL REMAIN SUFFICIENT FOR THE DURATION OF THE UPDATE (APP. 15 MINUTES).

Note: On rare occasions, the update process can fail. If the update procedure fails, try it again until you succeed.

Note: If **SxS** recording is switched off, switch it back on again before performing a firmware update.



Figure 76: MENU>SYSTEM>FIRMWARE

11.1.5.4.1.1 Licensed Features

Licensed features are camera functionalities that require a license key to be enabled. Licenses can be purchased through the ARRI ALEXA License webshop, which can be found at http://alshop.arri.de. A detailed instruction on how to purchase a license key can be found on the website.

License keys are linked to the camera serial number and cannot be transferred from one camera to another.

To order a license key, you must have the hardware info file of the camera for which you want to order the license key.

The INSTALLED LICENSES screen shows currently installed license keys for licensed features. New license keys located on the SD card can be installed by pressing the INSTALL button.



Figure 77: List of installed licenses

The license key file (suffix *.lic*) to be installed must be located on the SD card in the correct folder (folder *ARRI* >subfolder *ALEXA* >subfolder *Licenses*).

Note: Only license keys that have been created for the camera in use will appear in the SD card license list.

The list shows the file names in the SD card directory. Below the list the feature contained in the license key is displayed for the currently selected license key file.

Press the jogwheel to install the currently selected license on the camera.

License keys can be deleted from the camera to prevent the use of the feature. The license can be reinstalled at any later point in time. Press the DELETE button and select the license to be removed. Confirm the removal by pressing the jogwheel.

Note: Make sure to keep an offline copy of the license file! In case you lost a license file, you can reload it from your account in the license webshop.

To save the hardware info file of the camera, press the HW INFO button. The file will be saved to the SD card root directory, named *sn####-AlexaHardware.ipkg*.

11.1.5.5 Frame grabs

By pressing the GRAB button, or by assigning the function "Grab still frame" to one of the user buttons 1-3, a still image from the sensor can be stored on the SD card.

The images inherit the REC OUT color settings (Gamma + Look). If REC OUT is set to ARRIRAW, frame grabs are in .ari file format. For all other formats, users can choose from .jpg, .tif or .dpx file formats in this screen.

Grabbing an image can take up to 45 seconds, depending on the chosen file format. During this time, no further images can be grabbed.



Compare Grab 2 Live image

An image grabbed with the camera to the SD card can be reloaded to the camera and displayed on the EVF and MON OUT.

Note: Currently only JPEG images can be used for the compare function.

Load a grab by pressing the LOAD GRAB screen button. A list of all grabs on the SD card will appear. Select a grab and load it. When loading the image has finished, press the COMPARE screen button to activate the image on the selected image paths.



Figure 78: Compare screen

The OPTIONS button gives access to additional settings.

Compare mode	Interleave creates an interlaced image from the live image and the loaded image. Toggle only displays the laoded image.
Active on EVF	Sets the compare function on the EVF on or off.
Active on MON	Sets the compare function on the MON OUT on or off.

Note: The image quality on the MON OUT in interleave mode depends strongly on the connected display device. Displays with a resolution different from full HD (1920x1080) may show flickering images or other artifacts. This is not caused by the camera, but the display's electronics.

11.1.5.6 User Setups

In this section the user can store the current setup to the SD card or load previously stored setups from the SD card. An SD card must be present in the camera to perform these operations. Only complete camera setups can be stored or loaded!

Save current setup	A setup containing the current camera settings is stored to the SD card. File is named with time and date stamp.
Load setup	Loads a list with all setups located on the SD card. Select a setup and load it. Check that the project settings of this setup really match those of your current project.
Factory reset	Resets the camera to factory defaults. Confirm factory reset by pushing the two lower outer screen buttons simultaneously when the request appears.



Figure 79: MENU>SETUPS

Note: Before loading or saving a setup, make sure an SD card is present. When saving a setup, the write protection of the SD card must be switched off.

Note: User setups cannot be used across SUPs. Always create new setup files after a SUP update, and discard the old ones. The camera will block the usage of a user setup that has been created with a different SUP.

11.2 Operator controls

The operator controls are located on the camera left side and consist of three function buttons plus three assignable buttons.

1	User button 1. Can be assigned with functions through the USER button on the main UI.
2	User button 2. Can be assigned with functions through the USER button on the main UI.
3	User button 3. Can be assigned with functions through the USER button on the main UI.
REC	Starts and stops internal recording. LED tally goes red during record.
PLAY	Short press loads last clip. Short press again to toggle between play and pause. Press for 2 seconds to stop playback.
LOCK	Long pressing of the button locks the main and the operator controls. LED indicates if lock is active. Long pressing again deactivates the locking.

Figure 80: Operator UI

11.3 EVF Controls

The EVF controls are located on the electronic viewfinder. They consist of a number of function buttons and a jogwheel.

CAM	Opens the viewfinder CAM menu
EVF	Opens the viewfinder EVF menu.
ZOOM	Zooms into the image with a 2.25x magnification for focus checking. This results in matching one sensor pixel to one viewfinder pixel. Zoom button toggles zoom on and off. Active zoom is indicated by an orange frame around the image. Frame lines are deactivated while zoom is active.
EXP	Toggles false color display on and off.

The EVF buttons CAM and EVF are locked whith the camera UI. ZOOM and EXP are not affected by the lock. The controls are locked by pressing the LOCK button on the camera left or right side until the lock timer has elapsed. On the right side the timer is shown as a countdown on the display. The locked controls are visualized by a lock icon. On the left side the locked controls are visualized by a blue LED next to the LOCK button.

The EVF shows the info text "button is locked!" when a locked button is pressed.

11.3.1 Viewfinder EVF menu

Pushing the EVF button opens a menu in the viewfinder display to set the viewfinder parameters. Select the setting to be changed with the jogwheel, press the wheel and set it to the desired value. Press again to confirm. To quit the menu, press the EVF button.

Brightness	Select the brightness of the EVF. A level of 5 is recommended for normal circumstances.

Rotate image	When mounting the EVF on the camera right side, the image can be flipped so it appears upright in the viewfinder. Affects only the EVF image, MON OUT and REC OUT are not affected!
Smooth mode	With smooth mode set, the EVF image shutters less when panning. Note that smooth mode is only possible with shutter angles of 180.0 or less.
Surround view	The ALEV III sensor has 10% additional pixels outside the recorded image for a better monitoring experience. The user can decide whether he wants to see these 10% in the viewfinder or not. By switching surround view on, objects that are not wanted in the image, such as microphone booms, can be seen by the operator before they enter the image.
Surround mask	If surround view is set to "On", it must be separated from the recorded image area to allow proper framing. Users can choose from different mask levels, or a black oir colored line for separation.
Status info	At the upper and lower edge of the EVF, right outside the active image area, additional status info can be displayed. The upper area contains camera image parameters, the lower area contains camera status infos.
Framelines	Frame lines are a reference for framing that typically consist of an image frame, a center cross and an aspect ratio reference. See the appendix for more information on the ALEXA frame line format.
Select framelines 1	Choose the main frame lines template from those stored in the camera.
Select framelines 2	Choose the secondary frame lines template from those stored in the camera.
Center mark	A center mark, either a cross or a dot can be added to the image to help the framing.
User rectangles	Display up to two additional recangles that can be set in the EVF.
Edit user rectangles	Adjust the user rectangles visually.
Framelines color	Change the color of the frame lines.
Framelines intensity	Change the brightness of the frame lines.

11.3.2 Viewfinder CAM menu

Pressing the CAM button on the viewfinder opens the cam menu in the viewfinder display. The settings displayed in the top bar section of the viewfinder can be adjusted.

FPS	Sensor fps. Settings of the FPS list can be loaded.
SHUTTER	Shutter angle. Settings of the Shutter list can be loaded.
EI	Exposure index. Settings from EI 160 to EI 3200 can be loaded, in steps of 1/3 stop.
WB	White Balance. Settings from WB list can be loaded.

The values that can be chosen mirror the content of the respective lists in the main UI. Select the setting to be changed with the jogwheel, press the jogwheel to open the list. Select a list value and press the jogwheel again. To quit the menu, press the CAM button.

12 Operation of The Camera

This chapter describes what has to be done overall to perform a certain task. It contains the necessary hardware setup and camera configuration to perform the task.

12.1 Recording

12.1.1 Internal recording

This chapter contains in formation and recommendations for recording with **SxS PRO** cards. The user is of course free to modify the recommended worksteps to his needs.

Note: ARRI cannot be held responsible for the loss of any data in conjunction with internal recording!

ALEXA can internally record on Sony **SXS PRO** cards. These cards have an ExpressCard34 form factor and are currently available with 8, 16 or 32 GB storage space.

Card file format

SxS PRO cards have to be formatted in the camera before they can be used for recording. ALEXA uses an UDF file system. This file system is read-only for computers, which means data can be copied from the card to another device, but the data cannot be manipulated on the card itself.

Card preparation

The typical usage cycle of a card is: Format - Record - Copy - Backup - Verification - Format

Format	Before recording, cards have to be formatted in the camera. The camera always performs a blank format, which means that the cards contain no meta data and are not assigned a reel number prior to recording the first clip. The camera auto-detects cards with a wrong file system and asks the user to format the card. ALEXA uses an UDF file system. This file system is read-only for computer systems, which minimizes the risk of data corruption.
Record	When pressing the REC button, the camera starts to write a clip to the card. With the first clip, the card is a assigned a reel number. More information on file naming later in this chapter.
Copy	After recording to the card is finished, either because it is full, or for any other reason, the data should be copied to another device to minimize the risk of data loss. Also, the data should be verified after copying through checksums to ensure that no error has occured during the copy process.
Backup	The data should actually be copied to two physically separate destinations, with the first copy being the "working copy", and the second copy being the "Backup". These two copy processes can be done in parallel, as long as the result are two independent devices containing the verified data.
Format	Only when the data has been copied and verified to two independent devices, the card should be formatted to remove all data from it. It is also recommended that the card is formatted by the person that has verified the copy and backup, so that the camera crew only receives empty cards. This fuctions as a security check, so that the crew is alerted if they receive a card with valid data on it, which might not have been copied and backed up. The card can be formatted with any file system, as it has to be reformatted by the camera anyway.

Codec

ALEXA can record both Apple ProRes™ as Quicktime files and Avid DNxHD as MXF (OP1A) files.

Note: Recording in Avid DNxHD requires license key.

The Apple ProRes™ codec family consists of 5 different codecs:

Name	Color coding	Data rate @ 30 fps	Recording time on 32 GB SxS PRO @ 30 fps[3]	max. frame rate[2]
ProRes 422 (Proxy)	YCbCr	45 Mb/s	1 h 23 min	60 fps
ProRes 422 (LT)	YCbCr	102 Mb/s	37 min	60 fps
ProRes 422	YCbCr	147 Mb/s	25 min	60 fps
ProRes 422 (HQ)	YCbCr	220 Mb/s	17 min	60 fps
ProRes 4444[1]	RGB*	330 Mb/s[1]	11 min	40 fps

[1]Without alpha channel (444 only)

[2]The maximum frame rate is also limited my the write speed of the **SxS PRO** card in use, which might reduce the maximum frame rate below the values given in the table.

[3]Apple ProRes™ is a VBR (variable bit rate) codec. This means that the actually available recording time depends on the image content. The number given in the table is the MINUMUM available recording time for a 32 GB **SxS PRO** card. When image content is easily compressable without loss of image quality, the available recording time can exceed the number given in the table.

Also note that the available recording time is given for a 32 GB **SxS PRO** card at 30 fps. A lower sensor fps will increase the available recording time, while a higher sensor fps will decrease it.

The following Avid DNxHD codecs are available on ALEXA (when required license key is installed):

Name	Color coding	Data rate @ 29.97 fps	Recording time on 32 GB SxS PRO @ 29.97 fps	max. frame rate[2]
DNxHD 115/120/ 145	YCbCr	145 Mb/s	29 min	60 fps

DNxHD 175x/185x/ 220x	YCbCr	220 Mb/s	19 min	60 fps

DNxHD 115/120/145 has a bit depth of 8 bit. DnxHD 175x/185x/220x has a bit depth of 10 bit.

DNxHD is a FBR (fixed bitrate codec), the codec naming differs with the project frame rate. Lowest number is for 23.976/24 fps, middle number for 25 fps and highest number for 29.97 fps. 30 fps project frame rate is not available with DNxHD. The given recording time does not depend on the image content.

[2]The maximum frame rate is also limited my the write speed of the **SxS PRO** card in use, which might reduce the maximum frame rate below the values given in the table.

Choosing a codec

Selecting the codec that fits best for the shoot is a crucial task. Choosing a codec with a high data rate, such as ProRes 4444, delivers the highest image quality, but at the same time lowers the available recording time on an **SxS** card.

ProRes 422 (Proxy)	On-set monitoring and proxy editing while the master is captured with an external device.
ProRes 422 (LT)	Same as above when higher image quality is desired.
ProRes 422	Basic television application, if images do not require adjustments in post production.
ProRes 422 (HQ)	High quality TV applications requiring color correction.
ProRes 4444	Cinema applications requiring color correction and pulling mattes.
DNxHD 115/120/145	Basic television application, if images do not require adjustments in post production.
DNxHD 175x/185x/220x	High quality TV applications requiring color correction.

If possible, the full workflow pipeline with the preferred codec should be tested before a shoot.

Card file format

SxS PRO cards have to be formatted in the camera before they can be used for recording. ALEXA uses an UDF file system. This file system is read-only for computers, which means data can be copied from the card to another device, but the data cannot be manipulated on the card itself.

CARD file structure

SxS cards are named ARRI UDF after they are formatted in the camera until the first clip is record. Clips are stored in a folder named exactly like the card. In addition to the clips, an XML file named like the card and the folder extended by _FCP (example: A001R1JL_FCP.xml) is created by the camera. The XML file is according to the FinalCutPro XML specification. If the XML file is opened in FinalCutPro directly from the card, all clips are imported as one bin into FCP. If the clips are copied from the card to another destination, the file paths in the XML file have to be adjusted to match the new file location.



Figure 81: Screenshot of ALEXA SxS card under Mac OS X

File naming scheme

ALEXA automatically names files as they are created on the **SxS** card. While it is possible to change the file names later on a computer, it is not recommended, as the ALEXA naming scheme has been developed to minimize the risk of duplicate file names.

The file name consists of 6 parts:

- Camera Index: One character, A-Z. User assignable, should match the camera unit.

- Reel Counter: 3 characters, 001-999. Auto-assigned to each card, increased by one for each new card. The user can change the counter to be given to the next card. This should only be done on special occasions, like after changing the camera body in the middle of a shoot.
- Clip Index: One character, fixed to C. Main use is to separate the reel counter from the clip counter. If more than 999 clips are recorded to one card (not likely to happen), it changes to D.
- Date: Current date, in order YYYYMMDD, as set in Menu>System/Time/Date
- Camera ID: Consists of a 1 letter prefix, user adustable between R and L, and the camera serial number encoded in 3 letters Base36 (0-9, A-Z).

The date is separated by underscores at the start and the end.

The reel counter shall be set to 001 at the start of a shoot. The camera will then automatically increase the reel counter whenever a card is recorded for the first time after formatting. If a previously recorded card is used again (comparable to a short end of a film roll), this card will keep its reel count and the camera will remember how far it has counted. If the reel counter has to be changed by the user, it can be done via Menu>Project>Next reel count. Note that this is only recommended for special occasions.

Example

A typical file name could look like this:

A004C010_20100610_R1JL.mov for ProRes/Quicktime or
A004C010_20100610_R1JL.mxf for DNxHD/MXF.

What it tells the user is that this clip was the tenth clip recorded on the fourth card used. It was recorded on the 10th of June 2010, and the camera had the Base 36 serial number 1JL, which translates into the decimal serial number 2001 (Plenty of Base 36 to decimal converters can be found on the Internet, for example here: *http://www.translatorscafe.com/cafe/units-converter/numbers/calculator/decimal-to-base-36/*).

Additional recommendations

To ensure correct card handling and reduce the risk of data loss, ARRI recommends the following procedure for card and data handling:

- Pre-format cards. Format all available cards in the camera before the shoot starts. This reduces downtime during production caused by the need to format. Cards do not receive a reel counter before the first clip is recorded to them, so there is no need to record the cards in a certain order. Formatting a 32 GB card usually takes less than 10 seconds.

- Limit card recording time. Codecs with lower data rates like ProRes 422 (Proxy) can be recorded for quite a duration onto **SxS PRO** cards with high capacities. Users should consider limiting the recording time per card to a maximum of 30 minutes of material as it is easier to handle and reduces the impact on the production in case of a problem.
- Immediately copy the data after a card change. The data should be in a single instance for the shortest time possible.
- Switch on write protection when a card has been recorded and is sent to the copy instance.
- Switch off write protection when data has been copied and backed up, then format the card.

Metadata

Metadata is stored in the index.xml file as well as the quicktime file header. Most important for the post production workflow is the tape name, as it will be one of the main image identifiers in an EDL. Even though tape name is not quite a good name for nonlinear media, it is used due to post production naming conventions. Alternatively, reel name is used sometimes.

The tape name of ALEXA files is limited to 8 letters to match the CMX 3600 EDL standard. It consists of the Camera Index, reel counter and the Camera ID.

The tape name of the clip from the previous example would then be: A004R1JL.

Even if the user forgets to assign different camera indices to two cameras on one shoot, the Camera ID guarantees unique tape names.

Currently one time code track is recorded in the Quicktime file.

Dual recording

Dual recording allows to record in parallel to two **SxS PRO** cards to create an instant backup at the time of recording. To enable dual recording, go to MENU>Recording>SxS CARDS and set "Dual recording" to "On".

Take care of the following points to ensure successfull dual recording:

- **SxS PRO** cards must be of identical size
- For a new reel, both cards must be formatted
- Cards must have an identical file structure

The best way to ensure this is to follow the rules for regular recording, but with sets of two cards. After recording, one card can be used for the backup process, and the other card for the copy process.

12.1.2 External recording

Uncompressed HD and unprocessed ARRIRAW data is available via the REC OUT for recording with external devices.

The preferred output format also depends on the application. As a rule of thumb, the following guideline can be used:

- 422 1.5G: Television applications that only require color correction, high-speed capture above 30 fps
- 444 1.5G: High-quality television applications that require color correction and pulling mattes, cinema applications
- ARRIRAW: High-quality cinema applications for multi-format distribution

422 1.5G YCbCr

422 is a color sub-sampled format, meaning that the camera-native RGB image is transformed to YCbCr color space. Y represenst luminance, while Cb and Cr are color difference signals. These are sampled with only half the horizontal resolution, as the human eye is less sensitive to color resolution than to luminance resolution. As a result, bandwidth is saved in transmission while receiving good visual results.

For frame rates up to 30 fps, 422 1.5G is transmitted over 1 HD-SDI cable. REC OUT "A" and "B" carry the identical signal independently. Frame rates higher than 30 fps require 2 cables, and the image signal is carried by REC OUT "A" and "B" combined.

422 3G YCbCr

3G is an improved HD-SDI format that can transmit signals over 1 cable which previously required two cables. It transports the same signal as 422 1.5G YCbCr dual link, but over one cable with a higher clock rate. REC OUT "A" and "B" carry the identical signal independently.

444 1.5G RGB

444 is still in the RGB color space, and each color has its full reolution. This is important when pulling chroma keys, as these rely on color resolution.

444 1.5G is transmitted over 2 HD-SDI cables, where each of both links carries a part of the image data. It is important to

- connect REC OUT "A" of the camera with REC IN "A" and REC OUT "B" of the camera with REC IN "B" of the recorder
- use cables of equivalent lengths for link A and B

444 3G RGB

Two iterations exist of the 444 3G signal.

- The single link version contains the same signal as the 444 1.5G signal, but according to SMPTE 425M over one cable.
- The dual link version uses a proprietary image mapping for frame rates from 30 to 60 fps, and is only supported by certain recorders at this point of time.

ARRIRAW 1.5G DL

ARRIRAW is the name of raw data from ARRI cameras. Raw data is the sensor image data before it is converted to RGB images. As ALEXA has a single sensor with a Bayer pattern color filter array, this means that every pixel only has information of one color channel.

With normal HD images, the missing color channel information is calculated from the adjacent pixels in the camera.

For raw data, this calculation is delayed until after the recording to save bandwidth and creative options, as many decisions on how to convert the images can be made in post.

ALEXA ARRIRAW specs:

- Bayer pattern color coding
- 12 bit log luminance coding
- No white balance applied
- No exposure index applied
- Full sensor resolution (2880x1620)

ARRIRAW is transmitted to the recorder via the ARRIRAW T-Link by using a standard HD-SDI dual link connection with a proprietary coding. The HD-SDI wrapping signal is according to SMPTE 372M.

An ARRIRAW T-Link certified recorder must be used for recording. These are available from a number of manufacturers like Codex, Keisuko Giken or S.Two.

For more information, go to www.arri.de/arriraw

ARRIRAW 3G SL

The ARRIRAW 3G SL signal format uses a HD-SDI wrapping signal format according to SMPTE 425M. It is basically the same signal as ARRIRAW 1.5G DL, but utilizes only one cable.

ARRIRAW 3G DL

This output format is fully proprietary and does not follow SMPTE standards. It is used to transmit ARRIRAW with frame rates from 30 to 60 fps.

Note: Only use double shielded HD-SDI cables on all HD-SDI outputs to ensure error free data transmission!

Triggering record on an external recorder

When "SxS recording" is set to *Off,* the REC button triggers only the SDI rec flag. If the recorder understands this flag, it will automatically start to record.

Note: With the SDI rec flag, sucessfull recording cannot be guaranteed, as there is no feedback from the recorder to the camera.

12.1.3 Parallel recording

Recording to both **SxS PRO** cards and external devics at the same time requires additional attention from the user. First, it has to be determined what function the two sets of data have. For example, the internal recording could be used for on-set review and proxy editing, while the external device captures the master data. Or the internal recording is used for TV utilization and the external recorder captures ARRIRAW for cinematic use.

Remote controlling the external recorder

By activating the "SDI remote" in the REC OUT menu screen, it is possible to control external recorders if they support this feature. When "SxS recording" is set to *On*, this is only possible while recording to an **SxS PRO** card.

Note: There is no feedback channel providing information to the camera if the external recording is active - make sure to check the external recorder directly!

Timecode on external recorders

To guarantee the same Timecode for images that are parallely record internally and exterally, set the external recorder so that it uses the TC embedded in the HD-SDI stream coming from the camera.

12.1.4 High Speed recording

With a valid High Speed license key installed, the camera can be switched into High Speed mode. In High Speed mode, the camera can be operated at frame rates of 60-120 fps. Recording is only possible on **Sony SxS PRO** cards with ProRes™ codecs up to ProRes 422 HQ. ProRes 4444 is not available in High Speed mode.

It is highly recommended to use **Sony SxS PRO 64 GB** cards, as only this card type achieves the required write speeds.

The following table shows the achievable frame rates with the different **SxS PRO** card types.

	Regular Speed mode	High Speed mode

Codec	**SxS PRO 8-32 GB**	**SxS PRO 64 GB**	**SxS PRO 8-32 GB**	**SxS PRO 64 GB**
ProRes 422 Proxy	60 fps	60 fps	120 fps	120 fps
ProRes 422 LT	60 fps	60 fps	120 fps	120 fps
ProRes 422	60 fps	60 fps	60 fps	120 fps
ProRes 422 HQ	60 fps	60 fps	60 fps	120 fps
ProRes 4444	40 fps	60 fps	---	---
DNxHD 115/120/145[1]	60 fps	60 fps	60 fps	120 fps
DNxHD 175x/185x/220x[1]	60 fps	60 fps	60 fps	120 fps

[1]requires DNxHD license key to be installed on camera.

The REC OUT carries the same signal as the MON OUT during High Speed mode.

Note: Camera boot time is increased by app. 40 seconds when High Speed mode is activated.

12.2 Monitoring

The electronic viewfinder and the MON OUT can be used for monitoring purposes. They can both display the surround view area, an extra 10% of image outside the recorded area to track any unwanted objects before they enter the image.

To help the framing, both EVF-1 and MON OUT can overlay frame lines to the image. These frame lines are an electronic version of the ground glass of analog cameras.

12.2.1 Frame Lines

Frame lines are stored as XML files. A standard set of frame lines is stored in each camera. In addition, the user can create personal frame lines matching his preferences.

Once the idea behind the frame lines system is understood, personal frame lines can be created with little effort.

Description

The different sections in the file are:

- camera: describes the camera that the frame lines file is made for. As the ALEXA camera system will consist of several cameras in the future, this is necessary to differentiate between the camera types.
- line: all frame lines and the center cross in the active image area consist of single lines. The line orientation is defined by three attributes (left and right and bottom or top for horizontal lines, top and bottom and left or right for vertical lines), where two attributes define the start and end point, and the third defines the distance from the parallel image edge.
- Distances for start, end and position are relative to the width or the height of the image and have a precision of 5.
- To create a centered frame line with a center cross as in the example, a total of 6 lines is necessary.
- To calculate the position of a line for a given aspect ratio, use the following formulas:
  - horizontal lines for aspect ratios >1.78 (e.g. 1.85): [1-(1.78/Aspect)]/2=distance from bottom or top
  - vertical lines for aspect ratios <1.78 (e.g. 1.33): [1-(Aspect/1.78)]/2=distance from left or right

XML example

The best way to understand the frame lines system is by looking at an example. The following example describes a frame lines file for a 2.35 centered aspect ratio inside the cameras 1.78 recorded image.

```
<?xml version="1.0" encoding="UTF-8"?>
<!-- NOTES:
       All widths are in pixels.
       All colors can be one of: black, white, or user.
       If you select user, the color can be changed through
       the user interface.
       You can add as many lines as you like. Lines are
       defined by giving 3 distances from the border.
       So if you specify top, left and right it will
       be a horizontal line with the given distance
       from left, right and from the top.
       The values are in the range [0, 1], where:
               0 is at the edge
               1 is on the opposite edge
       So specifing 0.4 from left is the same as 0.6 from right.
-->
<framelines>
       <!-- The description of the camera, this will
            only be used for selecting the correct files.
            So the user can only select glasses for his
           camera/current setup. -->
       <camera>
               <type>Alexa EV</type>
               <sensor>3K</sensor>
               <aspect>1.78</aspect>
               <hres>2880</hres>
               <vres>1620</vres>
       </camera>

       <!--user color line at top and bottom of 2.35 aspect-->
       <line>
               <left>0</left>
               <top>0.12174</top>
               <right>0</right>
               <width>4</width>
               <color>user</color>
       </line>
       <line>
               <left>0</left>
               <bottom>0.12174</bottom>
               <right>0</right>
               <width>4</width>
               <color>user</color>
       </line>

       <!-- Center cross horizontal lines, user color -->
       <line>
               <left>0.46355</left>
               <top>0.5</top>
               <right>0.50868</right>
               <width>4</width>
               <color>user</color>
       </line>
       <line>
               <left>0.50868</left>
               <top>0.5</top>
               <right>0.46335</right>
               <width>4</width>
               <color>user</color>
       </line>
       <!-- Center cross vertical lines, user color -->
       <line>
               <left>0.5</left>
```

```
                <top>0.43519</top>
                <bottom>0.51543</bottom>
                <width>4</width>
                <color>user</color>
        </line>
        <line>
                <left>0.5</left>
                <top>0.51543</top>
                <bottom>0.43519</bottom>
                <width>4</width>
                <color>user</color>
        </line>
</framelines>
```

12.3 Using Time Code

The purpose of Time code is to ensure that each image stored on one medium has a unique value through which it can be identified. By doing this in combination with correct reel naming, which is toi ensure that each storage medium used in a production has a unique name, each image acquired in a production can be identified uniquely.

There are many different ways how Timecode can be used in a production. The 2 most common ways are presented as examples.

External TC, Time of day

- Use: This format is often used on multi-camera productions with sync-sound. The cameras are running on a sync-sound speed, which is also the project frame rate. if done correctly, sound and image time code should match and allow an easy alignment in post.
- Setup: The sound department acts as the Time code master, and generates a Timecode which uses the Time of day as a value, and the time base is the project frame rate. 24 hours of time will translate into 24 hours of Time code.

  This Time code is fed to the camera via the LTC in. The camera must be set to Ext LTC Free Run, and the project fps setting must match both the sensor frame rate and the time base of the external TC signal. Then the camera can either use Jam sync mode, in which it samples the TC value once and then continues counting based on its own high-precision crystal clock, and the TC signal can be disconnected from the camera after jamming. This mode ensures stable time code with an offset of less than 1 frame for 8 hours, after which the camera has to be re-jammed. Or the camera can be set to Regenerate mode, where the camera uses the TC value of the external TC signal. This ensures correct CT for an infinite duration, but the TC signal must remain connected to the camera.
- Variations: If the shooting starts close to midnight, the TC might be started with an offset to prevent a rollover at midnight.

- Restrictions: Only possible if the camera is running at sync-sound speed. If the camera is over- or under-cranking, the TC frame rate will no longer match the sensor frame rate, so that TC values would either be duplicate or dropped. Due to this reason, the camera will automatically switch to Int TC Regen, when the sensor frame rate is changed.

Internal TC, Rec Run

- Use: Single camera productions, either MOS or where a classical slate is used for alignment of image and sound. Guarantees continuous time code for each storage medium. Works alos with over- and under-cranking.
- Setup: The camera is set to Int TC Rec Run Regen. TC is only increased during record by 1 frame for each image generated by the sensor. The TC counts with the project fps set on the camera as time base. Normally, the TC hour value is increased by 1 hour for each new reel, usiong only hours 01-20 for reel 1-20, and then restarting at hour 01 for reel 21.
- Variations: Might be used on a production normally using external TC for high-speed scenes, then returning to Ext TC for regular scenes later.
- Restrictions: None.

12.4 Syncing the Sensors of Two Cameras

For 3D applications or shoots where it is necessary to synchronize the sensors of two cameras so that images are exposed at the exact same time, it its possible to sync two ALEXAs through their EXT connectors via cable.

Note: Syncing two sensors is possible in an fps range from 1.000 to 60.000 fps

First, the cameras have to be connected with an EXT cable (type: KC 155-S). After this, the sensor sync mode has to be activated. This is done in MENU>SYSTEM>EXT SYNC>Sensor sync. One camera has to be set as EXT master, and the other camera as EXT slave.

The master triggers the slave camera so that images are created at the same moment of time with an accuracy of 10 µs. After connecting both cameras and activating the correct sensor sync modes, this takes about five seconds. If any error occurs, the camera issues a warning.

Image integration between master and slave camera has a locked offset of less than 10µs. This means that in the worst case, exposure differs by 4.3 % (@ 60 fps frame rate and 5.0° shutter angle). With a regular exposure time (24 fps, 172.8°), the maximum difference is 0.05 %.

Synchronizing Image Output

The output of images both on the REC OUT and the MON OUT can be synchronized, too. To achieve this, the user must send a trigger from the master camera to the slave camera after sensor sync is established.

This is done by selecting "Send HD sync trigger" in the EXT SYNC menu screen. When pressing the jogwheel, the trigger is sent. The slave camera will then no longer display the warning "HD outs not synced. Trigger now!".

If the two camera's settings are synced over Ethernet, the trigger is automatically sent.

When the outputs are synced, jitter between the two camera's HD outputs is less than 500 ns. The HD output of a camera can be pre- or delayed by 30 HD clocks (1 HD clock= 13.46 ns), allowing for a total shift of 60 HD clocks (808 ns total) between cameras, if desired.

Timecode

Timecode is also transmitted from the master to the slave via the EXT cable. When a camera has been set to slave, it automatically uses the TC values transmitted via the EXT cable. The TC screen will show "EXT TC from master camera" as TC source, and all options are disabled.

Note: When the mirror shutter is switched on, an ALEXA Studio can only be synced to another ALEXA Studio.

12.5 Syncing the Settings of Two Cameras

It is possible to operate two ALEXAs with synchronized settings. It is recommended to do this only with cameras of the same type, e.g. two ALEXA Plus.

Camera connection

Connect two ALEXAs with the ALEXA Ethernet/Ethernet Cable KC 156-S, or with the ALEXA Ethernet/RJ-45 Cable KC 153-S over an Ethernet hub.

Camera setup

Go to MENU>SYSTEM>EXT SYNC, and set "Settings sync" to "ETH master" on one camera. Set the other camera to "ETH slave".

The cameras will automatically negotiate IP addresses. After about 5 seconds, connections are established.

The master camera will initially distribute its settings to the slave camera. Once this is done, settings can also be changed on the slave camera, and the change will take effect on both cameras. This is useful if the master camera's controls are not accessible.

If a camera is set to ETH master or ETH slave, but is not connected to another camera, a warning is emitted on the STATUS Info screen.

Synced settings

This is a list of all settings that are affected by the sync:

WB>White Balance + CC Tint

EI>Exposure Index

FPS>Sensor FPS

FPS>HIGH SPEED>High Speed mode[2]

SHUTTER>Shutter Angle

COLOR>Gamma>SxS

COLOR>Gamma>REC OUT

COLOR>Gamma>MON OUT

COLOR>Gamma>REC OUT

COLOR>Gamma>EVF

COLOR>Gamma>LOG C film matrix

MENU>Recording>SxS>SxS Recording

MENU>Recording>SxS>SxS Codec

MENU>Recording>SxS>High Speed codec[2]

MENU>Recording>SxS>Dual recording

MENU>Recording>REC OUT>Frame rate

MENU>Recording>REC OUT>HD-SDI format

MENU>Recording>REC OUT>Scan format

MENU>Recording>REC OUT>Output range

MENU>Recording>REC OUT>REC OUT fps sets sensor fps

MENU>Recording>REC OUT>SDI remote

MENU>Recording>REC OUT>Vari flag

MENU>Monitoring>EVF>Status info

MENU>Monitoring>EVF>Surround view

MENU>Monitoring>EVF>Surround mask

MENU>Monitoring>EVF>Framelines

MENU>Monitoring>EVF>Anamorphic desqueeze*

MENU>Monitoring>MON OUT>Frame rate

MENU>Monitoring>MON OUT>Scan format

MENU>Monitoring>MON OUT>Status info

MENU>Monitoring>MON OUT>Surround view

MENU>Monitoring>MON OUT>Surround mask

MENU>Monitoring>MON OUT>Framelines

MENU>Monitoring>MON OUT>Anamorphic desqueeze[1]

MENU>Project>Project fps

In addition, the slave camera takes over the Camera ID of the master camera, so file names are identical except for the Camera ID prefix. It is important to give the master and the slave camera different Camera ID prefixes to prevent duplicate file names.

[1]Valid license for anamorphic desqueeze must be installed on both cameras.

[2]Valid license for SxS High Speed recording must be installed on both cameras

12.6 Sensor modes 16:9 and 4:3

The ALEXA M, ALEXA Plus 4:3 and the ALEXA Studio have ALEV III sensors that can be operated in 16:9 and 4:3 mode.

Note: ALEXA and ALEXA Plus can only be operated in 16:9 mode.

To change the sensor mode, go to MENU>System>Sensor. The first line reads 'Sensor mode' and shows the currently active mode.



To switch the mode, select the first line and press the jogwheel.

In the next screen, confirm the switch by doublepressing the two lower outer screen buttons.



This will trigger the loading process, which is monitored by a progress screen similar to the SUP update screen. The loading process takes about 30 seconds. When it has finished, a reboot must be triggered by the user.

Note: Switching from 16:9 to 4:3 and vice versa always triggers a factory reset.

In 4:3 mode, a few restrictions apply to the camera system:

- SxS module is shut down. Recording is currently only possible with external ARRIRAW recorder.
- The REC OUT can only be set to ARRIRAW formats.
- No High Speed mode is available with 4:3 sensor mode. When switching to High Speed mode, the sensor is always operated in 16:9.

The currently active sensor mode can also be checked at INFO>SYSTEM.

13 ALEXA Plus

13.1 General Description

The ALEXA Plus has an extended electronic side cover that offers the following additional functions over the standard ALEXA:

- Built-in radio modem for wireless remote control of lens and camera.
- A level sensor to determine the camera's tilt and roll degrees.
- Three CLM ports for driving CLM-2 or CLM-3 motors.
- Two LCS bus interfaces for connecting WCU-3, WHA-3 and ZMU-3 hand units
- LDS Lens Data System for reading lens data from LDS lenses
- Depth of field calculation for LDS lenses and LDA lenses in combination with calibrated lens motors
- LDD (Lens Data Display) interface
- Lens Adapter PL Mount LA-PL-2 with LDS support
- Control of LDS, radio, and lens motors through the camera user interface.
- A third RS socket.
- A second MON OUT connector.
- An additional function button labeled WRS. It gives access to the WRS screen, from where all camera settings related to the Plus camera features can be handled.

Any ALEXA can be upgraded to an ALEXA Plus by installing the Plus module.

Note: The Plus module must be installed by an authorized ARRI service center.

Figure 82: CLM sockets

Figure 83: ALEXA Plus connectors

13.2 Optics

13.2.1 Lens Adapter PL-Mount LA-PL-2 (with LDS)

The lens mount of the ALEXA Plus supports the ARRI Lens Data System. The LDS lens must be mounted in the 12 o'clock or 3 o'clock position to enable the LDS functions. Take great care not to harm any elements of the LDS contacts on either lens or camera when attaching or deattaching a lens or lens port cover.

Besides the LDS feature, the same rules as with the LA-PL-1 LA-PL-1 apply.



Figure 84: Lens adapter PL-Mount LA-PL-2 (with LDS)

13.3 Radio System

A radio unit is incorporated into the ALEXA Plus module. This enables wireless communication of lens control and lens data information as well as remote control of basic camera functions.

Yellow radio

The ALEXA Plus can be equipped with yellow radio. This radio system has also been in use with ARRI film cameras, so it is an interesting option for rentals that already own equipment with yellow radio. Yellow radio can be identified by a yellow ring at the antenna mount pont.

Note: Only a limited supply of yellow radio units is still available. Yellow radio is no longer produced and approaches will no longer be available once all existing units are sold.

Channel	Frequency
1,3,5,6	2.406 - 2.435 GHz (Low band)
0,2,4,6,8	2.444 - 2.472 GHz (High band)

Note: only odd numbered channels are legally permitted in France!

White radio

White radio is the standard radio system for the ALEXA Plus. It has 8 available channels. White radio can be identified by a white ring at the antenna mount point.

Channel	Frequency
0	2.410 GHZ
1	2.415 GHZ
2	2.430 GHZ
3	2.435 GHZ
4	2.450 GHZ
5	2.455 GHZ
6	2.470 GHZ
7	2.475 GHZ

Within one radio network of camera and hand units white radio and yellow radio cannot be mixed. In general, it is possible to use both systems in different radio networks in parallel.

Up to three hand units can be connected to one camera in parallel to form a radio network.

Note: When a camera is set to "Sensor sync: EXT slave", its radio module automatically switches itself off, and the camera receives CLM control commands from the Master camera via the EXT cable.

13.4 Wireless Remote System

13.4.1 Lens Motors

CLM-2 and CLM-3 motors can be used with the ALEXA PLUS. CLM-1 motors are not supported. CLM-2 and CLM-3 motors can be used in a mixed setup.

Note: Use only one lens motor per lens axis.

Lens motors should be connected, according to their position on the lens, to the IRIS, FOCUS and ZOOM sockets on the camera's right side.

Motor calibration

After connecting a lens motor to the camera and the lens axis, it must be calibrated. Every time a lens motor has been deattached from the lens, it must be recalibrated after reattachment. When CLM-2 or CLM-3 motors are used, the camera will ask the user to calibrate the lens motors after booting the camera. As a lens change or a change of the motor position during power down would invalidate the calibration, the high motor torque of the CLM-3 could damage the lens when driving with high force against the limit of a lens axis. If the user is sure that no changes where made to the lens and motor setup, he can skip this step.

Motor direction

The direction of the CLM-2 and CLM-3 motors can be changed in the camera settings.

Motor torque

For CLM-3 motors, the motor torque can be adjusted in the camera settings.

Note: Make sure the motor torque level matches the current lens to avoid lens damage.

3D lens sync

When two ALEXA Plus cameras are set Sensor sync EXT master and EXT slave, the slave camera will switch off its radio module and receive motor control commands from the master camera via the EXT connection.

Note: The matching of the master and slave cameras lens ring positions depends on the mechanical accuracy and matching of the lenses. make sure the lenses in use are matched as good as possible.

13.4.2 Hand Units

For detailed unformation of the hand units, please refer to the device's own manuals.

Wireless Compact Unit WCU-3

The WCU-3 is a compact hand unit featuring a radio system to connect to the camera wirelessly. It has two LCS ports for connecting the device to the camera via cable and to attach a ZMU-3. A wheel and a slider can be used to control focus and iris axes. Zoom axis can be controlled by attaching a ZMU-3 at an LCS port.

The WCU-3 also has a display where it shows current fps, shutter angle, exposure index and white balance of the camera.

Wireless Main Unit WMU-3

The WMU-3 is a radio system for wireless connection to the camera. Both WFU-3 and WZU-3 can be attached to the WMU-3.

Wireless Focus Unit WFU-3

The WFU-3 has a knob and a slider that can be used to control focus and iris axes. It connects to the camera through a WMU-3 or a WHA-3.

Wireless Zoom Unit WZU-3

The WZU-3 controls the zoom axis. It connects to the camera through a WMU-3 or a WHA-3.

Wired Hand Adapter WHA-3

The WHA-3 allows both WFU-3 and WZU-3 to connect to the camera via cable.

Zoom Main Unit ZMU-3

The ZMU-3 controls the the zoom axis. It can be connected to the camera via cable to an LCS port, or via cable through an LCS port of an WCU-3, or wirelessly by using a WZE-3.

Wireless Zoom Extension WZE-3

The WZE-3 is a radio system that enables direct wireless connection of a ZMU-3 and a camera.

Hand Unit Priorization

Different priority levels are assigned to the hand unit devices to ensure only one device has control over a motor at a time.

A device's knob that is assigned to an axis has a higher priority than a device's slider assigned to the same axis. When steering items of the same type are assigned to the same axis, the one connected via WRS has highest priority, second highest priority has a device cable on the upper LCS port, the lower LCS port has the lowest priority. Of two radio devices with the same steering items assigned to the same axis, the one that connects to the camera first gains control.

Cabled devices can gain control of an axis at the time of connection. Wireless devices must be rebooted if an axis has become idle before they can gain control.

Exceptions to the rule are devices on the zoom axis. Here the cabled devices have the highest priority, with LCS port 1 having priority over LCS port 2.

13.5 Lens Data Display LDD-FP

The Lens Data Display for Focus Pullers LDD-FP can be used to display lens information. Connect it to the LDD port of the Plus module.

13.6 Plus Camera Controls

The ALEXA PLUS has an additional function button labeled WRS. It gives access to the WRS screen, from where all camera settings related to the Plus camera features can be handled.

The WRS screen gives an overview of radio status, camera level, LDS status, and CLM status. The screen buttons lead to screens containing more detailed info on these topics and where settings can be changed.



Figure 85: WRS screen

RADIO

Shows the currently set radio channel, the number of connected hand units and the status of the radio system. Pressing the screen button opens a screen where radio can be set on or off and the channel number can be set. When radio is switched on, a small icon appears in the camera homescreen.



Figure 86: WRS radio screen

CAM LEVEL

Shows the tilt and roll of the camera in degrees as measured by the camera's position sensor. This sensor can be reset if it appears to have an offset. Press the CAM LEVEL screen button to access the reset screen. By pressing the two lower outer screen buttons simultaneously, the sensor is reset.

Note: The sensor can only be reset while both axis are within a threshold of +/-10

degrees around 0.



Figure 87: Motion sensor reset screen

LENS DATA

Shows the type of LDS lens connected and the LDS status. The LENS DATA screen button leads to the LDS screen, where lens info like lens type, current focal length, iris, focus distance and close and far point of depth of field are shown.

The OPTIONS screen button opens the LDS options screen, where the LDS unit can be switched between imperial and metric, and the circle of confusion for correct calculation of depth of field can be set.

Note: After connecting a new LDS lens, turn all lens rings slowly until all lens axes have transmitted their current positions.



Figure 88: LDS info screen

LDA

When a non-LDS lens is connected, the user can achieve LDS functionality by using the Lens Data Archive. In the LDS screen, a button labelled LDA appears except when a LDS lens is connected.

The LDA consists of a user list and a main archive list. The user list should only contain the lenses currently used to achieve quick access to the desired lens tables. The main archive contains a set of lens tables for ARRI/Zeiss Highspeed, Master Primes and Ultra Primes and can be extended with additional lens tables for any PL-Mount lens.



Figure 89: User LDA

Note: Custom lens tables may have to be created manually beforehand.

Pressing the LDA button opens the User LDA. Select a lens table and press the wheel. After calibrating the lens motors, the LDS functionality can be used.

To add a lens table from the main archive, access the User LDA screen and press the ADD button. This opens the Main LDA list. From the main archive, first select a lens type, the a lens model and then a lens class. The lens class can be found on the lens barrell below the infinity symbol of the focus scale. Then select to add the lens table to the user list (Press ADD), use it without adding (USE), or both (ADD+USE).



Figure 90: Main LDA screen

To delete a lens table from the user archive, access the user list and press the DELETE button. Select the lens table to delete and press the two buttons labeled DELETE simultaneously. Repeat this procedure to delete further lens tables.

Custom lens tables can be added to the main archive via the SD card. Place the lens table on the SD card in a folder named "LDA". Insert the SD card into the camera. Go to the main archive list and press ADD. Select the desired lens table and press the wheel. The lens table will be located in the main archive as lens type "Custom".

To delete a custom lens table from the camera, go the main archive list and press DELETE. Select the lens table and press the two buttons labeled DELETE simultaneously. Repeat this procedure to delete further custom lens tables.

Lenses can also be equipped with the lens data mount LDM. The mount contains a chip with the lens table stored inside, so the lens transmits its data to the camera as soon as it is connected. For information on current ring positions, these lenses must be used in combination with controlled lens motors.

CLM screens

The screens for IRIS, FOCUS and ZOOM controlled lens motors all have the same layout. They show the motor type, motor direction and motor torque.

Note: For CLM-2 motors the torque value is greyed out as torque is only active for CLM-3 motors. It can nonetheless be changed in case a CLM-3 motor might be used but is currently not at hand.

In addition, a lens motor calibration can be triggered, either for all lens motors, or only for the one featured in the particular screen.

Note: When starting a motor calibration, make sure each motor's cog wheel is connected properly to the lens. Pay extra attention that no one is close to the motors or holding them. Catching a finger, cloth or anything else on the motor's cog wheel can cause sever body harm as well as damage to the system.

IRIS CLM



Figure 91: Iris CLM screen

Shows status, direction and torque of the CLM connected to the IRIS socket.

Press the IRIS CLM screen button to access the iris CLM screen. This screen shows the type of motor connected to the IRIS socket, its direction and torque. Direction and torque can be changed by the screen buttons below and above the value. The upper left screen button calibrates only the iris motor.

Pressing the lower left screen button starts calibration of all connected lens motors.

ZOOM CLM



Figure 92: Zoom CLM screen

Shows status, direction and torque of the CLM connected to the ZOOM socket.

Press the ZOOM CLM screen button to access the zoom CLM screen. This screen shows the type of motor connected to the ZOOM socket, its direction and torque. Direction and torque can be changed by the screen buttons below and above the value. The upper left screen button calibrates only the zoom motor.

Pressing the lower left screen button starts calibration of all connected lens motors.

FOCUS CLM



Figure 93: Focus CLM screen

Shows status, direction and torque of the CLM connected to the FOCUS socket.

Press the FOCUS CLM screen button to access the focus CLM screen. This screen shows the type of motor connected to the FOCUS socket, its direction and torque. Direction and torque can be changed by the screen buttons below and above the value. The upper left screen button calibrates only the focus motor.

Pressing the lower left screen button starts calibration of all connected lens motors.

3D Lens Sync

When two cameras are connected and their sensors are synced with via the EXT connectors, the slave camera will receive its motor commands from the master camera. Its radio module switches automatically off. Calibration of lens motors must happen individually for each camera.

14 ALEXA Plus 4:3

The ALEXA Plus 4:3 is identical to an ALEXA Plus except for its ALEV III sensor which has a 4:3 active area. This makes the camera the ideal companion camera to an ALEXA Studio.

Licenses

The ALEXA Plus 4:3 includes a bundle license, which enables DNxHD, High Speed recording and anamorphic desqueeze. The license is pre-installed on the camera and cannot be deleted.

Note: Do not downgrade the camera to a software version before SUP 6.1.

4:3 mode

The ALEXA Studio, ALEXA M and ALEXA Plus 4:3 cameras can be operated in 4:3 mode.

In 4:3 mode, the camera captures images from a vertically extended sensor area. The used area is 23.76 x 17.82mm in size, which translates to 2880 x 2160 sensor pixels.

Note: The sensors of regular ALEXA and ALEXA Plus cameras are not capable of creating a 4:3 image!

Loading 4:3 mode

Go to MENU>System>Sensor mode. The currently loaded mode is shown in the first line.

Press the wheel. To load the new mode, press the two lower screen buttons.

Note: Loading 4:3 or 16:9 mode results in all settings being set to factory reset values!

Frame rate

The maximum sensor frame rate in 4:3 mode is 48 fps.

Recording

SxS recording is switched off, as this is currently not possible.

External recording is only possible in ARRIRAW with external ARRIRAW recorders that support ARRIRAW 4:3.

Monitoring

For monitoring, the 4:3 image is downscaled to 958 x 720 pixels for the EVF and 1440 x 1080 for the MON OUT. Only horizontal surround view is available in 4:3 mode. The image is not rescaled for surround view, but horizontally extended. The non-active area of the EVF and MON OUT is filled with black ("pillarboxed").

Anamorphic desqueeze

Both 1.3x and 2x anamorphic desqueeze is available in 4:3 mode. 1.3x anamorphic desqueeze results in an image size of 1280 x 720 for the EVF and 1920 x 1080 for the MON OUT, while 2x desqueeze results in an image size of 1280 x 480 for the EVF and 1920 x 720 for the MON OUT.

4:3 and High Speed Mode

It is possible to switch from 4:3 to High Speed mode and vice versa. In High Speed mode, only the 16:9 center area of the image sensor is read out.

15 ALEXA Studio

15.1 General Description

The ALEXA Studio extends the features of an ALEXA Plus by:

- Optical viewfinder

  Brand-new construction from ARRI, featuring optical anamorphic desqueeze, diopter correction, image flip, camera left/right positioning and horizontal distance adjustment

- Electronic mirror shutter

  The electronic mirror shutter can be adjusted in a range of 11.2° to 180.0° degrees. When in use, it completely removes rolling shutter effects of the sensor.

- Built-in motorized ND filter

  The ND filter has a density of 1.3 and can be moved in and out of the optical path with the push of a button. It is located between the mirror shutter and the image sensor, so the optical viewfinder image is not affected by the filter and stays bright.

- 4:3 Super35 sensor size (only active in SUP 5.2 BETA)

  Allows output of 2880 x 2160 (23.76 x 17.82mm sensor size) sensor pixels in ARRIRAW for recording on external recorders, and monitoring of the full sensor aspect in HD (pillarboxed).

Note: Internal recording of 4:3 images will be enabled in a future software update.

Note: The ALEXA Studio does not support SUP 6.0! This means that DNxHD recording, Color bars and extended user button features are currently not supported by the ALEXA Studio.

15.2 ALEXA Studio Images

Figure 94: ALEXA Studio right

Figure 95: ALEXA Studio left

Figure 96: ALEXA Studio top

Figure 97: ALEXA Studio bottom

Figure 98: ALEXA Studio front

Figure 99: ALEXA Studio back

15.3 Optics

15.3.1 Electronic Mirror Shutter

The electronic mirror shutter is located between the PL-mount and the image sensor at an angle of about 45°. It is part of the optical reflex viewfinder system in that it reflects the lens image into the optical viewfinder.

It is synchronized with the electronic shutter of the camera sensor so that the sensor is only read out in the dark phase. This completely removes rolling shutter effects of the sensor readout.

Its 180° mirrored surface reflects the lens image into the optical viewfinder. The open sector of the mirror shutter can be reduced through an electronically controlled sector gate. The mirror shutter rotates 360° for every capured frame, controlling the exposure of the sensor through its open sector. The readout of the sensor happens while the mirror reflects the light of the optical path into the optical viewfinder.

The angle of the open sector is electronically controlled via the regular camera controls.

15.3.2 Lens Adapter PL Mount LA-PL-2 (with LDS)

The lens mount of the ALEXA Studio supports the ARRI Lens Data System. The LDS lens must be mounted in the 12 o'clock or 3 o'clock position to enable the LDS functions. Take great care not to harm any elements of the LDS contacts on either lens or camera when attaching or deattaching a lens or lens port cover.

Besides the LDS feature, the same rules as with the LA-PL-1 apply.

Figure 100: ALEXA Studio PL-Mount

Note: Due to the optical mirror shutter, the use of Angenieux Optimo Rouge lenses, any Super16 lenses, or lenses with dimensions not matching the dimensions in the figure "Allowed lens dimensions with mirror shutter" drawing cannot be used with the ALEXA Studio, as they would destroy the rotating mirror shutter!



Figure 101: Allowed lens dimensions with mirror shutter

15.3.3 Optical Viewfinder

The ALEXA Studio has an optical reflex viewfinder system with interchangeable ground glasses.

It offers an exceptional viewing quality favoured by a large optical design. Special care has been taken to avoid the unpleasant vignette effect that could occur by moving the eye.

Note: To use the optical viewfinder, the mirror shutter must be set to On.

The viewfinder is adjustable in two axes, laterally extendable for left eye operation and shows illuminated frame lines (ARRIGLOW).

The viewfinder image stays upright and correct left-to-right when the viewfinder is swivelled within the main axis.

Figure 102: OVF top view, with mounting points marked

Extending the viewfinder arm

- Loosen the straight-structured ring next to the FIX engraving counter-clockwise (contrary to the arrow).
- Adjust the horizontal position.
- Tighten the ring clockwise (with the arrow direction).

Adjust Barrel Friction

- Move the dot-structured ring according to the engravings LOOSE and FRICTION to loosen or tighten the friction of the OVF barrel.

Contrast Filter

To achieve a temporary subjective reduction of viewfinder contrast range, a contrast filter (density 0.6) can be pivoted into the optical beam path.

- Use the lever next to the level bubble to pivot the contrast filter into the optical path.
- Releasing the lever pivots the contrast filter back out of the optical path.

Ground glasses

The ground glass is the equivalent to the image sensor for the optical viewfinder. The image created by the lens is projected to the ground glass, from where it is picked up by the optical viewfinder.

Ground glasses contain frame and format markings to show the recorded image area and the area of interest. The sensor aperture of the ALEXA Studio is different from the camera aperture of ANSI and DIN Super35 formats. Therefore, Super35 ground glasses of the ARRICAM system do not provide exact frame markings in the ALEXA Studio viewfinder image. For exact framing, use only ground glasses made specifically for the ALEXA Studio.

To exchange a ground glass:

- Press the VIEW button so that the sensor is protected by the mirror shutter.
- Turn off the camera and disconnect it from power supply.
- Remove the lens or protective cap.
- Screw the ARRI Ground Glass Puller into the ground glass.
- Carefully pull out the ground glass.
- Check that the new ground glass and the ground glass holder are clean.
- Screw the ARRI Ground Glass Puller into the new ground glass and push it into the holder.
- Make sure the ground glass is inserted completely and correctly locked in place.
- Attach a lens or a protective cap to the lens mount.



Figure 103: Ground glass in camera with Ground Glass Puller attached

Figure 104: Ground glass with attached Ground Glass Puller

To remove the field lens, which is located above the ground glass:

- Remove the ground glass first
- Screw the ARRI Ground Glass Puller into the field lens
- Carefully pull out the field lens



Figure 105: Field lens in camera with attached Ground Glass Puller

Figure 106: Field lens with attached Ground Glass Puller

Note: Due to the risk of displacement caused by shock force, we recommend to remove both ground glass and field lens before transportation and shipping of the camera. Whenever removing the camera from its case, check that both ground glass and field lens are properly seated before switching on the camera to prevent any damage to the mirror shutter.

ARRIGLOW

The ARRIGLOW module is integrated in the optical viewfinder system of the ALEXA Studio. It allows illuminated format markings to be superimposed onto the viewfinder image with adjustable brightness.

- Press the buttons on the left side of the OVF below the DIMMER engravement to adjust the brightness of the ARRIGLOW. At its lowest brightness setting, the ARRIGLOW is switched off.
- The ARRIGLOW color is set in the camera menu under MENU>Monitoring>Frame lines> Frame lines color

Figure 107: ARRIGLOW buttons

Changing the ARRIGLOW mask

The ground glass used for the optical viewfinder should be combined with a matching glow mask. To change the glow mask:

- Loosen the 3mm allen screw next to the level bubble.
- Remove the level bubble element.
- Grab the glow mask with a Hirschmann clamp at the forceps hole and pull it out of the glow mask frame.
- Check that both the new glow mask and the glow mask frame are clean.
- Carefully push the new glow mask into the glow mask frame.
- Make sure the glow mask is inserted completely.

- Place the bubble element on top of the ARRIGLOW module and tighten the 3mm allen screw.
- Turn on the ARRIGLOW and check that ground glass and glow mask are correctly aligned.

Figure 108: Glow mask slot

Anamorphic Desqueeze

- Turn the wheel on top of the OVF ball element to swing the anamorphic desqueeze element into the optical path.
- *Note: By default, the anamorphic element is for 2x anamorphic lenses. It can be changed to an element for 1.3x anamorphic lenses.*

Image Flip

- Press the button next to the image flip symbol.
- Turn the knob next to the image flip symbol until the image is fully flipped.
- To undo the flip, rotate the knob until the button jumps out and the knob is locked again.

Diopter Adjustment

- *Note: Depends on the eyepiece in use. Description for default eye piece of ALEXA Studio.*
- Turn the eyepiece barrel until the ground glass is in focus.
- A neutral, unstructured, bright out-of-focus image content helps with this.

Attaching the optical viewfinder

Upon delivery, the OVF is not connected to the camera and must be installed by the user.

- Remove the protective cover from the OVF by loosening its 2x 3mm allen screws.
- Remove the blinding plate from the camera by loosening its 2x 3mm allen screws.
- Place the OVF on the camera.
- Take special care that the electronic connectors of camera and viewfinder are connected before pushing the OVF in place.
- Tighten the 3x 3mm allen screws of the OVF (See OVF top view image for locations of screws).

Note: The torx screws on the camera that are painted red may not be tightened or loosened, as this would corrupt the alignment of the OVF.

Figure 109: OVF with cover plate



Figure 110: Alexa Studio with cover plate

Swapping the optical viewfinder for an electronic viewfinder EVF-1

- Make sure the camera is powered down.
- Loosen the 3x 3mm hex screws of the OVF completely (See OVF top view image for locations of screws).
- Remove the optical viewfinder.
- Place the EVA-1 electronic viewfinder adapter plate where the optical viewfinder was.
- Tighten the 2x 3mm hex screws.
- Attach the EVF mounting bracket with the EVF-1 to the camera housing with its 2x 3mm allen screws.
- Connect the EVF cable to the camera.
- Power the camera.



Figure 111: Electronic viewfinder adapter EVA-1



Figure 112: ALEXA Studio with mounted EVF-1

15.3.4 ND Filter

The ALEXA Studio has a ND filter in front of the sensor, which can be moved in and out of the optical path. The motorized filter slider contains a ND filter with a density of 1.3, and a cover glass without additional density. The filter slider is sealed, so that no dirt or dust can enter the area between the slider and the sensor.

Note: Perform regular dust checks on the outside of the ND filter slider, as dust that might collect on top of it. As the slider is very close to the sensor, dust or dirt collecting on it might be visible as artifacts in images.

When performing a dust check, make sure the camera is switched off and disconnected from any power source to prevent the mirror shutter from activation during the cleaning process.

The ND filter can be activated in the EI screen by pushing the lower right screen button.



Figure 113: EI screen

If activated, the ASA rating in the Homescreen will have an ND index next to it.



Note: The use of the internal ND filter has no influence on the EI rating of the camera. When measuring exposure with a light meter, take into account the light loss of 4 1/3 stops generated by the ND filter.

15.4 Studio Camera Controls

Only a few additional controls are available on the ALEXA Studio. These are used to control the mirror shutter and the ND filter.

The Homescreen has icons for the active ND filter and the mirror shutter position and state.



Icon	Meaning
ND	ND filter is active
G	Mirror is on & parked in gate position (Grey icon if mirror shutter is switched off)
V	Mirror is on & parked in view position (Grey icon if mirror shutter is switched off)
M S	Mirror shutter is running

ND filter activation

- In the Homescreen, press EI.

- In the EI screen, press the lower right screen button labeled ND FILTER to move the ND filter in and out of the optical path.



Figure 114: EI screen

Mirror shutter activation

- In the Homescreen, press SHUTTER.
- In the Shutter screen, press the lower right screen button labeled MIRROR to activate or deactivate the mirror shutter.



Note: When mirror shutter is active, the shutter angle is limited to 180.0 degrees. Frame rates higher than 37 fps for 4:3 and higher than 46 fps for 16:9 reduce the shutter angle range further!

Note: For frame rates higher than 30 fps, it is recommended to use a power source with a voltage level of 18-35 V to ensure the mirror shutter is powered sufficiently!

MIRROR PARK buttons VIEW and GATE

The camera left side Operator Controls have two additional function buttons labelled VIEW and GATE. These buttons control the parking position of the mirror shutter.

A spinning mirror shutter can be stopped by pressing either of the two buttons. Pressing the VIEW button will park the mirror in the optical path, enabling a live preview in the optical viewfinder.

Pressing the GATE button will stop the mirror shutter out of the optical path, enabling a live preview on the EVF (if mounted), the MON OUT and the REC OUT. Each button is accompanied by a blue LED that lights when the mirror is parked in the respective position. When the mirror shutter is running, both of the LEDs will be active.

Pressing the GATE button while the mirror is parked in the VIEW position will move the mirror shutter by 180.0° degrees into the GATE position.

Pressing the VIEW button while the mirror is parked in the GATE position will move the mirror shutter by 180.0° degrees into the VIEW position.

To restart the mirror shutter, press the button of the position the mirror is parked in.

Note: After booting the camera, the mirror shutter is parked in the GATE position for safety reasons.

When stopping, the mirror shutter always open up the electronic sector gate to 180.0°, and closes down when it is restarted.

A live image on EVF, MON OUT and REC OUT is available when the mirror shutter is spinning or parked in the GATE position. A parked mirror shutter will automatically start spinning when recording is started.

When the mirror shutter is switched off, it is still possible to move the mirror shutter between the GATE and VIEW positions, but it is not possible to spin the shutter.

Note: For safety reasons, it is required to power down the camera before performing a "gate check". Do not check or clean the sensor cover glass while the camera is powerded up and the mirror is parked in the GATE position!

Frame rate and shutter angle with mirror shutter on

When the mirror shutter is switched on, the sensor frame rate is limited to 60 fps in 16:9 and 48 fps in 4:3 (*Note: 4:3 is only supported in SUP 5.2 BETA*).

Frame rates higher than 37 fps in 4:3 or 46 fps in 16:9 reduce the maximum possible mirror shutter angle. When the frame rate change reduces the allowed mirror shutter angle below the currently active shutter angle, the camera automatically sets the shutter angle to 135.0°. The technically possible maximum shutter angle depends on the frame rate. To achieve the maximum possible shutter angle:

- Press the SHUTTER button in the Homescreen to get to the Shutter list screen.
- Press the ADD button in the Shutter list screen to get to the Shutter angle screen.
- Press the MAX button in the Shutter Angle screen and confirm by pressing the jogwheel twice.
- The maximum possible shutter angle is now a part of the shutter list and can be set by pressing the jogwheel.

When the mirror shutter is on, the camera redirects the user to the Shutter list screen after setting the sensor frame rate, where the shutter angle can be adjusted as desired. To cancel this action, press the HOME button.

15.5 4:3 Mode

The ALEXA Studio, ALEXA M and ALEXA Plus 4:3 cameras can be operated in 4:3 mode.

In 4:3 mode, the camera captures images from a vertically extended sensor area. The used area is 23.76 x 17.82mm in size, which translates to 2880 x 2160 sensor pixels.

Note: The sensors of regular ALEXA and ALEXA Plus cameras are not capable of creating a 4:3 image!

Loading 4:3 mode

Go to MENU>System>Sensor mode. The currently loaded mode is shown in the first line.

Press the wheel. To load the new mode, press the two lower screen buttons.

Note: Loading 4:3 or 16:9 mode results in all settings being set to factory reset values!

Frame rate

The maximum sensor frame rate in 4:3 is 48 fps.

Recording

SxS recording is switched off, as this is currently not possible.

External recording is only possible in ARRIRAW withexternal ARRIRAW recorders that support ARRIRAW 4:3.

Monitoring

For monitoring, the 4:3 image is downscaled to 958 x 720 pixels for the EVF and 1440 x 1080 for the MON OUT. Only horizontal surround view is available in 4:3 mode. The image is not rescaled for surround view, but horizontally extended. The non-active area of the EVF and MON OUT is filled with black ("pillarboxed").

Anamorphic desqueeze

Both 1.3x and 2x anamorphic desqueeze is available in 4:3 mode. 1.3x anamorphic desqueeze results in an image size of 1280 x 720 for the EVF and 1920 x 1080 for the MON OUT, while 2x desqueeze results in an image size of 1280 x 480 for the EVF and 1920 x 720 for the MON OUT.

For the optical viewfinder, anamorphic desqueeze can be achieved by flipping an anamorphic element into the optical path. By default, the OVF has an optical element for 2x desqueeze. Elements for 1.3x desqueeze are also available.

4:3 and Highspeed Mode

It is possible to switch from 4:3 to High Speed mode and vice versa. In High Speed mode, only the 16:9 center area of the image sensor is read out.

15.6 Licensed Features

Licensed features DNxHD, High Speed mode and Anamorphic Desqueeze are automatically enabled in the ALEXA Studio.

16 ALEXA M

16.1 General Description

The ALEXA M is a specialty camera where the camera body is split into two parts. The camera head contains the image sensor, while the backend contains the image processing modules. Both parts are connected via a fibre interface.

The advantages of this system are:

- Better access to small spaces where a regular ALEXA would not fit into
- Lighter handheld operation.
- Lighter and smaller setups on 3D rigs
- Easy camera operability when the camera head cannot be accessed, e.g. a camera crane or a helicopter rig.

16.2 ALEXA M Images

REC

Figure 115: ALEXA M Backend left side

Figure 116: ALEXA M Backend right side

OPTICAL
LINK
ETH
AUDIO IN
TC
12 V
AUDIO OUT

SXS

16.3 ALEXA M Camera Head

The ALEXA M camera head contains the image sensor and parts of the image processing. Images are transmitted to the Backend via fibre cable. The fibre connection is bi-directional and returns the EVF image to the camera head from the Backend.

Due to the fibre connection, the ALEXA M has an increased power draw of approximately 120W. The head draws 40W of power. It can be powered from the backend with hybrid fibre cables of up to 30m length.

It can also be powered directly through its BAT connector.

16.3.1 CCH-2

The Camera Center Handle 2 CCH-2 is the handle for the ALEXA M camera head. It is mounted with 4x 3mm allen screws and can be attached either to the top or the bottom of the camera head.

Figure 117: CCH-2 mounted on ALEXA M camera head

Note: The CCH-2 only fits the ALEXA M camera head and not the ALEXA M backend or any other ALEXA camera.

16.4 ALEXA M Camera Backend

The ALEXA M camera backend contains the main controls, image processing, output and recording. It behaves like any regular ALEXA, only that it lacks the operator controls and is slightly longer.

16.5 Fibre Connection

Figure 118: SMPTE 311optical fibre connectors

The ALEXA M utilizes SMPTE 311 fibre connectors and cables. The camera head can be powered with hybrid fibre/power cables with a length of up to 30m, if the backend power supply can deliver 120 W in total. If this is not the case, the head should be powered separately through its BAT connector.

For regular fibre cable, a signal loss of up to 10 dB is acceptable. 1 km of fibre cable has a signal loss of 0.5 dB, while a fibre connector pair introduces a signal loss of 0.5-2 dB, depending on the amount of dirt on the optical contacts. Typically, a cable length of up to 1 km with 4 connection joints is still acceptable.

To connect the cable to the camera, make sure the cable direction is correct. Line up the red guides and push the cable connector onto the camera connector piece. A clicking sound indicates the connector has locked. Plug the rubber caps of the connectors into each other to protect their inside from dirt.

To disconnect the cable from the camera head, pull on the rubber end of the connector in the direction of the cable. To disconnect the cable from the backend, push the metal ring of the camera connector piece and pull on the cable connector in the opposite direction.

Connect the camera head to the backend via the optical link before powering the camera. Disconnecting the head from the backend during operation requires both parts to be powered down and reconnected before powering up the system again.

Figure 119: Correctly aligned fibre connectors

Cleaning of fibre connectors

Cleaning of the fibre connectors is an important task. Only use cleaning devices certified for SMPTE 311 connectors, like the “IBC M20” which is delivered with the camera package. Never use compressed air or any other uncertified cleaning method, as this could permanently damage or destroy the fibre connectors.

Both dry and wet cleaning tools are available, with the dry cleaners having proved to be more efficient for regular cleaning, while the wet cleaners are better with strong and sticky contaminations.

Regular cleaning of at least one time per day is recommended, as well as any time the signal quality deteriorates.

Fibre connection status

Next to the fibre connectors of the ALEXA M is a fibre status LED that reflects the signal strength.

A green LED reflects a good signal strength.

If the LED is alternately flashing between green and amber, the signal is weak, which can be caused by dirty connectors, faulty cables, or a bad connection. Power down the camera, clean the connectors, reconnect the cable to the camera and repower the camera in this particular order. If the problem does not go away, swap the cable.

An amber LED indicates a link error. The camera must be rebooted. If the link error reoccurs, follow the steps described for the green/amber flashing LED.

16.6 4:3 mode

The ALEXA Studio, ALEXA M and ALEXA Plus 4:3 cameras can be operated in 4:3 mode.

In 4:3 mode, the camera captures images from a vertically extended sensor area. The used area is 23.76 x 17.82mm in size, which translates to 2880 x 2160 sensor pixels.

Note: The sensors of regular ALEXA and ALEXA Plus cameras are not capable of creating a 4:3 image!

Loading 4:3 mode

Go to MENU>System>Sensor mode. The currently loaded mode is shown in the first line.

Press the wheel. To load the new mode, press the two lower screen buttons.

Note: Loading 4:3 or 16:9 mode results in all settings being set to factory reset values!

Frame rate

The maximum sensor frame rate in 4:3 is 48 fps.

Recording

SxS recording is switched off, as this is currently not possible.

External recording is only possible in ARRIRAW withexternal ARRIRAW recorders that support ARRIRAW 4:3.

Monitoring

For monitoring, the 4:3 image is downscaled to 958 x 720 pixels for the EVF and 1440 x 1080 for the MON OUT. Only horizontal surround view is available in 4:3 mode. The image is not rescaled for surround view, but horizontally extended. The non-active area of the EVF and MON OUT is filled with black ("pillarboxed").

Anamorphic desqueeze

Both 1.3x and 2x anamorphic desqueeze is available in 4:3 mode. 1.3x anamorphic desqueeze results in an image size of 1280 x 720 for the EVF and 1920 x 1080 for the MON OUT, while 2x desqueeze results in an image size of 1280 x 480 for the EVF and 1920 x 720 for the MON OUT.

4:3 and Highspeed Mode

It is possible to switch from 4:3 to High Speed mode and vice versa. In High Speed mode, only the 16:9 center area of the image sensor is read out.

16.7 Licensed Features

Licensed features SxS High Speed Recording and Anamorphic desqueeze are automatically enabled in the ALEXA M.

16.8 Lens Data System

The ALEXA M is equipped with a LA-PL-2 lens mount with LDS contacts. When using a LDS lens, such as Master Primes or LDS UltraPrimes, the camera reads, displays and records lens metadata.

The LDS screen can be accessed through the menu, which contains an additional item "LDS". This menu item is only available on the ALEXA M.

Note: Lens motors and the lens data archive LDA are not supported by the ALEXA M.

---

17 RCU-4

Figure 120: RCU-4 remote control unit

The camera can be remote controlled with an RCU-4. This device mirrors the controls on the camera's right side. It is connected to the camera's Ethernet port. Power is supplied via the Ethernet cable.

To power the RCU-4, press the power button after connecting the device to a camera.

During boot-up, the RCU-4 compares its firmware version with the camera firmware version. If it detects a difference, it will update itself to match the camera's firmware version. When the update is completed, the RCU-4 will shut down automatically.

The power button of the RCU-4 only affects the RCU-4. It is not possible to power or to shut down the camera with the RCU-4. When the camera is powered down, the RCU-4 shuts down automatically as it loses its power supply.

The LOCK button of the RCU-4 locks only the RCU-4. It does not affect the camera lock.

For more info, please refer to the RCU-4 user manual.

18 Index

1

12 V 42
12 V Accessories 26

2

24 V Accessories 26

4

4
  3 mode 166
  3 Mode 155

A

About This Manual 13
ALEXA Images 13
ALEXA M 157
ALEXA M Camera Backend 163
ALEXA M Camera Head 163
ALEXA M Images 158
ALEXA Plus 123
ALEXA Plus 4
  3 136
ALEXA Studio 138
ALEXA Studio Images 139
Appendix 173, 174
AUDIO 58
AUDIO IN 41
AUDIO OUT 42

B

BAT 40
BAT Connector 22
Bridge Plate adapter BPA-1 35
Bridge Plates BP-12/BP-13 34

C

Camera Controls 48
CCH-2 163
Center Camera Handle CCH-1 32
Cine-Style Batteries 22
COLOR 63
Condensation 20
Connector Pin Outs 179
Connectors 38

D

Dimensions, Weights and Menu Structure Trees 193
Disclaimer 7
Display 49
Display + Beeper 95

E

EI 61
Electromagnetic Interference 19
Electronic Mirror Shutter 142
Electronic Viewfinder 85
Electronic Viewfinder EVF-1 28
ETHERNET 41
EVF 41
EVF Controls 102
Explanation of Warning Signs and Indications 16
EXT 40
External recording 111
External Sync 93

F

False Color Display 184
False Color Index 90
Fan 96
Fibre Connection 164
Firmware 97
FPS 54
Frame grabs 99
Frame Lines 89, 114
Function Buttons 67

G

General Description 123, 138, 157
General Precautions 19
General Safety Instructions 16
Gold Mount Batteries 25

H

Hand Units 129
High Speed recording 113
HOMESCREEN 49

I

INFO 70
Infos and Warnings 185
Installation of The Camera 27
Internal recording 104
Introduction to ALEXA 10

L

Lens Adapter PL Mount LA-PL-1 (no LDS) 45
Lens Adapter PL Mount LA-PL-2 (with LDS) 142
Lens Adapter PL-Mount LA-PL-2 (with LDS) 125
Lens Data Display LDD-FP 130
Lens Data System 167
Lens Motors 127
Lens Support 46
Leveling Block LB-1 35
Licensed Features 98, 156, 167
Lists and User Lists 52

M

Main Controls 48
Mains Unit NG 12/26 R 22
Menu 79
Minimum Equipment Recommended For Operation 27
MON OUT 40, 87
Monitoring 85, 114

N

ND Filter 151

O

Onboard Batteries 23
Operation of The Camera 104
Operator controls 101
Optical Viewfinder 143
Optics 45, 124, 141

P

Parallel recording 113
PLAY 76
Plus Camera Controls 131
Power 23, 93
Power Management 21
Power Outputs 26
Power Supply 21
Production Info 91
Project 90

R

Radio System 126
RCU-4 168
REC OUT 82
REC OUT 1 + 2 40
Recording 79, 104
RET/SYNC IN 40
RS 41

S

Safety Instructions 16
Scope 9
Screen Buttons 49
SD card 96
SD Card 42
Sensor 92
Sensor modes 16
9 and 4
3 121

Shoulder Pad SP-3 36
SHUTTER 60
Side Camera Handle SCH-1 33
Specific Safety Instructions 17
Storage and Transport 19
Studio Camera Controls 152
SxS CARDS 80
SxS Slots 43
Syncing the Sensors of Two Cameras 93, 118
Syncing the Settings of Two Cameras 94, 119
System 92
System Time + Date 95

T

TC 42
TC (Time Code) 68
Test Signal 94
Tripod and Remote Heads 27

U

USER 73
USER BITS 70
User Setups 100
Using Time Code 117

V

Viewfinder Cables 29
Viewfinder CAM menu 103
Viewfinder EVF menu 102
Viewfinder Mounting Bracket 30
V-Lock Batteries 23

W

WB 65
Wedge Adapter WA-1 + Quick-Release Plate 35
Wireless Remote System 127
WNA-1 97

Appendix

In this appendix

Appendix	174
Connector Pin Outs	179
False Color Display	184
Infos and Warnings	185
Dimensions, Weights and Menu Structure Trees	193

A.1 Appendix

Image Sensor	
Type	ALEV III CMOS sensor
Sensor frame rates	0.750 - 60.000 fps 60.000 - 120.000 fps in High Speed mode
Shutter angle	5.0° - 358.0° 5.0° - 356.0° in High Speed mode
Total active pixels (incl. surround view)	3112 x 1782
Pixels of recorded image	2880 x 1620
Aperture of recorded image	23.76 x 13.365 mm
Image aperture (incl. surround view)	25.674 x 14.701 mm
Pixel pitch	8.25 µm
Aspect ratio	1.78:1 (16:9)
Filters	optical low pass, UV, IR
Color filters	RGB primary colors
Lens	
Lens mount	Exchangeable lens mount, with PL mount LA-PL-1 installed
Flange focal depth	52.00 mm nominal
Image processing	
White balance	2000 - 11000 Kelvin
CC Shift	-8 to +8 (translates to full magenta/ full green gel correction)
EI rating	160 - 3200 ASA
Recorded image resolution	1920 x 1080 pixels (downscaled from 2880 x 1620)
Viewfinder	
Type	ARRI EVF-1
Technology	LCOS imaging device
Resolution	1280 x 784 pixels
Power	
Power supply	DC 11 - 34V
Power management	Active ORing between BAT connector and onboard battery adapters
Power consumption	ca. 85W w/o accessories
Power outputs	2 x RS (24V), 1x 12V
Recording	

Recording media	Sony **SxS PRO** cards
Recording compression codec	Apple ProRes 422/4444 codec family Avid DNxHD (requires license key)
Frame rates	0.75 - 60 fps 60 - 120 fps in High Speed mode (no ProRes 4444)

Image Outputs

Recording output	2x REC OUT configurable as: 2x 422 1.5G SL YCbCr @ frame rates: 23.976, 24, 25, 29.97 and 30 fps or 1x 422 1.5G DL YCbCr @ frame rates: 48, 50, 59.94 and 60 fps or 2x 422 3G SL YCbCr @ frame rates: 48, 50, 59.94 and 60 fps or 1x 444 1.5G DL RGB @ frame rates: 23.976, 24, 25, 29.97 and 30 fps or 2x 444 3G DL RGB @ frame rates: 23.976, 24, 25, 29.97 and 30 fps or 1x 444 3G DL YCbCr @ frame rates: 48, 50, 59.94 and 60 fps or 1x ARRIRAW 1.5G DL @ frame rates: 23.976, 24, 25, 29.97 and 30 fps or 2x ARRIRAW 3G SL @ frame rates: 23.976, 24, 25, 29.97 and 30 fps or 1x ARRIRAW 3G DL @ frame rates: 48, 50, 59.94 and 60 fps
Monitoring outputs	EVF out: proprietary signal for EVF-1 with delay <1 frame 1x MON OUT: 1x 422 1.5G @ frame rates: 23.976, 24, 25, 29.97 and 30 fps

Timecode

Type	TC clock generator with crystal oscillator
TC input	LTC in
TC outputs	LTC out HD-SDI LTC/VITC out

Dimensions and weight

Length x Width x Height (body)	332 x 153 x 158 mm 12.95" x 6.02" x 6.22"
Camera body weight	6.26 kg / 13.79 lb
Camera setup weight (incl. EVF-1, VMB-1, CCH-1)	7.65 kg / 16.85 lb
Others	
SD card	most SD cards with FAT/FAT32 up to 4 GB
Sound level	under 20 dB(A) @ 24 fps and ambient temperature < 25° C / 77° F
Environmental	-20° C to +45° C @ 95% relative humidity max, non condensing
ALEXA Plus	
Length x Width x Height (body)	332 x 175 x 158 mm 12.95" x 6.89" x 6.22"
Camera body weight	8.0 kg / 17.6 lb
Camera setup weight (incl. EVF-1, VMB-1, CCH-1)	8.4 kg / 18.5 lb
Lens mount	Exchangeable lens mount, with PL mount LA-PL-2 installed
ALEXA Studio	
Length x Width x Height (body)	363 x 177 x 163 mm 14.29" x 6.97" x 6.41"
Camera body weight	7.0 kg / 15.4 lb
Camera setup weight (incl. SxS module, OVF, CCH-1)	10.2 kg / 22.5 lb
Lens mount	Exchangeable lens mount, with PL mount LA-PL-2 installed
Sensor frame rates	0.750 - 60.000 fps 60.000 - 120.000 fps in High Speed mode 0.75 - 48.000 fps in 4:3 mode
Viewfinder	Optical viewfinder
Mirror shutter	Electronic mirror shutter
Shutter angle	5.0° - 358.0° 5.0° - 356.0° in High Speed mode 11.2° - 180.0° (Mirror shutter on)
Aspect ratio	1.78:1 (16:9) 1.33:3 in 4:3 mode
Total active pixels (incl. surround view)	3112 x 1782 3112 x 2160 in 4:3 mode

Pixels of recorded image	2880 x 1620 2880 x 2160 in 4:3 mode
Aperture of recorded image	23.76 x 13.365 mm 23.76 x 17.82 mm in 4:3 mode
Image aperture (incl. surround view)	25.674 x 14.701 mm 25.674 x 17.82 mm in 4:3 mode

ALEXA M

Length x Width x Height (M head)	212 x 129 x 149 mm 8.35" x 5.08" x 5.87"
M head weight	2.9 kg / 6.39 lb
Length x Width x Height (M backend)	323 x 153 x 158 mm 12.72" x 6.02" x 6.22"
M backend weight	5.5 kg / 12 lb
Lens mount	Exchangeable lens mount, with PL mount LA-PL-2 installed
Sensor frame rates	0.750 - 60.000 fps 60.000 - 120.000 fps in High Speed mode 0.75 - 48.000 fps in 4:3 mode
Viewfinder	Electronic Viewfinder EVF-1
Shutter angle	5.0° - 358.0° 5.0° - 356.0° in High Speed mode
Aspect ratio	1.78:1 (16:9) 1.33:3 in 4:3 mode
Total active pixels (incl. surround view)	3112 x 1782 3112 x 2160 in 4:3 mode
Pixels of recorded image	2880 x 1620 2880 x 2160 in 4:3 mode
Aperture of recorded image	23.76 x 13.365 mm 23.76 x 17.82 mm in 4:3 mode
Image aperture (incl. surround view)	25.674 x 14.701 mm 25.674 x 17.82 mm in 4:3 mode

ALEXA Plus 4:3

Length x Width x Height (body)	332 x 175 x 158 mm 12.95" x 6.89" x 6.22"
Camera body weight	8.0 kg / 17.6 lb
Camera setup weight (incl. EVF-1, VMB-1, CCH-1)	8.4 kg / 18.5 lb
Lens mount	Exchangeable lens mount, with PL mount LA-PL-2 installed

Aspect ratio	1.78:1 (16:9) 1.33:3 in 4:3 mode
Total active pixels (incl. surround view)	3112 x 1782 3112 x 2160 in 4:3 mode
Pixels of recorded image	2880 x 1620 2880 x 2160 in 4:3 mode
Aperture of recorded image	23.76 x 13.365 mm 23.76 x 17.82 mm in 4:3 mode
Image aperture (incl. surround view)	25.674 x 14.701 mm 25.674 x 17.82 mm in 4:3 mode

A.2 Connector Pin Outs

Note: The drawings of the connectors are not to scale.

BAT



1 GND

2 +24V

3 BAT-COM

RS



1 GND

2 24V-AUX

3 R/S

12V



1 GND

2 12V-AUX

TC



1 GND

2 LTC IN

3 ASCII

4 TUNE OUT

5 LTC OUT

EXT



1	RS422-TXD(+)
2	RS232-TXD
3	CAN1-L
4	CAN1-H
5	CAN2-L
6	CAN2-H
7	24V-AUX
8	RS232-RXD
9	RS422-RXD(-)
10	RS422-RXD(+)
11	RS422-TXD(-)
12	GND
13	TTL-IN1
14	TTL-IN2
15	24V-AUX
16	GND

ETHERNET



1 MX-1P

2 MX-1N

3 MX-2P

4 MX-2N

5 MX-3P

6 MX-3N

7 MX-4P

8 MX-4N

9 GND

10 24V-ETH

AUDIO IN



1 AGND

2 L-IN(+)

3 L-IN(-)

4 R-IN(+)

5 R-IN(-)

AUDIO OUT



1 GND

2 R-OUT

3 L-OUT

A.3 False Color Display

The false color display is a tool to check correct exposure. It can be activated in the EVF and the MON OUT image. When active, the image is turned into a greyscale image with important luminance ranges shown in signal colors.

Color Encoding

Six different colors are used to show the important luminance ranges.

What	Signal Level	Color	
White clipping	100% - 99%	red	
Just below white clipping	99% - 97%	Yellow	
One stop over medium gray (Caucasian skin)	56% - 52%	pink	
18% medium gray	42% - 38%	green	
Just above black clipping	4.0% - 2.5%	blue	
Black clipping	2.5% - 0.0%	purple	

Figure 121: False Color Encoding

The following example illustrates the behavior of the false color display.

Figure 122: Night scene captured with ALEXA



Figure 123: ALEXA night shot with false color active

A.4 Infos and Warnings

If anything unwanted occurs in the camera, it will give a message to the user.

These states, that require attention from the user, are indicated by icons in the main display, the viewfinder and the MON OUT.

Warnings are message that inform the user that a state has changed or that an error might occur soon. Anyway, recording is still possible.

If the camera goes into error state, recording is no longer possible, as it cannot be guaranteed that images are acquired as the user intended, or recording is simply not possible.

The messages give a compact info what has happened. If more information is required, please refer to the following tables.

Special warnings and errors: Sensor temperature

ALEXA has a Peltier element that keeps the image sensor at a stable temperature. This is important to achieve constant image quality. Under some occasions, the camera might not be able to keep this temperature, or it might take some time to reach the correct level. This can be the case right after booting, or with very hot or cold ambient temperatures.

A red temperatrue icon indicates that the sensor temperature is too far off to guarantee a high image quality, while a white temperature icon indicates that image quality is still in the (very high set) quality limits required by ARRI.

The related messages in the INFO screen are shown in the following tables.

ALEXA status message

System state: Good	Camera works properly.

ALEXA warning messages and meanings

Warning message	Meaning
Main Bat: Power warning	The battery attached to the BAT connector has reached its warning level. Battery power is about to end, and a replacement battery should be prepared.
Onboard Bat: Power warning	The battery attached to the onboard battery adapter has reached its warning level. Battery power is about to end, and a replacement battery should be prepared.
Card 1: Low capacity	The **SxS PRO** card in slot 1 has less than 3 minutes recording time left. Prepare a new card for recording.
Card 2: Low capacity	The **SxS PRO** card in slot 2 has less than 3 minutes recording time left. Prepare a new card for recording.

Card 1: Rec protected	The **SxS PRO** card in slot 1 is Rec protected. Remove the card from the camera, slide the switch located on the camera back end to the Rec enable position and re-insert the card.
Card 2: Rec protected	The **SxS PRO** card in slot 2 is Rec protected. Remove the card from the camera, slide the switch located on the camera back end to the Rec enable position and re-insert the card.
Card 1: Full	**SxS PRO** card in slot 1 is selected, but the **SxS PRO** card is full. Use a new card. Card in other slot can still record.
Card 2: Full	**SxS PRO** card in slot 2 is selected, but the **SxS PRO** card is full. Use a new card. Card in other slot can still record.
Card 1: Wrong file system	The **SxS PRO** card in slot 1 is not formatted in the file system required by the camera. Format the card.
Card 2: Wrong file system	The **SxS PRO** card in slot 2 is not formatted in the file system required by the camera. Format the card.
Card 1: Card is too slow	The write speed of **SxS PRO** card in slot 1 is insufficient for the sensor fps set on the camera. Use a card with a higher write speed.
Card 2: Card is too slow	The write speed of **SxS PRO** card in slot 2 is insufficient for the sensor fps set on the camera. Use a card with a higher write speed.
Card 1: files damaged!	One or more files on **SxS PRO** card in slot 1. Continue with a fresh card.
Card 2: files damaged!	One or more files on in slot 2 are defect. Continue with a fresh card.
Card 1: invalid cardtype	The card in slot 1 is not an **SxS PRO** card.
Card 2: invalid cardtype	The card in slot 2 is not an **SxS PRO** card.
Card 1: write problem!	The camera has problems writing to the **SxS PRO** card in slot 1. Continue with a fresh card.
Card 2: write problem!	The camera has problems writing to the **SxS PRO** card in slot 2. Continue with a fresh card.
Camera overheating	The camera system's temperature is reaching a critical level. this can either be due to a blocked camera fan or ambient temperature exceeding the system's limits. Apply additional cooling or switch of the camera to prevent hardware damage.
Low sensor temperature	The sensor temperature is lower than it should be. High image quality is still guaranteed.
High sensor temperature	The sensor temperature is higher than it should be. High image quality is still guaranteed.

Ext TC: Different frame rate	The external TC signal's time base differs from the project fps of the camera. Syncing is still possible.
Re-jam Timecode soon	Accuracy of jammed Timecode can soon expire. Re-jam camera with external Timecode soon.
Re-jam Timecode now	Accuracy of jammed Timecode has expired. Re-jam camera with external Timecode.
TC source forced to internal	Sensor fps does not match Project fps. External Free Run TC cannot be used, camera has switched to Int Rec Run TC.
TC mode forced to Rec Run	Sensor fps does not match Project fps. External Free Run TC cannot be used, camera has switched to Int Rec Run TC.
Interface bit error	Reboot camera. If error continues to occur, contact ARRI service.
Internal processing problem	Reboot camera. If error continues to occur, contact ARRI service.
Internal battery error	The internal battery which powers the real-time clock must be replaced. Contact an ARRI service center near you.
System problem	Reboot the camera. If error continues to occur, contact ARRI service.
System problem (I2C bus error)	Problem on camera data bus. Reboot the camera. If error continues to occur, contact ARRI service.
External TC: Incompatible frame rate	The external TC signal's time base is not accepted by the camera.
HD outs not synced. Trigger now!	Appears on slave cam with Ext sync activated, but not using settings sync. Send trigger from Ext sync master camera to ensure the REC OUTs of both cameras are in sync.
Connect with Ethernet slave!	Camera is set to Settings sync: Enet master, but is not connected with slave camera via Ethernet
Connect with Ethernet master!	Camera is set to Settings sync: Enet slave, but is not connected with master camera via Ethernet
External TC: Jamming. Please wait!	Camera jams to external TC signal. Do not disconnect TC source from camera until warning disappears.
External TC: Signal missing!	Camera is set to Ext LTC regen, but external TC signal is missing.
External TC: Incompatible frame rate!	The external TC signal has a time base that does not match the project fps of the camera.
Framegrab: Grabbing image failed	A problem occured in the camera. The frame grab failed.

Framegrab: Storing image failed	A problem occured with the SD card. The frame grab failed.
Playback failed	The camera could not play back the internally recorded clips.
EVF smooth mode not possible	Smooth mode is set to "On", but either sensor fps is higher then 30.000, or shutter angle is higher than 180.0
Ext LTC: Forced to JAM sync!	Ext LTC had to be switched to Jam sync by camera system.
Playback failed!	A problem with playback occured. Camera had to abort playback.
Card removed! Playback failed!	Camera had to abort playback, as **SxS** card was removed.
Calibrate lens motors!	New lens motors are attached to the camera. Prior to use they must be calibrated.
Temperature at limit. Fan RPM raised.	With camera fan is in "Rec low" mode, fan noise might exceed silent level because camera is becoming too hot.
Master/slave: Focus unit mismatch	With ALEXA Plus and 3D lens sync, both cameras must have same focus unit activated, which is not the case here.
Slave: No lens table active.	With ALEXA Plus and 3D lens sync, select lens table on slave when using LDA.
REC OUT: Switch on Vari flag!	When **SxS** recording is off and sensor fps does not match REC OUT fps, switch on Vari flag to prohibit duplicate frames.
Tropical mode active	Reminder for active tropical mode
REC OUT: Switch on Vari flag!	Issued when SxS is switched on and sensor fps is bigger than project fps.
ND filter stuck.	ALEXA Studio only. ND filter slider has mechanical problems.
Mirror sector problem.	ALEXA Studio only. Mirror sector has mechanical problems.
Mirror cannot reach sync speed.	ALEXA Studio only. Mirror cannot reach speed due to technical problems.
Voltage too low for mirror!	ALEXA Studio only. Power supply voltage level insufficient to drive mirror shutter.
Mirror out of phase	ALEXA Studio only. Mirror shutter and sensor are out of phase, may result in exposure artifacts.

Some buttons are defect.	Camera button signals are failing. Reboot camera. If reappearing after reboot, contact service for button replacement. Mostly hardware problem.
SxS: Check last clip. Low data rate!	Data rate of last recorded clip is very low. Check for artifacts in replay. Can also occure when forgetting to remove lens cap during recording.
Loading highspeed mode	While High Speed Mode is loading, the camera functionality is limited. Wait until High Speed mode loading has finished.
LDS failure, restart camera.	The lens data system has failed. Restart the camera if LDS is used.
M head: Clean fibre connection	The fibre signal quality of the ALEXA M camera is insufficient and requires cleaning of the connections.
M head: Power warning	The power level on the ALEXA M camera head is insufficient. Use a power source with a power supply of at least 40 W.
M head: High temperature	The temperature of the camera head is too high. Apply additional cooling to prevent automatic shutdown.
M head: Low fan speed	The fan of the ALEXA M camera head cannot reach a sufficient cooling speed. Fan might have to be cleaned or replaced.

ALEXA error messages and meanings

Main Bat: Low power	The battery attached to the BAT connector has reached its low level (10% below warning level). Battery must be replaced.
Onboard Bat: Low power	The onboard battery has reached its low level (10% below warning level). Battery must be replaced.
All Bats: Low power	Batteries on both BAT connector and onboard battery(s) have to be replaced.
Card 1: End of lifetime	The **SxS PRO** card in slot 1 has reached the end of its life cycle and has become read-only. Use a new card.
Card 2: End of lifetime	The **SxS PRO** card in slot 2 has reached the end of its life cycle and has become read-only. Use a new card.

Card 1: Write speed error	The current write speed could not be handled by the **SxS PRO** card in slot 1
Card 2: Write speed error	The current write speed could not be handled by the **SxS PRO** card in slot 2
Cards 1&2: Full	Both **SxS PRO** cards are full. Use fresh cards.
Cards 1&2: End of lifetime	Both **SxS PRO** cards have reached the end of their life cycle and has become read-only. Use fresh cards.
Cards 1&2: Wrong file system	Both **SxS PRO** cards are not formatted in the file system required by the camera. Format the cards.
Cards 1&2: Rec protected	Both **SxS PRO** cards are rec-protected. Eject the cards, switch off the protection and re-insert the cards.
Camera overheating	The camera is getting too warm. Apply additional cooling or shut down to prevent hardware damage.
Low sensor temperature	Sensor temperature is out of range. Wait until error message disappears before continuing to shoot.
High sensor temperature	Sensor temperature is out of range. Wait until error message disappears before continuing to shoot.
System error	Reboot the camera.
Codec error - Reboot!	An error in the compression module has occured, and recording was aborted. Reboot the camera before you continue to record!
Sensor error. Reboot!	The image sensor has a problem. reboot the camera.
Sensor boot error!	The sensor has not booted. Reboot the camera.
Interface error. reboot.	An internal data interface has a problem. If rebooting does not solve the problem, contact the ARRI service.
Fan error. Contact service!	The fan module is not working properly. Either install an SFM-1, or contact the ARRI service.

Fatal system error! Reboot camera now!	Camera has to be rebooted. If this error continues to occur, a hardware problem might be the reason. Contact the ARRI service.
Sync clock out of range.	The sync signal clock does not match the camera setting. Make sure the settings match!
Syncing sensor. Please wait!	Slave camera syncs to master camera. Wait until message disappears before starting to record!
A slave is not ready	One of the slave cameras is not ready for recording.
Software error - reboot camera!	A part of the camera software has stopped functioning properly and requires a camera reboot.
SxS: Audio recording failed	Audio recording on **SxS** card failed.
REC OUT: Frame drops. Set frame rate!	Frame rate of REC OUT is smaller than sensor fps. Make sure REC OUT frame rate matches sensor fps.
SxS cards differ. Recording prohibited!	With dual recording active, the two **SxS PRO** cards must have identical file structure. Use two fresh **SxS PRO** cards and analyze the not matching ones.
REC OUT: Frame drops. Set FPS.	SxS is switched off, and sensor fps is higher than REC OUT fps. Increase REC OUT fps to at least the sensor fps value.
REC error. please reboot!	Error in the recording module. Reboot camera.
Mirror shutter not calibrated!	ALEXA Studio only. Mirror shutter must be calibrated by ARRI service.
Mirror shutter phase error!	ALEXA Studio only. Mirror shutter continuosly not in phase with sensor. If rebooting does not solve the problem, contact ARRI service.
Mirror shutter: Cannot reach sync speed	ALEXA Studio only. Mirror shutter continuosly not reaching sync speed. If rebooting does not solve the problem, contact ARRI service.
No M head detected - reboot camera!	ALEXA M was booted without head connected. Connect head and reboot camera.

Fibre Connection Error!	Fibre connection between ALEXA M head and backend could not be established or has terminated. Check and clean connection, then reboot.
M head: Low power!	The power level of the ALEXA M head is critical. Make sure power supply can deliver at least 40 W of power. Check if power warning levels are set correctly.
M head: Temperature high	The temperature of the ALEXA M head is too high. Apply additional cooling to prevent automatic shutdown.
M head: Fan error. Contact service!	The fan of the ALEXA M camera head is defect. If replacing the fan does not solve the problem, contact the camera service.

If any error that requires rebooting continues to occur regularly, contact the ARRI service.

A.5 Dimensions, Weights and Menu Structure Trees

Dimensional drawings including weights information are attached to the end of this document. A version with higher resolution can be downloaded from the ARRI website:

http://www.arri.com/camera/digital_cameras/downloads.

A Menu Structure Tree can also be found at the end of this document.



ALEXA	Length	Width	Height	Weight
Body, Camera Center Handle (CCH-1)	321 mm - 12.64"	153 mm - 6.02"	224 mm - 8.82"	6.5 kg - 14.33 lbs
Body, Camera Center Handle (CCH-1), Electronic Viewfinder EVF-1, Viewfinder Mounting Bracket (VMB-1)	384 mm - 15.12"	251 mm - 9.88"	" - "	7.5 kg - 16.53 lbs
Body, Camera Center Handle (CCH-1), Electronic Viewfinder EVF-1 extended, Viewfinder Mounting Bracket (VMB-1)	406 mm - 15.98"	319 mm - 12.56"	" - "	7.5 kg - 16.53 lbs

Camera Left



Camera Back




Camera Top
Image Plane
230 mm
9.05"
46.7 mm
1.84"
25.4 mm
1"
25.4 mm
1"
25.4 mm
1"
25.4 mm
1"
50.8 mm
2"
67 mm
2.64"
171 mm
6.73"
68 mm
2.68"
239 mm max.
9.41" max.
UNC 3/8"–16
(10 mm deep)
Optical Center
Camera Bottom
Image Plane
oval hole 7 mm (+0.022) wide and 8 mm long (4.5 mm deep)
UNC 3/8"–16 (10 mm deep)
73 mm
2.87"
80 mm
3.15"
12.5 mm
0.49"
2.5 mm
0.1"
27.5 mm
1.08"
120 mm
4.72"
198 mm
7.79"

Camera Top

Image Plane



Optical Center

Camera Top



ALEXA Plus

CAMERA DIMENSIONS – **Version 2012-03**

Technical Data are subject to change without notice.



ALEXA Plus	Length	Width	Height	Weight
Body, SxS Module	332 mm - 12.95"	175 mm - 6.89"	158 mm - 6.22"	7.0 kg - 15.4 lb
Body, SxS Module, Camera Center Handle (CCH-1), Optical Viewfinder OVF-1	384 mm - 15.12"	274 mm - 10.8"	224 mm - 8.82"	8.4 kg - 18.5 lb

ALEXA Plus

CAMERA DIMENSIONS – **Version 2012-03**

Technical Data are subject to change without notice.

Camera Left



Camera Back



ALEXA Plus

CAMERA DIMENSIONS – **Version 2012-03**

Technical Data are subject to change without notice.




Camera Top
Image Plane
M4 (4 mm deep)
Optical Center
Camera Top
332 mm
12.95"
175 mm
6.89"
67 mm
2.64"
54 mm
2.13"
40 mm
1.58"
43 mm
1.69"
35.5 mm
1.4"
26.5 mm
1.04"
12.8mm
0.5"
3 mm
0.12"
23 mm
0.91"
38.5mm
1.52"
55 mm
2.17"
88.8 mm
3.5"
180 mm
7.09"
183 mm
7.21"
230 mm
9.06"

ALEXA M

CAMERA DIMENSIONS – **Version 2012-03**

Technical Data are subject to change without notice.



ALEXA M	Length	Width	Height	Weight
ALEXA M Head	212 mm - 8.35″	129 mm - 5.08″	149 mm - 5.87″	2.9 kg - 6.39 lb
ALEXA M Backend	323 mm - 12.72″	153 mm - 6.02″	158 mm - 6.22″	5.5 kg - 12 lb


Head Top
Image Plane
16 mm
0.63"
33 mm
1.3"
36 mm
1.42"
56 mm
2.2"
M4 (4 mm deep)
UNC 3/8"–16 (10 mm deep)
43 mm
1.69"
40 mm
1.58"
25 mm
0.98"
M4 (4 mm deep)
53 mm
2.09"
13 mm
0.51"
Head Bottom
Image Plane
Optical Center

ALEXA M

CAMERA DIMENSIONS – **Version 2012-03**

Technical Data are subject to change without notice.

Head with Cage Right



Head with Cage Top



Head with HEAD-PLATE-2 Right



Head with HEAD-PLATE-2 Top



Head with Handle Right



Head with Handle Top



Head with Handle Right



Head with Handle Top



Backend Right



Backend Front



ALEXA M

CAMERA DIMENSIONS – **Version 2012-03**

Technical Data are subject to change without notice.

Backend Top



Backend Bottom



ALEXA Studio

CAMERA DIMENSIONS – **Version 2012-03**

Technical Data are subject to change without notice.





ALEXA Studio	Length	Width	Height	Weight
Body, SxS Module	364 mm - 14.33"	177 mm - 6.97"	163 mm - 6.42"	8.0 kg - 17.6 lb
Body, SxS Module, Camera Center Handle (CCH-1), Optical Viewfinder OVF-1	402 mm - 15.9"	268 mm - 10.55"	241 mm - 9.49"	10.2 kg - 22.5 lb

ALEXA Studio

CAMERA DIMENSIONS – **Version 2012-03**

Technical Data are subject to change without notice.

Camera Left



Camera Back




Camera Top
Image Plane
230 mm
9.05"
46.7 mm
1.84"
25.4 mm
1"
25.4 mm
1"
25.4 mm
1"
25.4 mm
1"
67 mm
2.64"
156 mm
6.14"
UNC 3/8"–16
(10 mm deep)
Camera Bottom
Image Plane
UNC 3/8"–16 (10 mm deep)
Optical Center
16 mm
0.63"
1 mm
0.04"
49 mm
1.93"
19 mm
0.75"
67 mm
2.64"
21 mm
0.83"
69 mm
2.72"

Camera Top

Image Plane



Camera Top



HOME

FPS

set sensor speed (0.75 fps-60fps /120fps*HS; 24fps)
add/delete value
HIGHSPEED/EXIT HS*HS (boot ALEXA to HS mode; 60-120fps)
SxS CODEC (MENU > RECORDING > SxS CARDS)
SxS INFO (INFO > SxS CARDS)
SDI FPS >>
REC OUT (23.976, 24, 25, 29.97, 30)
MON OUT (23.976, 24, 25, 29.97, 30)

Quick-option for choosing REC and MON fps

AUDIO

adjust CH1+/- (level +20/-10; unity)
adjust CH2+/- (level +20/-10; unity)

Change volume of channel 1 and 2 with jogwheel

AUDIO OUT
set AUDIO OUT
Phones Level (+/-)
OPTIONS
AUDIO OUT > OPTIONS >>
Left out (CH1, CH2, CH1+2, None)
Right out (CH1, CH2, CH1+2, None)
Audio OUT level (Manual, Unity max.)

OPTIONS
AUDIO IN > OPTIONS >>
Record (On/Off)
Channel 1/2 level (Manual/Unity)
Channel 1/2 source (L/R in)
Soundroll (=Tape) (edit name)

SHUTTER

set shutter angle (5.0°-358.0°; 172,8°)
in highspeed mode (5.0°-356.0°)*HS
add/delete value
see calculated exposure time
MIRROR*STUDIO (On/Off)

Enable Mirrorshutter on ALEXA Studio

EI

set exposure index (160ASA-3200ASA; 800ASA)
ND FILTER*STUDIO (On/Off)

BACK & JOGWHEEL

press BACK while turning the jogwheel to change the display brightness

continued on next page

HOME

COLOR

SET LOOK

choose/delete/load look from SD

set COLORPATH

EVF (LOOK ON/OFF FOR REC709, DCI P3)
MON OUT (LOOK ON/OFF FOR REC709, DCI P3)
SxS, REC OUT } (LOOK ON/OFF FOR REC709, DCI P3)

GAMMA

COLOR > GAMMA >>

SxS (REC709, DCI P3, LOGC)
REC OUT (REC709, DCI P3, LOGC, ARRIRAW)
MON OUT (REC709, DCI P3, LOGC)
EVF (REC709, LOGC)

LOG C film matrix (On/Off)

WB

set WHITEBALANCE (2000K-11000K, Auto WB; 5600K; and CC SHIFT)

add/rename/delete value

MENU

RECORDING menu

SxS Cards >>

SxS Recording (Off/ProRes/DNxHD*DNxHD)
Codec (ProRes 422 Proxy/422 LT/422/422 HQ/4444)
(DNxHD 115/120/145 or DNxHD 175x/185x/220x)
HS Codec (ProRes 422 Proxy/422 LT/422/422 HQ)
(DNxHD 115/120/145 or DNxHD 175x/185x/220x)
Dual Recording (On/Off)
Quick format SxS CARD 1
Quick format SxS CARD 2
Erase SxS CARD 1
Erase SxS CARD 2

REC OUT >>

Framerate (23.976/24/25/29.97/30/48/50/59.94/60fps)
HD-SDI format (422 1.5G SL/422 1.5G DL/422 3G SL
444 1.5 DL/444 3G SL/444 3G DL
ARRIRAW 1.5G DL/ARRIRAW 3G SL
ARRIRAW 3G DL)
Scan format (psf/p)
Output range (Legal/Extended/Raw)
REC OUT fps sets sensor fps (On/Off)
SDI remote (On/Off)
Vari flag (On/Off)

continued on next page

MENU

MONITORING menu

Electronic viewfinder >>
- Brightness (1-5)
- Rotate image (On/Off)
- Smooth mode (On/Off)
- Surround view (On/Off)
- Frame lines + status info >>
  - Frame lines (On/Off)
  - Surround mask (Black line/Color line/Mask 25%/50%/75%)
  - Center mark (Off/Dot/Cross)
  - Status info (On/Off)
  - Electronic level (On/Off)
  - LDS info (On/Off)
- Peaking (Off/On) >>
  - Peaking (On/Off)
  - Peaking level (Low/Off)
- Anamorphic desqueeze*ANAMORPH (Off/1.3x/2.0x/2.0xmag)
- Zoom position (Centered/Eye level)

MON OUT >>
- Framerate (23.976/24/25/29.97/30/48/50/59.94/60fps)
- Scanformat (psf/p)
- Surround view (On/Off)
- Frame lines + status info >>
  - Frame lines (On/Off)
  - Surround mask (Black line/Color line/Mask 25%/50%/75%)
  - Center mark (Off/Dot/Cross)
  - Status info (On/Off)
  - Electronic level (On/Off)
  - LDS info (On/Off)
  - Show reel + clip number (On/Off)
  - Camera index letter (On/Off)
- Peaking (Off/On) >>
  - Peaking (On/Off)
  - Peaking level (Low/Off)
- False Color (On/Off)
- Anamorphic desqueeze*ANAMORPH (Off/1.3x/2.0x/2.0xmag)

Frame lines >>
- Frame line 1 (choose/add/delete; Off)
- Frame line 2 (choose/add/delete; Off)
- User rectangles >>
  - User rectangles (Off/Rect 1/Rect 2/Rect 1+2)
  - Set rect 1/2 >>
    - Top, Bottom, Left, Right (0-1000), Reset
- Color (Red/Green/Blue/Yellow/Black/White)
- Intensity (1-4)

RET IN path (EVF, MON OUT, EVF+MON)
Electronic level sensitivity (1x, 2x, 4x, 8x, 16x)
False color index >>

continued on next page

MENU

PROJECT menu

Project frame rate (23.976/24/25/29.97/30fps)
Camera index (A-Z)
Next reel count (001-999)
Production info >>
- Director
- Cinematographer
- Location
- Production
- User info 1
- User info 2

SYSTEM menu

Sensor >>
- Sensor mode (16:9/4:3*STUDIO/M/PLUS 4:3)
- Sensor temperature (Standard/Tropical)
- Mirror image horizontal (On/Off)

Power >>
- BAT1 (Plug) warning (10.0-30.0V; 21.0V)
- BAT2 (Onboard) warning (10.0-30.0V; 12.0V)

External sync >>
- Eye index (R/L)
- Sensor sync (Off/EXT master/EXT slave)
- HD out phase (+/-30 clocks; 0 clocks)
- Send HD sync trigger >
- Settings sync (Off/ETH master/slave)

Test signal >>
- Color bar (On/Off)
- Enable test tone (On/Off)
- Test tone level (0 dB(fs)/-9 dB(fs)/-18 dB(fs))

Display + beeper >>
- Display button brightness (1-8)
- Button brightness (Off/Low/Medium/High)
- Run beeper mode (Off/Start/Stop/Start+Stop)

System time + date >>
- set date, time, timezone and daylight saving time

Fan >>
- Fan mode (Regular/Rec low)

SD card >>
- Format + prepare SD card
- Prepare SD card

WNA-1 >>
- WNA state *(shows WNA-1 status)*
- WiFi power (On/Off)
- Mode (Ad Hoc/Access Point Client)
- SSID (set SSID name)
- Password (set Password)
- IP Address (adjust IP address)
- Subnet (adjust subnet mask address)
- Frequency band (2.4 GHz/5 GHz)
- Channel selection (Auto/Manual)
- Channel >> (select channel in manual mode)
- Authentication (Open/Shared Secret/PSK/LEAP/PEAP/MSCHAP V2)
- Encryption (None/WEP 64/WEP 128/TKIP/AES CCMP)

continued on next page

MENU

Encryption (None/WEP 64/WEP 128/TKIP/AES CCMP)

Firmware >>

Select update file >>

Licensed features >>

install/delete licenses; save hardware info

LDS *M

see Lens Data for PLUS/STUDIO on the following pages

FRAME GRABS menu

File format (Jpeg/Tiff/Dpx/Ari)

Compare grab to live image >>

load grab

Options Compare Options >>

Compare mode (Toggle/Interleave)

Active on EVF (On/Off)

Active on MON OUT (On/Off)

Grabbed images inherit REC OUT settings!

Ari only possible, when REC OUT = ARRI RAW

USER SETUPS menu

Save current setup

Load setup

Factory reset

USER

USER BUTTON ASSIGNMENT

set Button 1, 2, 3

- None
- MON OUT surround
- MON OUT gamma
- MON OUT frame lines
- MON OUT status info
- MON OUT false color
- MON OUT peaking
- MON anam. desqu.*ANAMORPH
- Frame lines color
- EVF surround
- EVF gamma
- EVF frame lines
- EVF status info
- EVF zoom
- EVF false color
- EVF peaking
- EVF anam. desqu.*ANAMORPH
- Grab still frame
- Return in active
- Toggle SxS
- Check last clip
- Circle clip
- Auto WB
- ND filter active*STUDIO

set Button 4, 5

- None
- MON OUT surround
- MON OUT gamma
- MON OUT frame lines
- MON OUT status info
- MON OUT false color
- MON OUT peaking
- Return in active
- Frame lines color
- Toggle SxS
- Format Card1
- Format Card2
- False color index
- View position*STUDIO
- Gate position*STUDIO

***ANAMORPH** = requires Anamorphic Desqueeze License ***DNxHD** = requires DNxHD License ***HS** = requires High Speed License
***PLUS** = ALEXA PLUS only ***PLUS 4:3** = ALEXA PLUS 4:3 only ***STUDIO** = ALEXA STUDIO only ***M** = ALEXA M only

PLAY

SxS PLAYBACK screen

start Playback of last clip *(press wheel or PLAY 2x on operator's side)*
CLIPLIST
OPTIONS
PLAY Options >>
Clip end action (Stop/Pause/Loop)
Show frame lines (On/Off)
Status info on MON OUT (On/Off)
STEPSIZE (1 frame/1 second)
CIRCLE CLIP

INFO

SYSTEM INFORMATION screen

LIVE INFO
SAVE TO SD
VERSION
SxS CARDS
SYSTEM
FPS INFO

GRAB

FRAME GRAB TRIGGER

save Framegrab to SD Card

TC

TIMECODE screen

SET TC (SET TO TIME/RESET/MANUAL)
OPTIONS
Timecode Options >>
Source (Int TC/Ext LTC)
Mode (Rec run/Free Run)
Generator (Regen/Jam Sync)
User bit source (Internal/LTC in UB)
USERBITS (set Userbits)
PROJECT (Menu > Project)

LOCK

BUTTON LOCK

locks HOMESCREEN, MENU, PLAY, INFO, GRAB and TC;
also locks the buttons on EVF and WRS*PLUS & STUDIO!

***ANAMORPH** = requires Anamorphic Desqueeze License ***DNxHD** = requires DNxHD License ***HS** = requires High Speed License
***PLUS** = ALEXA PLUS only ***PLUS 4:3** = ALEXA PLUS 4:3 only ***STUDIO** = ALEXA STUDIO only ***M** = ALEXA M only

WRS* PLUS & STUDIO

RADIO

STATUS
Channel: 0
Units: 0
Ready/Off

WRS > RADIO >>
WRS radio power (On/Off)
WRS radio channel (0-7)

CAM LEVEL

STATUS READOUT FROM SENSORS
Tilt: 0.0°
Roll: 0.0°

CAM LEVEL > CALIBRATE
use to reset your null balance

LENS DATA

LDS READOUT
Status

LENS DATA
displays FOCAL LENGTH, IRIS, FOCUS and DoF close/far

LDS OPTIONS
Lens distance unit (Metric, Imperial, Default Unit)
Circle of confusion (0.013/0.025/0.035/0.050mm)
Inverse iris scale (On/Off)
Inverse zoom scale (On/Off)
Inverse focus scale (On/Off)

LDA *available when non-LDS lens in use*
manage lens data for non-LDS lenses

IRIS/ZOOM/FOCUS CLM

CLM STATUS
displays TYPE, DIRECTION and TORQUE(1-4; only CLM-3)

IRIS/ZOOM/FOCUS CLM
set DIRECTION
set TORQUE (only CLM-3)
CALIBRATE/CALIBRATE ALL motors

ELECTRONIC VIEWFINDER **EVF-1**

ZOOM

magnify EVF image 2.25x (toggle mode)

EXP

false color exposure check (toggle mode)

continued on next page

***ANAMORPH** = requires Anamorphic Desqueeze License ***DNxHD** = requires DNxHD License ***HS** = requires High Speed License
***PLUS** = ALEXA PLUS only ***PLUS 4:3** = ALEXA PLUS 4:3 only ***STUDIO** = ALEXA STUDIO only ***M** = ALEXA M only

ELECTRONIC VIEWFINDER **EVF-1**

CAM

FPS

set sensor speed (0.75 fps - 60fps /120fps*HS; 24fps)

SHUTTER

set shutter angle (5.0°-358.0°; 172,8°;
in High Speed Mode 5.0°-356.0°)*HS

EI

set exposure index (160ASA - 3200ASA; 800ASA)

WB

set white balance (2000K - 11000K, Auto WB; 5600K;
and CC SHIFT)

EVF

EVF menu

Brightness (0-5)
Rotate Image (On/Off)
Smooth Mode (On/Off)
Surround View (On/Off)
Surround Mask (Black line/Color Line/Mask 25%/50%/75%)
Status Info (On/Off)
Frame Lines (On/Off)
Select Frame Lines 1 (choose from list)
Select Frame Lines 2 (choose from list)
Center Mark (Off/Dot/Cross)
User Rectangles (Off/Rect 1/Rect 2/Rect 1&2)
Edit User Rectangles (only when User Rectangles active)
Frame Lines Color (Red/Green/Blue/Yellow/Black/White)
Frame Lines Intensity (1-4)

MIRROR CONTROL*STUDIO

VIEW

switch to VIEW-mode (Operator sees an image)
press VEW + GATE for spinning mirror

GATE

switch to GATE-mode (sensor & all video outs "see" an image)
press GATE + VIEW spinning mirror

***ANAMORPH** = requires Anamorphic Desqueeze License ***DNxHD** = requires DNxHD License ***HS** = requires High Speed License
***PLUS** = ALEXA PLUS only ***PLUS 4:3** = ALEXA PLUS 4:3 only ***STUDIO** = ALEXA STUDIO only ***M** = ALEXA M only